



CUP22-0010/Stella Battery Storage Exhibit A: Location/Vicinity Map




24-0734 B 1 of 10




CUP22-0010/Stella Battery Storage Exhibit B: Assessor's Parcel Map



CUP22-0010/Stella Battery Storage Exhibit C: General Plan Land Use Map




CUP22-0010/Stella Battery Storage Exhibit D: Zoning Map



HAAR JIM & SHERI 5698 EASTWOOD LANE POLLOCK PINES MOBILE HOME PK & CA LLC POLLOCK PINES, CALIFORNIA 95726 2933 FOREBAY ROAD APN: 009660006 POLLOCK PINES, CALIFORNIA 95726 APN: 009330060 APPROXIMATE BOUNDARY LINE--WOOD POWER POLE - APPROXIMATE ADJACENT LOT LINE APPROXIMATE BOUNDARY LINE -~ · — GRAVEL —— ──GRAVEL ──✓ PARCEL B **BASIS OF BEARINGS:** 49 PM 131 PARCEL A 49 PM 131 N/F BADNVLLC 6565 PONY EXPRESS TRAIL WOOD POWER POLE -POLLOCK PINES, CALIFORNIA 95726 WITH UNGERGROUND APN: 009330052 POWER POLE AGAHI TOORAJ TR & ADOREA CELÉSTE TR 6505 PONY EXPRESS TRAIL POLLOCK PINES, CALIFORNIA 95726 APN: 009330063 - ASPHALTIC CONCRETE LINK FENCE (N) &
(S), 7' CHAIN LINK
FENCE (W) 5' CL FENCE END

® BUILDING CORNER DATED: 09-26-2008 **ZONING:** INDUSTRIAL SOIL TYPE: **ZONING**: INDUSTRIAL AREA OF DISTURBANCE: 14240.0 SF CUP22-0010/Stella Battery Storage Exhibit F: Grading Plan PONY EXPRESS TRAIL



VICINITY MAP

SHEET INDEX:

EXISTING CONDITIONS GRADING AND DRAINAGE PLAN CONSTRUCTION BMP PLAN EROSION AND SEDIMENT CONTROL DETAILS

THE BASIS OF BEARING FOR THIS SURVEY IS ASSUMED

BENCHMARK:

THE ELEVATION FOR THIS SURVEY IS ASSUMED

UTILITY NOTE:


THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING DRAWINGS. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.

NOTICE TO CONTRACTOR - ORDER OF WORK:

PRIOR TO THE START OF ANY CIVIL WORK, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL EXISTING UTILITIES BY POTHOLING SHALL CONTACT CWE IMMEDIATELY AND PROVIDE THE ACTUAL LOCATION INFORMATION. RFE ENGINEERING WILL VERIFY IF THERE ARE ANY CONFLICTS WITH THE IMPROVEMENTS AND WILL PROVIDE MODIFICATIONS TO THE DESIGN TO MITIGATE THE CONFLICTS IF ANY CONFLICTS EXIST.


FLOOD PLAIN:

SUBJECT PROPERTY IS LOCATED WITHIN ZONE "X", AREAS WITHIN ZONE "X" ARE DETERMINED TO BE OUTSIDE THE 0.2 ANNUAL CHANCE FLOOD PLAIN AS DETERMINED BY THE NATIONAL FLOOD INSURANCE PROGRAM, FLOOD INSURANCE RATE MAP COMMUNITY PANEL NO.: 06017C0550E





Know what's **below**. Call before you dig. or (800) 227-2600







STELLA BATTERY STORAGE EL DORADO COUNTY, CA APN: 009-330-064-000

of **4**

04/10/2023 24-0734 B 6 of 10





EROSION AND SEDIMENT CONTROL NOTES:

- 1. THE CONTRACTOR SHALL FOLLOW ALL JURISDICTIONAL GUIDELINES FOR GRADING AND THE EROSION AND SEDIMENT CONTROL MEASURES SHOWN OR STATED ON THESE PLANS.
- 2. CONTRACTOR MUST ENSURE THAT THE CONSTRUCTION SITE IS PREPARED PRIOR TO THE ONSET OF ANY STORM.
 CONTRACTOR SHALL HAVE ALL EROSION AND SEDIMENT CONTROL MEASURES IN PLACE FOR THE WINTER MONTHS PRIOR
 TO OCTOBER 1
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED UNTIL DISTURBED AREAS ARE STABILIZED.
 CHANGES TO THIS EROSION AND SEDIMENT CONTROL PLAN SHALL BE MADE TO MEET FIELD CONDITIONS ONLY WITH THE APPROVAL OF OR AT THE DIRECTION OF A REPRESENTATIVE OF THE DEPARTMENT OF UTILITIES.
- 4. THIS PLAN MAY NOT COVER ALL THE SITUATIONS THAT ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS MAY BE MADE TO THE PLAN IN THE FIELD SUBJECT TO THE APPROVAL OF OR AT THE DIRECTION OF A REPRESENTATIVE OF THE DEPARTMENT OF UTILITIES.
- 5. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED BEFORE AND AFTER ALL STORMS TO ENSURE MEASURES ARE FUNCTIONING PROPERLY.
- 6. CONTRACTOR SHALL MAINTAIN A LOG AT THE SITE OF ALL INSPECTIONS OR MAINTENANCE OF BMPS, AS WELL AS, ANY CORRECTIVE CHANGES TO THE BMPS OR EROSION AND SEDIMENT CONTROL PLAN.
- IN AREAS WHERE SOIL WILL BE EXPOSED LONGER THAN 14 DAYS, CONTRACTOR SHALL STABILIZE EXPOSED SOILS WITH HYDROSEEDING OR OTHER EQUIVALENT METHOD. CONTRACTOR SHALL ENSURE NO AREAS WILL BE LEFT EXPOSED OVER THE WINTER SEASON.
- 8. THE CONTRACTOR SHALL INSTALL THE STABILIZED CONSTRUCTION ENTRANCE PRIOR TO COMMENCEMENT OF GRADING. LOCATION OF THE ENTRANCE MAY BE ADJUSTED BY THE CONTRACTOR TO FACILITATE GRADING OPERATIONS. ALL CONSTRUCTION TRAFFIC ENTERING THE PAVED ROAD MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCE. THE STABILIZED CONSTRUCTION ENTRANCE SHALL REMAIN IN PLACE UNTIL THE ROAD BASE ROCK COURSE IS COMPLETED.
- 9. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE SWEPT AT THE END OF EACH WORKING DAY OR AS NECESSARY.
- 10. CONTRACTOR SHALL PLACE GRAVEL BAG BARRIERS AROUND ALL NEW DRAINAGE STRUCTURE OPENINGS IMMEDIATELY AFTER THE STRUCTURE OPENING IS CONSTRUCTED. THESE GRAVEL BAG BARRIERS SHALL BE MAINTAINED AND REMAIN IN PLACE UNTIL CONSTRUCTION IS COMPLETED.
- 11. SOIL STOCKPILE SHALL BE SURROUNDED BY STRAW WATTLE. CONTRACTOR SHALL COVER STOCKPILE WHEN NOT IN USE.

- 12. CONTRACTOR SHALL IMPLEMENT HOUSEKEEPING PRACTICES AS FOLLOWS:

 A. SOLID WASTE MANAGEMENT:
 - PROVIDE DESIGNATED WASTE COLLECTION AREAS AND CONTAINERS. ARRANGE FOR REGULAR REMOVAL AND DISPOSAL. CLEAR SITE OF TRASH INCLUDING ORGANIC DEBRIS, PACKAGING MATERIALS, SCRAP OR SURPLUS BUILDING MATERIALS AND DOMESTIC WASTE DAILY.
 - B. MATERIAL DELIVERY AND STORAGE:
 PROVIDE A DESIGNATED MATERIAL STORAGE AREA WITH SECONDARY CONTAINMENT SUCH AS BERMING. STORE
 MATERIAL ON PALLETS AND PROVIDE COVERING FOR SOLUBLE MATERIALS. RELOCATE STORAGE AREA INTO
 BUILDING SHELL WHEN POSSIBLE. INSPECT AREA WEEKLY.
 - C. CONCRETE WASTE:
 PROVIDE A DESIGNATED AREA FOR A TEMPORARY PIT TO BE USED FOR CONCRETE TRUCK WASH-OUT. DISPOSE OF
 HARDENED CONCRETE OFFSITE. AT NO TIME SHALL A CONCRETE TRUCK DUMP ITS WASTE AND CLEAN ITS TRUCK
 INTO THE CITY STORM DRAINS VIA CURB AND GUTTER. INSPECT DAILY TO CONTROL RUNOFF, AND WEEKLY FOR
 REMOVAL OF HARDENED CONCRETE.
 - D. PAINT AND PAINTING SUPPLIES:
 PROVIDE INSTRUCTION TO EMPLOYEES AND SUBCONTRACTORS REGARDING REDUCTION OF POLLUTANTS
 INCLUDING MATERIAL STORAGE, USE, AND CLEAN UP. INSPECT SITE WEEKLY FOR EVIDENCE OF IMPROPER
 DISPOSAL
 - DISPOSAL.

 E. VEHICLE FUELING, MAINTENANCE AND CLEANING:
 PROVIDE A DESIGNATED FUELING AREA WITH SECONDARY CONTAINMENT SUCH AS BERMING. DO NOT ALLOW
 MOBILE FUELING OF EQUIPMENT. PROVIDE EQUIPMENT WITH DRIP PANS. RESTRICT ON-SITE MAINTENANCE AND
 - F. HAZARDOUS WASTE MANAGEMENT:
 PREVENT THE DISCHARGE OF POLLUTANTS FROM HAZARDOUS WASTES TO THE DRAINAGE SYSTEM THROUGH
 PROPER MATERIAL USE, WASTE DISPOSAL AND TRAINING OF EMPLOYEES. HAZARDOUS WASTE PRODUCTS
 COMMONLY FOUND ON-SITE INCLUDE BUT ARE NOT LIMITED TO PAINTS & SOLVENTS, PETROLEUM PRODUCTS,
 FERTILIZERS, HERBICIDES & PESTICIDES, SOIL STABILIZATION STABILIZATION PRODUCTS, ASPHALT PRODUCTS AND
 CONCRETE CURING PRODUCTS.
- 13. THE FOLLOWING SOIL WIND EROSION CONTROL (DUST CONTROL) METHODS ARE PROPOSED AS PART OF THESE
 - MPROVEMENT PLANS:
 A. WATER THE SOIL OF THE SITE AND THE ADJACENT STREETS BEING USED IN CONNECTION WITH SOIL DISTURBANCE
 - OPERATIONS ON THE SITE AND THE ADJACENT STREETS BEING USED IN CONNECTION WITH SOIL DISTURB.
 - B. COVER EXPOSED SOIL WITH GRAVEL OR ROCK LANDSCAPING.

CLEANING OF EQUIPMENT TO A MINIMUM. INSPECT AREA WEEKLY.

- C. COVER EXPOSED SOIL WITH ORGANIC MULCHES, SPRINKLER IRRIGATED.
 D. IRRIGATE GRASSES.
- E. MAINTAIN LANDSCAPE VEGETATION.

EROSION AND SEDIMENT CONTROL MEASURES													
PHASE OF CONSTRUCTION	(WET SEASON)				(WET AND DRY SEASON)								
	HYDRO- SEEDING	STRAW MULCHING & TACKIFIER	PRESERVATION OF EXISTING VEGETATION	SOIL BINDERS	FIBER ROLLS	OUTLET PROTECTION	STORM DRAIN INLET PROTECTION	DEWATERING	STABILIZED CONSTRUCTION ENTRANCE	MATERIAL & WASTE DISPOSAL LOCATION	CONCRETE WASHOUT	DUST CONTROL	SEDIMENT TRAP
PRE-GRADING			•		•		•		•	•		•	•
CUT AND FILL QUANTITIES	•	•		•				•				•	•
UNDERGROUND WORK												•	
STORM DRAIN IMPROVEMENTS						•					•	•	
CURB & GUTTER							•					•	
STREET IMPROVEMENTS					•							•	
POST CONSTRUCTION	•	•	•										

CUP22-0010/Stella Battery Storage Exhibit F: Grading Plan

