

## **Enoven Truck Body + Equipment**

Quote #: 86054

2904 Duluth St West Sacramento, CA 95691 916-372-9692

Date: 4/25/2025

CustID: 32021

Thank you for the opportunity to quote your business, please call if you have any questions.

County of El Dorado Procurement & Contracts 360 Fairlane Court Placerville, CA 95667 County of El Dorado 2441 Headington Road Placerville, CA 95667

**Attn: Nathan Haynes** 

530-642-4900

nathan.haynes@edcgov.us

Qty>=	Description	Unit Price	Ext Price
2	Parts: Snow Plow, Henke 43R11J, PLP, SSTE, POLY	\$33,405.00	\$66,810.00
	PRICING PROVIDED PER WAUSAU-ALAMO GROUP SOURCEWELL CONTRACT 062222-AGI		
	<ul> <li>- 11' Long X 43" High "J" style Poly Moldboard</li> <li>- Dual A Arm Parallel Lift with central pivot point, single lift cylinder with mechanical float lockout pin, and two reversing cylinders</li> <li>- Dual stabilizer bars with (3) layback positions</li> <li>- Square Spring Trip Edge</li> <li>- Dual parking stands</li> <li>- 1/2" X 8" high carbon cutting edge</li> <li>- Rubber shield</li> <li>- Rod markers</li> <li>- Plow framework painted BLACK; Poly moldboard is BLUE</li> </ul>		
	***FREIGHT INCLUDED TO PLACERVILLE, CA***		
2	Parts: Spreader, 14', Henke HXC-2000, Pintle Chain  PRICING PROVIDED PER WAUSAU-ALAMO GROUP SOURCEWELL CONTRACT 062222-AGI	\$59,739.00	\$119,478.00
	- Capacity: 9.76 cuyds - 304 SSTL construction - 14'L X 82"W X 60"H - 10ga ends, sides, and ribs are continuously welded on the inside - Hopper top edge is a 2" formed channel to increase stiffness - Sides, front, and rear are sloped at 45°, 10°, and 18° respectively - Front spill shield - Inverted "V", SSTL - 7ga longsills with 7ga bolt-in replaceable conveyor floor - 24" wide conveyor chain cartridge with 3/8" X 1.5" cross bars - (2) adjustable internal baffles and (4) external spread control baffles		

- (3) adjustable spinner deflectors (front deflector is fixed) are easily adjustable and

 Qty>=
 Description
 Unit Price
 Ext Price

 removable without tools<br/>- Top mounted hydraulic motor

- All hydraulic motors are mounted directly to

their work piece to reduce maintenance

- 20" Urethane Spinner Disk
- Standard Duty Top Grates, Painted Black
- Remote Grease System
- Heavy duty storage legs, painted A36 mild steel, with trunnion bar locks
- Remote grease system
- SSTL light bar housing at top rear of hopper with (2) LED S/T/T, (2) LED Amber strobe, (2) LED B/U, and LED Clearance and ID lamps
- \*\*\*FREIGHT INCLUDED TO PLACERVILLE, CA\*\*\*

## 2 **OPTION: Pre-Wet**

\$7,400.00 \$14,800.00

\*\*\*MUST BE ADDED TO SPREADER AT TIME OF ORDER AND INSTALLED AT HENKE FACTORY\*\*\*

- Twin 200gal poly pre-wet tanks (400 gallons in total)
- Fill port, drainage port and ball valves; pre-plumbed
- Unpainted stainless steel mounting brackets
- Curbside mounted 10 GPM hydraulic pre-wet pump with flow meter and M12 connection
- Spinner chute mounted pre-wet spray bar with (2) two brass fan nozzles and quick disconnect

Sales Tax (7.25%)

\$14,578.88 \$14,578.88

TOTAL \$215,666.88

This Quote is good for 30 days. Acceptance of this Quote is confirmed and accepted by issuance of a Purchase Order, signing and returning this Quote, and/or delivery of a truck chassis to Enoven. This quotation was made expressly upon your request and is confidential and non transferable. If provided, estimated delivery dates are estimates only; actual delivery dates depend on a variety of factors that may/may not be within the direct control of Enoven. FUEL SERVICE CHARGE - IF A TRUCK IS DELIVERED WITH LESS THAN 1/4 TANK OF DIESEL/GASOLINE OR LESS THAN 1,500PSI CNG, A \$100.00 FUEL SERVICE CHARGE WILL BE ADDED TO THE FINAL INVOICE. For complete Terms and Conditions please go to www.enoven.com.

Terms of Sale	T	er	m	S	of	Sa	le:
---------------	---	----	---	---	----	----	-----

**Enoven Truck Body + Equipment** 

Net10

Authorized by: senochian

Date: 4/25/2025

Printed: 4/25/2025 4:35:55 PM