



## EL DORADO COUNTY STANDARD PLANS

### **MARKUP COPY - for reference purposes only**

This markup copy documents changes made to these draft standard plans during the period between August 8, 2010 and February 14, 2011.

### **Legend**

Comments presented in a **Red Border** represent corrections or modifications made to the Standard Plans over the period between the November 18, 2010 Planning Commission Meeting and the February 14, 2011 Board of Supervisor's Meeting.

Comments presented in a **Blue Border** represent changes made at the request of the EDAC Technical Subcommittee or to correct errors prior to the November 18, 2010 Planning Commission Meeting.

**ADOPTED MONTH, DAY, YEAR**

*DRAFT*

NOTES:

Design Practice:

Design of Streets and Highways shall be performed under the direction of a professional Civil Engineer, licensed in accordance with the California Business and Professions Code. Use of these standards or referenced documents are not a substitute for sound professional engineering design.

Reference Documents

The County of El Dorado requires the design of streets and highways in accordance with the following reference documents:

1. County of El Dorado Standard Plans
2. A Policy on Geometric Design of Highways and Streets – American Association of State Highway and Transportation Officials
3. Caltrans Highway Design Manual, and Design Memorandums
4. Guidelines for Geometric Design of Very Low-Volume Local Roads (ADT <= 400) American Association of State Highway and Transportation Officials
5. California Manual of Uniform Traffic Control Devices (California MUTCD)
6. Highway Capacity Manual – Special Report No. 209 – Transportation Research Board
7. AASHTO Roadside Design Guide
8. Caltrans Standard Specifications and Standard Special Provisions

The most current adopted version of these documents should be consulted when performing design of Streets and Highways.

The county engineer may approve deviations or modifications to the application of the standard plans in accordance with the Department of Transportation design exception policy.

Applicability

RD Series Standard Plans shall be used for the design of Local Roads and Collectors carrying less than 4000 ADT.

The Department of Transportation should be consulted for design standards required for General Plan Roadways and Collectors carrying more than 4000 ADT.

STD.  
PLAN  
RD-01

GENERAL DESIGN  
REQUIREMENTS



EL DORADO COUNTY  
DEPARTMENT OF TRANSPORTATION  
DESIGN STANDARDS

APPROVED BY: \_\_\_\_\_  
 JAMES W. WARE, P.E. NO. C61036  
 DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION  
 DATE: \_\_\_\_\_  
 BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**NOTES:**

Horizontal Alignment

Design speed of the highway shall be controlled by the horizontal alignment whenever feasible.

Whenever possible, reversing curves shall be connected by a tangent with a minimum length of 100'. In no case shall tangents between reversing curves be less than required for superelevation runout or runoff.

Maximum angle point without a horizontal curve is 30 minutes.

The minimum radii of horizontal curves is determined by the formula

$R_{min} = V^2 / 15 (e+f)$  where:  
 $R_{min}$  = minimum design curve radius in feet  
 $V$  = design speed in miles per hour  
 $e$  = superelevation rate in feet per foot  
 $f$  = design friction factor.

Design friction factors (f) are presented in the following table:

DESIGN SPEED (MPH)	FRICION FACTOR (f)
20	0.27
25	0.23
30	0.20
35	0.18
40	0.16
45	0.15
50	0.14

In a normal crown section, superelevation (e) value is -0.02.

Where practical and feasible, curve radii in excess of the minimum required values should be used.

Superelevation

Superelevation for Local Streets is discouraged.

Superelevation for collector streets and highways with ADT's below 2500 may be designed in accordance with Method 2 of Reference Document 3 (Page 148, Design for Low-Speed Urban Streets)

For new construction, a standard superelevation rate of Normal Crown, 2%, 4% or 6% should be selected.

At intersections on local streets within Community Regions, or intersections where high truck volumes are anticipated, the maximum superelevation rate is 4%.

STD.  
PLAN  
RD-02

HORIZONTAL ALIGNMENT  
AND SUPERELEVATION  
REQUIREMENTS



EL DORADO COUNTY  
DEPARTMENT OF TRANSPORTATION  
DESIGN STANDARDS

APPROVED BY:

DATE:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

BOARD OF SUPERVISOR'S RESOLUTION NO.

**NOTES:**

- The vertical profiles shall be designed to exceed the design speed of the horizontal alignment whenever feasible.
- Maximum Grade Break
  - Local Roads - 2%
  - Collectors - 0.5%
- Vertical Curves

Vertical curves shall be designed based on the formula  $L = K \times A$ , where L is the required length of vertical curve, K is the distance required to achieve a 1% change in grade, and A is the algebraic grade difference between the incoming and outgoing profile tangents.

Design K values shall be selected from the following table based on design speed:

DESIGN SPEED (MPH)	STOPPING SIGHT DISTANCE (Ft)	MINIMUM K VALUE for CREST VERTICAL CURVES (Ft/%)	MINIMUM K VALUE for SAG VERTICAL CURVES (Ft/%)
20	115	7	17
25	155	12	26
30	200	19	37
35	250	29	49
40	305	44	64
45	360	61	79
50	425	84	96

Selected from Exhibit 5-2. Design Controls for Stopping Sight Distance and for Crest and Sag Vertical Curves (A Policy on Geometric Design of Highways and Streets, AASHTO, 2004)

For small changes in grade where sight distance is not infringed by the vertical curve, a minimum length vertical curve of 100' is suggested.

**STD. PLAN**  
RD-03

**GRADE BREAKS AND VERTICAL CURVATURE REQUIREMENTS**



**EL DORADO COUNTY**  
**DEPARTMENT OF TRANSPORTATION**  
**DESIGN STANDARDS**





APPROVED BY:

DATE:

JAMES W. WARE, P.E., NO. CE1036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

BOARD OF SUPERVISOR'S RESOLUTION NO.

Simplified presentation of note references prior to 10/28/10 P/C Mtg.



\* ADDITIONAL RIGHT-OF-WAY MAY BE REQUIRED WHEN ROAD COINCIDES WITH A DESIGNATED ROUTE FOR AN ADDITIONAL PUBLIC FACILITY (I.E. PEDESTRIAN, BICYCLE, OR EQUESTRIAN TRAIL)

\*\* DIMENSIONS FOR CURBED MEDIAN ALTERNATIVE

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



SIX-LANE  
DIVIDED ROAD

**STD.  
PLAN**

RS-01

SHT 1 OF 2

NOTES:

1. THE STANDARD SECTION SHALL BE USED EXCEPT AS NOTED BELOW. THE CURBED MEDIAN ALTERNATE MAY BE ACCEPTABLE UNDER ANY OF THE FOLLOWING CONDITIONS AND SUBJECT TO APPROVAL OF THE COUNTY.
  - A. WHEN IT FILLS A GAP ON A STRETCH OF ROADWAY ALREADY BUILT WITH CURBED MEDIAN.
  - B. WHEN IT IS A SHORT SECTION NEAR INTERSECTION FOR DELINEATION AND/OR PLACING TRAFFIC CONTROL DEVICES.
  - C. WHEN NECESSARY TO CONTROL TURN MOVEMENTS AND ACCESS ON HEAVILY TRAVELED ROADS WITH MULTIPLE DRIVEWAYS.
  - D. WHEN IT IS TO BE LANDSCAPED
2. IF THE CURBED MEDIAN ALTERNATIVE IS USED, THE FOLLOWING APPLIES:
  - A. SEE STANDARD PLAN RS-45 FOR MEDIAN DETAILS.
  - B. SEE STANDARD PLAN MC-20 FOR TYPE A1-8 CURB.
  - C. THE MEDIAN SHALL BE PAVED WITH 2" HMA AND APPROVED SOIL STERILANT UNLESS LANDSCAPING OR OTHER SURFACING IS APPROVED BY THE COUNTY.
  - D. LANDSCAPED MEDIANS SHALL NOT BE MAINTAINED WITH ROAD FUNDS; AN APPROVED METHOD OF FUNDING MAINTENANCE SHALL BE ESTABLISHED PRIOR TO APPROVAL OF STREET IMPROVEMENT PLANS.
3. 6' MEDIAN WIDTH IS MINIMUM FOR A DIVIDED ROADWAY. ADDITIONAL WIDTH IS REQUIRED FOR TWO-WAY LEFT-TURN LANES (TWLTL) AND AT INTERSECTIONS WHERE LEFT-TURN POCKETS ARE NECESSARY.
4. SEE STANDARD PLAN MC-20 FOR CURBS (A2-6, A1-8).
5. SEE STANDARD PLAN MC-01 FOR SIDEWALK DETAILS. SIDEWALK LOCATION MAY VARY. MAINTAIN MIN. 6" CLEARANCE FROM R/W LINE.
6. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL, UNLESS A GEOTECHNICAL ENGINEER DETERMINES THAT A STEEPER SLOPE WILL BE SAFE FOR THE INTENDED USE AND WILL NOT BE SUSCEPTIBLE TO EROSION. SLOPES CONSTRUCTED FOUR HORIZONTAL TO ONE VERTICAL OR FLATTER DO NOT REQUIRE SLOPE EASEMENTS.
7. MAXIMUM STREET GRADES WITHOUT APPROVED DESIGN EXCEPTION:
 

BELOW 3000' ELEVATION:

GENERAL PLAN ROADWAYS AND COLLECTOR ROADWAYS WHERE ADT >10,000 = 8%  
 COLLECTOR ROADWAYS WHERE ADT >4000 AND <10,000 = 10%  
 LOCAL ROADWAYS AND COLLECTOR ROADWAYS WHERE ADT <4000 = 12%

ABOVE 3000' ELEVATION:

10% ALL ROADWAYS
8. MINIMUM STREET FLOW LINE GRADES SHALL BE 0.5% REVERSE GRADE, VERTICAL CURVES EXCEPTED.
9. ROADS IN RURAL REGIONS, RURAL CENTERS, AND THE CAMINO/POLLOCK PINES COMMUNITY REGION ARE NOT REQUIRED TO HAVE PCC CURB, GUTTER AND SIDEWALK. SHOULDERS SHALL BE PAVED TO THE WIDTH SHOWN (6'). ALTERNATE DITCH SECTIONS MAY BE APPROVED OR REQUIRED.
10. STRUCTURAL SECTION SHALL BE BASED ON "R" VALUE AND "T.I.". DESIGN TO BE SUBMITTED TO DOT FOR REVIEW AND APPROVAL.
11. HOT MIX ASPHALT (HMA) SHALL BE TYPE A, 1/2"; AGGREGATE BASE (AB) SHALL BE CLASS 2, 3/4"
12. THE TOP 6" OF SUBGRADE AND ALL BASE AND SUBBASE SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
13. SUBGRADE ENHANCEMENT GEOTEXTILE SHOULD BE CONSIDERED FOR NATIVE SOIL R-VALUES LESS THAN 20.
14. FOUNDATION SLOPES STEEPER THAN FIVE HORIZONTAL TO ONE VERTICAL ARE TO BE KEYED WHEN PLACING EMBANKMENT FILL. KEYS PER GRADING REQUIREMENTS.
15. SLOPE & DRAINAGE EASEMENTS (S&DE) SHALL EXTEND 5' MIN. BEYOND HINGE POINTS, TOE OF SLOPES, AND DRAINAGE STRUCTURES. SEE STANDARD PLAN RS-11 FOR ADDITIONAL SLOPE DETAILS.

Added per EDAC request prior to 10/28/10 P/C Mtg.

Added reference to forthcoming standard plan prior to 10/28/10 P/C Mtg.


STD. PLAN RS-01 SHT 2 OF 2

SIX-LANE DIVIDED ROAD




EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION DESIGN STANDARDS


APPROVED BY: JAMES W. WARE, P.E. NO. C61036 DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION BOARD OF SUPERVISOR'S RESOLUTION NO. DATE:




**STANDARD SECTION**



**CURBED MEDIAN ALTERNATE**



**OPEN MEDIAN ALTERNATE**



**TWO LANES**  
(PHASED CONSTRUCTION-INITIAL PHASE)

**NOTES:**

1. ULTIMATE BRIDGE TYPICAL SECTIONS TO BE APPROVED BY THE COUNTY.
2. BRIDGE TYPE TO BE APPROVED BY THE COUNTY.
3. MEDIAN WIDTH SUBJECT TO VARIATION DEPENDING ON INTERSECTION PROXIMITY.
4. CURBED MEDIAN OR OPEN MEDIAN ALTERNATE TO BE USED ONLY WHEN APPROACHING ROAD ALSO HAS A RAISED MEDIAN.
5. WHERE BIKE LANE IS ADJACENT TO TYPE 25 BARRIER, USE CALTRANS BRIDGE STANDARD DETAIL SHEET XS16-500e, "TUBULAR BICYCLE RAILING".
6. WIDTH OF BRIDGE STRUCTURE SHALL BE CONSISTENT WITH APPROVED ROADWAY UNLESS OTHERWISE APPROVED BY COUNTY.
7. ALTERNATE DESIGNS ALLOWED/REQUIRED WHERE FUTURE MEDIAN IS PLANNED.

- \* RAISED SIDEWALK TO BE PROVIDED WHEN WARRANTED
- \*\* SEE CALTRANS STANDARD PLANS
- \*\*\* TYPE 7 CHAIN LINK FENCE RAILING REQUIRED IN LIEU OF TUBULAR HAND RAILING WHEN STRUCTURE SPANS OVER A PUBLIC ROADWAY

**APPROVED BY:**

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_



**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



**SIX-LANE**  
DIVIDED ROAD  
BRIDGE SECTIONS



**STD.**  
**PLAN**  
RS-02

Simplified presentation of note references prior to 10/28/10 P/C Mtg.



\* ADDITIONAL RIGHT-OF-WAY MAY BE REQUIRED WHEN ROAD COINCIDES WITH A DESIGNATED ROUTE FOR AN ADDITIONAL PUBLIC FACILITY (I.E. PEDESTRIAN, BICYCLE, OR EQUESTRIAN TRAIL)


\*\* DIMENSIONS FOR CURBED MEDIAN ALTERNATIVE



Sheet 2 of this Standard Plan was omitted from prior P/C and Board packets in error. Sheet 2 of this Standard Plan is functionally identical to Sheet 2, Standard Plan RS-01 and has been added to the current set.

APPROVED BY:  
 JAMES W. WARE, P.E. NO. C61036  
 DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION  
 DATE: \_\_\_\_\_  
 BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
 DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**







**FOUR-LANE DIVIDED ROAD**

**STD. PLAN**  
 RS-03  
 SHT 1 OF 2



**NOTES:**

1. ULTIMATE BRIDGE TYPICAL SECTIONS TO BE APPROVED BY THE COUNTY.
2. BRIDGE TYPE TO BE APPROVED BY THE COUNTY.
3. MEDIAN WIDTH SUBJECT TO VARIATION DEPENDING ON INTERSECTION PROXIMITY.
4. CURBED MEDIAN OR OPEN MEDIAN ALTERNATE TO BE USED ONLY WHEN APPROACHING ROAD ALSO HAS A RAISED MEDIAN.
5. WHERE BIKE LANE IS ADJACENT TO TYPE 25 BARRIER, USE CALTRANS BRIDGE STANDARD DETAIL SHEET XS16-500e, "TUBULAR BICYCLE RAILING"
6. WIDTH OF BRIDGE STRUCTURE SHALL BE CONSISTENT WITH APPROVED ROADWAY UNLESS OTHERWISE APPROVED BY COUNTY.
7. ALTERNATE DESIGNS ALLOWED/REQUIRED WHERE FUTURE MEDIAN IS PLANNED.



- \* RAISED SIDEWALK TO BE PROVIDED WHEN WARRANTED
- \*\* SEE CALTRANS STANDARD PLANS
- \*\*\* TYPE 7 CHAIN LINK FENCE RAILING REQUIRED IN LIEU OF TUBULAR HAND RAILING WHEN STRUCTURE SPANS OVER A PUBLIC ROADWAY

**NOT TO SCALE**

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_



**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



**FOUR-LANE**  
DIVIDED ROAD  
BRIDGE SECTIONS


**STD. PLAN**  
RS-04

Simplified presentation of note references prior to 10/28/10 P/C Mtg.



**STANDARD SECTION IN EMBANKMENT**

- RURAL FILL SECTION -  
SEE NOTE 7



**STANDARD SECTION IN EXCAVATION**

- RURAL CUT SECTION -  
SEE NOTE 7

\* ADDITIONAL RIGHT-OF-WAY MAY BE REQUIRED WHEN ROAD COINCIDES WITH A DESIGNATED ROUTE FOR AN ADDITIONAL PUBLIC FACILITY (I.E. PEDESTRIAN, BICYCLE, OR EQUESTRIAN TRAIL)

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



FOUR-LANE  
UNDIVIDED ROAD

**STD.  
PLAN**

RS-05


SHT 1 OF 2



**NOTES:**

1. PROVIDE FOR A TWELVE (12') FOOT LEFT TURN POCKET WITHIN 400' OF ANY INTERSECTION WITH A GENERAL PLAN DESIGNATED ROAD OR HIGH-VOLUME (GREATER THAN 400 PEAK HOUR) LOCAL ROAD, UNLESS OTHERWISE APPROVED BY THE COUNTY.
2. SEE STANDARD PLAN MC-20 FOR CURBS (A2-6, A1-8).
3. SEE STANDARD PLAN MC-01 FOR SIDEWALK DETAILS. SIDEWALK LOCATIONS MAY VARY. MAINTAIN 6" MIN. CLEARANCE FROM R/W LINE.
4. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL, UNLESS A GEOTECHNICAL ENGINEER DETERMINES THAT A STEEPER SLOPE WILL BE SAFE FOR THE INTENDED USE AND WILL NOT BE SUSCEPTIBLE TO EROSION. SLOPES CONSTRUCTED FOUR HORIZONTAL TO ONE VERTICAL OR FLATTER DO NOT REQUIRE SLOPE EASEMENTS.
5. MAXIMUM STREET GRADES WITHOUT APPROVED DESIGN EXCEPTION:
  - BELOW 3000' ELEVATION:
  - GENERAL PLAN ROADWAYS AND COLLECTOR ROADWAYS WHERE ADT >10,000 = 8%
  - COLLECTOR ROADWAYS WHERE ADT >4000 AND <10,000 = 10%
  - LOCAL ROADWAYS AND COLLECTOR ROADWAYS WHERE ADT <4000 = 12%
  - ABOVE 3000' ELEVATION:
  - 10% ALL ROADWAYS
6. MINIMUM STREET FLOW LINE GRADES SHALL BE 0.5%. REVERSE GRADE VERTICAL CURVES EXCEPTED.
7. ROADS IN RURAL REGIONS, RURAL CENTERS, AND THE CAMINO/POLLOCK PINES COMMUNITY REGION ARE NOT REQUIRED TO HAVE PCC CURB, GUTTER AND SIDEWALK. SHOULDERS SHALL BE PAVED TO THE WIDTH SHOWN (6'). ALTERNATE DITCH SECTIONS MAY BE APPROVED OR REQUIRED.
8. STRUCTURAL SECTION SHALL BE BASED ON "R" VALUE AND "T.I.". DESIGN TO BE SUBMITTED TO DOT FOR REVIEW AND APPROVAL.
9. HOT MIX ASPHALT (HMA) SHALL BE TYPE A, 1/2"; AGGREGATE BASE (AB) SHALL BE CLASS 2, 3/4"
10. THE TOP 6" OF SUBGRADE AND ALL BASE AND SUBBASE SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
11. SUBGRADE ENHANCEMENT GEOTEXTILE SHOULD BE CONSIDERED FOR NATIVE SOIL R-VALUES LESS THAN 20.
12. FOUNDATION SLOPES STEEPER THAN FIVE HORIZONTAL TO ONE VERTICAL SHALL BE KEYED WHEN PLACING EMBANKMENT FILL. KEYS PER GRADING REQUIREMENTS.
13. SLOPE & DRAINAGE EASEMENTS (S&DE) SHALL EXTEND 5' MIN. BEYOND HINGE POINTS, TOE OF SLOPES, AND DRAINAGE STRUCTURES. SEE STANDARD PLAN RS-11 FOR ADDITIONAL SLOPE DETAILS.

Added per EDAC request prior to 10/28/10

Added reference to forthcoming standard plan prior to 10/28/10 P/C Mtg.

<p><b>APPROVED BY:</b></p> <p>_____                  JAMES W. WARE, P.E. NO. C61036                  DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION</p> <p>DATE: _____</p> <p>BOARD OF SUPERVISOR'S RESOLUTION NO. _____</p>	<p><b>EL DORADO COUNTY</b>                  DEPARTMENT OF TRANSPORTATION</p> <hr/> <p><b>DESIGN STANDARDS</b></p>		<p>FOUR-LANE                  UNDIVIDED ROAD</p>	<p><b>STD.                  PLAN</b></p> <p>RS-05</p> <p style="font-size: small;">SHT 2 OF 2</p>
-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------	------------------------------------------------------	-------------------------------------------------------------------------------------------------------



**NOTES:**

1. ULTIMATE BRIDGE TYPICAL SECTIONS TO BE APPROVED BY THE COUNTY.
2. BRIDGE TYPE TO BE APPROVED BY THE COUNTY.
3. WHERE BIKE LANE IS ADJACENT TO TYPE 25 BARRIER, USE CALTRANS BRIDGE STANDARD DETAIL SHEET XS16-500e, "TUBULAR BICYCLE RAILING". ADDITIONAL WIDTH MAY BE REQUIRED.
4. WIDTH OF BRIDGE STRUCTURE SHALL BE CONSISTENT WITH APPROVED ROADWAY UNLESS OTHERWISE APPROVED BY COUNTY.

- \* RAISED SIDEWALK TO BE PROVIDED WHEN WARRANTED
- \*\* SEE CALTRANS STANDARD PLANS
- \*\*\* TYPE 7 CHAIN LINK FENCE RAILING REQUIRED IN LIEU OF TUBULAR HAND RAILING WHEN STRUCTURE SPANS OVER A PUBLIC ROADWAY

**NOT TO SCALE**

**APPROVED BY:**

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE: \_\_\_\_\_

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_



**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



FOUR-LANE  
UNDIVIDED ROAD  
BRIDGE SECTIONS


**STD. PLAN**  
RS-06

Simplified presentation of note references prior to 10/28/10 P/C Mtg.



**STANDARD SECTION IN EMBANKMENT**

- RURAL FILL SECTION -  
SEE NOTE 7



**STANDARD SECTION IN EXCAVATION**

- RURAL CUT SECTION -  
SEE NOTE 7

\* ADDITIONAL RIGHT-OF-WAY MAY BE REQUIRED WHEN ROAD COINCIDES WITH A DESIGNATED ROUTE FOR AN ADDITIONAL PUBLIC FACILITY (I.E. PEDESTRIAN, BICYCLE, OR EQUESTRIAN TRAIL)

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
**DEPARTMENT OF TRANSPORTATION**  
**DESIGN STANDARDS**



MAJOR TWO-LANE  
UNDIVIDED ROAD

**STD.  
PLAN**

RS-07


SHT 1 OF 2


**NOTES:**

1. PROVIDE FOR A TWELVE (12') FOOT LEFT TURN POCKET WITHIN 400' OF ANY INTERSECTION WITH A GENERAL PLAN DESIGNATED ROAD OR HIGH-VOLUME (GREATER THAN 400 PEAK HOUR) LOCAL ROAD, UNLESS OTHERWISE APPROVED BY THE COUNTY.
2. SEE STANDARD PLAN MC-20 FOR CURBS (A2-6, A1-8).
3. SEE STANDARD PLAN MC-01 FOR SIDEWALK DETAILS. SIDEWALK LOCATIONS MAY VARY. MAINTAIN 6" MIN. CLEARANCE FROM R/W LINE.
4. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL, UNLESS A GEOTECHNICAL ENGINEER DETERMINES THAT A STEEPER SLOPE WILL BE SAFE FOR THE INTENDED USE AND WILL NOT BE SUSCEPTIBLE TO EROSION. SLOPES CONSTRUCTED FOUR HORIZONTAL TO ONE VERTICAL OR FLATIER DO NOT REQUIRE SLOPE EASEMENTS.
5. MAXIMUM STREET GRADES WITHOUT APPROVED DESIGN EXCEPTION:  
BELOW 3000' ELEVATION:  
 GENERAL PLAN ROADWAYS AND COLLECTOR ROADWAYS WHERE ADT >10,000 = 8%  
 COLLECTOR ROADWAYS WHERE ADT >4000 AND <10,000 = 10%  
 LOCAL ROADWAYS AND COLLECTOR ROADWAYS WHERE ADT <4000 = 12%  
  
ABOVE 3000' ELEVATION:  
 10% ALL ROADWAYS
6. MINIMUM STREET FLOW LINE GRADES SHALL BE 0.5%. REVERSE GRADE VERTICAL CURVES EXCEPTED.
7. ROADS IN RURAL REGIONS, RURAL CENTERS, AND THE CAMINO/POLLOCK PINES COMMUNITY REGION ARE NOT REQUIRED TO HAVE PCC CURB, GUTTER AND SIDEWALK. SHOULDERS SHALL BE PAVED TO THE WIDTH SHOWN (6'). ALTERNATE DITCH SECTIONS MAY BE APPROVED OR REQUIRED.
8. STRUCTURAL SECTION SHALL BE BASED ON "R" VALUE AND "T.I.". DESIGN TO BE SUBMITTED TO DOT FOR REVIEW AND APPROVAL.
9. HOT MIX ASPHALT (HMA) SHALL BE TYPE A, 1/2"; AGGREGATE BASE (AB) SHALL BE CLASS 2, 3/4"
10. THE TOP 6" OF SUBGRADE AND ALL BASE AND SUBBASE SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
11. SUBGRADE ENHANCEMENT GEOTEXTILE SHOULD BE CONSIDERED FOR NATIVE SOIL R-VALUES LESS THAN 20.
12. FOUNDATION SLOPES STEEPER THAN FIVE HORIZONTAL TO ONE VERTICAL SHALL BE KEYED WHEN PLACING EMBANKMENT FILL. KEYS PER GRADING REQUIREMENTS.
13. SLOPE & DRAINAGE EASEMENTS (S&DE) SHALL EXTEND 5' MIN. BEYOND HINGE POINTS, TOE OF SLOPES, AND DRAINAGE STRUCTURES. SEE STANDARD PLAN RS-11 FOR ADDITIONAL SLOPE DETAILS.

Added per EDAC request prior to 10/28/10 P/C Mtg.

Added reference to forthcoming standard plan prior to 10/28/10 P/C Mtg.

<p><b>APPROVED BY:</b></p> <p>_____                  JAMES W. WARE, P.E. NO. C61036                  DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION</p> <p>DATE: _____</p> <p>BOARD OF SUPERVISOR'S RESOLUTION NO. _____</p>	<p><b>EL DORADO COUNTY</b>                  DEPARTMENT OF TRANSPORTATION</p> <hr/> <p><b>DESIGN STANDARDS</b></p>		<p>MAJOR TWO-LANE                  UNDIVIDED ROAD</p>	<p><b>STD.                  PLAN</b></p> <p>RS-07</p> <p>SHT 2 OF 2</p>
-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------	-----------------------------------------------------------	-----------------------------------------------------------------------------



**NOTES:**

1. ULTIMATE BRIDGE TYPICAL SECTIONS TO BE APPROVED BY THE COUNTY.
2. BRIDGE TYPE TO BE APPROVED BY THE COUNTY.
3. WIDTH OF BRIDGE STRUCTURE SHALL BE CONSISTENT WITH APPROVED ROADWAY UNLESS OTHERWISE APPROVED BY COUNTY.

- \* RAISED SIDEWALK TO BE PROVIDED WHEN WARRANTED
- \*\* SEE CALTRANS STANDARD PLANS
- \*\*\* TYPE 7 CHAIN LINK FENCE RAILING REQUIRED IN LIEU OF TUBULAR HAND RAILING WHEN STRUCTURE SPANS OVER A PUBLIC ROADWAY

**NOT TO SCALE**

**APPROVED BY:**

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE: \_\_\_\_\_

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_


**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



MAJOR TWO-LANE  
UNDIVIDED ROAD  
BRIDGE SECTIONS

**STD.  
PLAN**

RS-08



LEGEND	
A	WIDTH OF RIGHT OF WAY IN FEET
B	WIDTH OF ROADWAY IN FEET

\* ADDITIONAL RIGHT OF WAY MAY BE REQUIRED WHEN ROAD COINCIDES WITH A DESIGNATED ROUTE FOR AN ADDITIONAL PUBLIC FACILITY (I.E. PEDESTRIAN, BICYCLE, OR EQUESTRIAN TRAIL)

Per EDAC Comment #3  
- added prior to 10/28/10  
P/C Mta.

AVG DAILY TRAFFIC	CLASSIFICATION	TYPICAL ACCESS BY:	RESIDENTIAL FRONTAGE ALLOWED	MINIMUM DESIGN SPEED	A	B	SIDEWALK	MAX GRADE <sup>◆</sup>	CURB TYPE
4000-10,000	NON-RES. COLLECTOR	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	35	70	54	BOTH SIDES	10%	A2-6
<4,000	NON-RES. LOCAL	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	25	60	44	BOTH SIDES	10%	A2-6
4000-10,000	COLLECTOR	LOCAL STREETS	NONE	35-45	60	40	BOTH SIDES	10%	A2-6
2500-4000	COLLECTOR	LOCAL STREETS	NONE	35	60	36	BOTH SIDES	12%	A2-6
500-2500	LOCAL	LOCAL STREETS AND DRIVEWAY BOTH SIDES	BOTH SIDES	25	60	36	BOTH SIDES	12%	C-2
<500	LOCAL	DRIVEWAY BOTH SIDES	BOTH SIDES	25	50	32	BOTH SIDES	12%	C-2

◆ MAXIMUM GRADE FOR ALL STREETS ABOVE 3000' ELEVATIONS = 10%

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



LOCAL ROADS  
EL DORADO HILLS  
COMMUNITY REGION

**STD. PLAN**

RS-20

SHT 1 OF 2




**GENERAL NOTES:**


1. SIDEWALKS, ~~IN ADDITION~~ shall be constructed where required by the Land Development Manual Changed "R" to "B"
2. BASIC CRITERIA:  
 12' TRAVEL LANES FOR VOLUMES GREATER THAN 500 ADT.  
 10' MINIMUM TRAVEL LANES FOR VOLUMES LESS THAN 500 ADT.  
 ROADWAY WIDTH, ~~R~~, SHALL BE 50' WITHIN 100' OF CURB RETURN OF AN INTERSECTION WITH A HIGHER CLASSIFICATION ROAD. CURB & GUTTER TRANSITION SHALL BE CONSTRUCTED BETWEEN 100' & 140' FROM CURB RETURN. FOR NON-RESIDENTIAL ROADWAYS, AND LOCAL COLLECTOR ROADWAYS, PAVEMENT CROWLINE SHALL BE CENTERED BETWEEN CURBS.
3. MINIMUM STREET FLOW LINE GRADE SHALL BE 0.5%, REVERSE GRADE VERTICAL CURVES EXCEPTED.
4. SEE STANDARD PLAN MC-01 FOR SIDEWALK DETAILS. SIDEWALK LOCATION MAY VARY. MAINTAIN MIN. 6" CLEARANCE FROM R/W LINE.
5. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL, UNLESS A GEOTECHNICAL ENGINEER DETERMINES THAT A STEEPER SLOPE WILL BE SAFE FOR THE INTENDED USE AND WILL NOT BE SUSCEPTIBLE TO EROSION. SLOPES CONSTRUCTED FOUR HORIZONTAL TO ONE VERTICAL OR FLATTER DO NOT REQUIRE SLOPE EASEMENTS.
6. STRUCTURAL SECTION SHALL BE BASED ON "R" VALUE AND "T.I.". DESIGN TO BE SUBMITTED TO DOT FOR REVIEW AND APPROVAL.
7. HOT MIX ASPHALT (HMA) SHALL BE TYPE A, 1/2"; AGGREGATE BASE (AB) SHALL BE CLASS 2, 3/4".
8. THE TOP 6" OF SUBGRADE AND ALL BASE AND SUB-BASE SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
9. SUBGRADE ENHANCEMENT GEOTEXTILE SHOULD BE CONSIDERED FOR NATIVE SOIL R-VALUES LESS THAN 20.
10. SLOPES OVER FIVE HORIZONTAL TO ONE VERTICAL SHALL BE KEYED WHEN PLACING EMBANKMENT FILL. KEYS PER GRADING REQUIREMENTS.
11. SLOPE AND DRAINAGE EASEMENTS (S&DE) SHALL EXTEND 5' BEYOND HINGE POINTS, TOE OF SLOPES, AND DRAINAGE STRUCTURES.
12. DESIGN SPEED FOR LOCAL STREETS WITH RESIDENTIAL FRONTAGE SHALL BE 25 MILES PER HOUR. DESIGN SPEED FOR STREETS WITHOUT RESIDENTIAL FRONTAGE SHALL BE 35 MILES PER HOUR. STREET ALIGNMENT AND PROFILE SHALL COMPLY WITH THE CRITERIA FOR SAFE STOPPING SIGHT DISTANCE FOR THESE DESIGN SPEEDS.
13. STREET SYSTEMS SHOULD BE LAID OUT TO DISCOURAGE TRAVEL AT HIGHER THAN DESIGN SPEEDS BY INCORPORATING CURVES, KNUCKLES AND "T" INTERSECTIONS AT NO MORE THAN 1000' INTERVALS, DEPENDING ON TERRAIN. CONTINUOUS STRAIGHT STREETS CONNECTING TWO ARTERIAL HIGHWAYS, WHICH WOULD ACT AS A "SHORTCUT" THROUGH A RESIDENTIAL AREA, SHALL BE AVOIDED.
14. STREETS SHALL INTERSECT AT RIGHT ANGLES WHEREVER POSSIBLE. STREETS SHALL NOT INTERSECT AT GREATER THAN 20° SKEW TO RIGHT ANGLE. FOUR-LEGGED INTERSECTIONS SHALL BE AVOIDED EXCEPT AT SIGNALIZED LOCATIONS. INTERSECTIONS SHALL HAVE ADEQUATE SIGHT DISTANCE IN CONFORMANCE WITH STD PLAN ~~MC~~-40. INTERSECTIONS ON CREST VERTICAL CURVES OR ON THE INSIDE OF HORIZONTAL CURVES SHALL BE AVOIDED. THE MINIMUM DISTANCE BETWEEN INTERSECTIONS ON SHALL BE 300 FEET ON COLLECTOR ROADWAYS AND 250 FEET ON LOCAL ROADWAYS MEASURED FROM CENTERLINE.
15. THE LOCATION OF ANY INTERSECTION SHALL BE REVIEWED BY THE COUNTY ENGINEER TO DETERMINE SAFETY AND COMPATIBILITY FOR SIGNAL PROGRESSION. TRAFFIC AT ANY INTERSECTION MAY BE ULTIMATELY RESTRICTED TO RIGHT TURN IN AND OUT ONLY.
16. FUELS REDUCTION ZONE, OF 20 FEET ON EITHER SIDE OF THE ROAD CENTERLINE, MUST BE CLEARED INCLUDING THE FOLLOWING:
  - ALL BRUSH REMOVED.
  - ALL TREES LIMBED UP TO 10 FEET.
  - WEEDS AND GRASS MOWED TO A 2 INCH STUBBLE.
  - 15 FOOT VERTICAL CLEARANCE CREATED DIRECTLY ABOVE THE HORIZONTALLY CLEARED AREA.

Added per EDAC request prior to 10/28/10 P/C Mtg.

Changed "MC" to "RS"

NOT TO SCALE

<p><b>APPROVED BY:</b></p> <p>_____                  JAMES W. WARE, P.E. NO. C61036                  DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION</p> <p>DATE: _____</p> <p>BOARD OF SUPERVISOR'S RESOLUTION NO. _____</p>	<p><b>EL DORADO COUNTY</b>                  DEPARTMENT OF TRANSPORTATION</p> <hr/> <p><b>DESIGN STANDARDS</b></p>		<p>LOCAL ROADS                  EL DORADO HILLS                  COMMUNITY REGION</p>	<p><b>STD. PLAN</b></p> <p>RS-20</p> <p>SHT 2 OF 2</p>
-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------	--------------------------------------------------------



LEGEND	
A	= WIDTH OF RIGHT OF WAY IN FEET
B	= WIDTH OF ROADWAY IN FEET

\* ADDITIONAL RIGHT OF WAY MAY BE REQUIRED WHEN ROAD COINCIDES WITH A DESIGNATED ROUTE FOR AN ADDITIONAL PUBLIC FACILITY (I.E. PEDESTRIAN, BICYCLE, OR EQUESTRIAN TRAIL)

Per EDAC Comment #3  
- added prior to  
10/28/10 P/C Mtg.

AVG DAILY TRAFFIC	CLASSIFICATION	TYPICAL ACCESS BY:	RESIDENTIAL FRONTAGE ALLOWED	MINIMUM DESIGN SPEED	A	B	SIDEWALK	MAX GRADE	CURB TYPE
4000-10,000	NON-RES. COLLECTOR	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	35	70	54	BOTH SIDES	10%	A2-6
<4,000	NON-RES. LOCAL	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	25	60	44	BOTH SIDES	10%	A2-6
4000-10,000	COLLECTOR	LOCAL STREETS	NONE	35-45	60	40	BOTH SIDES	10%	A2-6
2500-4000	COLLECTOR	LOCAL STREETS	NONE	35	60	36	BOTH SIDES	12%	A2-6
500-2500	LOCAL	LOCAL STREETS AND DRIVEWAY BOTH SIDES	BOTH SIDES	25	50	32	BOTH SIDES	12%	C-2
<500	LOCAL	DRIVEWAY BOTH SIDES	BOTH SIDES	25	50	28	BOTH SIDES	12%	C-2

◆ MAXIMUM GRADE FOR ALL STREETS ABOVE 3000' ELEVATIONS = 10%

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



LOCAL ROADS  
CAMERON PARK/PLACERVILLE/  
DIAMOND SPRINGS/EL DORADO/  
SHINGLE SPRINGS  
COMMUNITY REGIONS

**STD. PLAN**

RS-21


SHT 1 OF 2


GENERAL NOTES:

1. SIDEWALKS, ~~IN AD~~ shall be constructed where required by the Land Development Manual Changed "R" to "B"
2. BASIC CRITERIA:  
 12' TRAVEL LANES FOR VOLUMES GREATER THAN 500 ADT.  
 10' MINIMUM TRAVEL LANES FOR VOLUMES LESS THAN 500 ADT.  
 ROADWAY WIDTH, ~~R~~, SHALL BE 50' WITHIN 100' OF CURB RETURN OF AN INTERSECTION WITH A HIGHER CLASSIFICATION ROAD. CURB & GUTTER TRANSITION SHALL BE CONSTRUCTED BETWEEN 100' & 140' FROM CURB RETURN. FOR NON-RESIDENTIAL ROADWAYS, AND LOCAL COLLECTOR ROADWAYS, PAVEMENT CROWLINE SHALL BE CENTERED BETWEEN CURBS.
3. MINIMUM STREET FLOW LINE GRADE SHALL BE 0.5%, REVERSE GRADE VERTICAL CURVES EXCEPTED. Deleted to be consistent with Land Development Manual
4. SEE STANDARD PLAN MC-01 FOR SIDEWALK DETAILS. SIDEWALK LOCATION MAY VARY. MAINTAIN MIN. 6" CLEARANCE FROM R/W LINE. ~~CURB, CUTTER AND SIDEWALKS MAY BE WAIVED WHERE ALL LOTS ARE LARGER THAN ONE ACRE.~~
5. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL, UNLESS A GEOTECHNICAL ENGINEER DETERMINES THAT A STEEPER SLOPE WILL BE SAFE FOR THE INTENDED USE AND WILL NOT BE SUSCEPTIBLE TO EROSION. SLOPES CONSTRUCTED FOUR HORIZONTAL TO ONE VERTICAL OR FLATTER DO NOT REQUIRE SLOPE EASEMENTS.
6. STRUCTURAL SECTION SHALL BE BASED ON "R" VALUE AND "T.I.". DESIGN TO BE SUBMITTED TO DOT FOR REVIEW AND APPROVAL.
7. HOT MIX ASPHALT (HMA) SHALL BE TYPE A, 1/2"; AGGREGATE BASE (AB) SHALL BE CLASS 2, 3/4".
8. THE TOP 6" OF SUBGRADE AND ALL BASE AND SUB-BASE SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
9. SUBGRADE ENHANCEMENT GEOTEXTILE SHOULD BE CONSIDERED FOR NATIVE SOIL R-VALUES LESS THAN 20.
10. SLOPES OVER FIVE HORIZONTAL TO ONE VERTICAL SHALL BE KEYED WHEN PLACING EMBANKMENT FILL. KEYS PER GRADING REQUIREMENTS.
11. SLOPE AND DRAINAGE EASEMENTS (S&DE) SHALL EXTEND 5' BEYOND HINGE POINTS, TOE OF SLOPES, AND DRAINAGE STRUCTURES.
12. DESIGN SPEED FOR LOCAL STREETS WITH RESIDENTIAL FRONTAGE SHALL BE 25 MILES PER HOUR. DESIGN SPEED FOR STREETS WITHOUT RESIDENTIAL FRONTAGE SHALL BE 35 MILES PER HOUR. STREET ALIGNMENT AND PROFILE SHALL COMPLY WITH THE CRITERIA FOR SAFE STOPPING SIGHT DISTANCE FOR THESE DESIGN SPEEDS.
13. STREET SYSTEMS SHOULD BE LAID OUT TO DISCOURAGE TRAVEL AT HIGHER THAN DESIGN SPEEDS BY INCORPORATING CURVES, KNUCKLES AND "T" INTERSECTIONS AT NO MORE THAN 1000' INTERVALS, DEPENDING ON TERRAIN. CONTINUOUS STRAIGHT STREETS CONNECTING TWO ARTERIAL HIGHWAYS, WHICH WOULD ACT AS A "SHORTCUT" THROUGH A RESIDENTIAL AREA, SHALL BE AVOIDED.
14. STREETS SHALL INTERSECT AT RIGHT ANGLES WHEREVER POSSIBLE. STREETS SHALL NOT INTERSECT AT GREATER THAN 20' SKEW TO RIGHT ANGLE. FOUR-LEGGED INTERSECTIONS SHALL BE AVOIDED EXCEPT AT SIGNALIZED LOCATIONS. INTERSECTIONS SHALL HAVE ADEQUATE SIGHT DISTANCE IN CONFORMANCE WITH STD PLAN ~~MC-40~~. INTERSECTIONS ON CREST VERTICAL CURVES OR ON THE INSIDE OF HORIZONTAL CURVES SHALL BE AVOIDED. THE MINIMUM DISTANCE BETWEEN INTERSECTIONS ON SHALL BE 300 FEET ON COLLECTOR ROADWAYS AND 250 FEET ON LOCAL ROADWAYS MEASURED FROM CENTERLINE.
15. THE LOCATION OF ANY INTERSECTION SHALL BE REVIEWED BY THE COUNTY ENGINEER TO DETERMINE SAFETY AND COMPATIBILITY FOR SIGNAL PROGRESSION. TRAFFIC AT ANY INTERSECTION MAY BE ULTIMATELY RESTRICTED TO RIGHT TURN IN AND OUT ONLY.
16. A FUELS REDUCTION ZONE, OF 20 FEET ON EITHER SIDE OF THE ROAD CENTERLINE, MUST BE CLEARED INCLUDING THE FOLLOWING:
  - ALL BRUSH REMOVED.
  - ALL TREES LIMBED UP TO 10 FEET.
  - WEEDS AND GRASS MOWED TO A 2 INCH STUBBLE.
  - 15 FOOT VERTICAL CLEARANCE CREATED DIRECTLY ABOVE THE HORIZONTALLY CLEARED AREA.Changed "MC" to "RS"

Added per EDAC request prior to 10/28/10 P/C Mtg

**NOT TO SCALE**

APPROVED BY:  _____ JAMES W. WARE, P.E. NO. C61036      DATE: DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION  BOARD OF SUPERVISOR'S RESOLUTION NO. _____	<b>EL DORADO COUNTY</b> DEPARTMENT OF TRANSPORTATION  <b>DESIGN STANDARDS</b>		LOCAL ROADS CAMERON PARK/PLACERVILLE/ DIAMOND SPRINGS/EL DORADO/ SHINGLE SPRINGS COMMUNITY REGIONS	<b>STD. PLAN</b>  RS-21  SHT 2 OF 2
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------	-------------------------------------------------



LEGEND	
A	= WIDTH OF RIGHT OF WAY IN FEET
B	= WIDTH OF ROADWAY IN FEET

- \* SPECIAL CONDITIONS MAY REQUIRE CURB AND GUTTER
- \*\* ALTERNATE DITCH SECTIONS MAY BE APPROVED OR REQUIRED

AVG DAILY TRAFFIC	CLASSIFICATION	TYPICAL ACCESS BY:	RESIDENTIAL FRONTAGE ALLOWED	MINIMUM DESIGN SPEED	A	B	MAX GRADE $\blacklozenge$
4000-10,000	NON-RES. COLLECTOR	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	35	70	54	10%
<4,000	NON-RES. LOCAL	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	25	60	44	10%
4000-10,000	COLLECTOR	LOCAL STREETS	NONE	35-45	60	40	10%
2500-4000	COLLECTOR	LOCAL STREETS	NONE	35	60	36	12%
500-2500	LOCAL	LOCAL STREETS AND DRIVEWAY BOTH SIDES	BOTH SIDES	25	50	32	12%
<500	LOCAL	DRIVEWAY BOTH SIDES	BOTH SIDES	25	50	28	12%

$\blacklozenge$  MAXIMUM GRADE FOR ALL STREETS ABOVE 3000' ELEVATIONS = 10%

NOT TO SCALE

APPROVED BY:  
 JAMES W. WARE, P.E. NO. C61036  
 DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION  
 DATE: \_\_\_\_\_  
 BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
 DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



LOCAL ROADS  
 CAMINO/POLLOCK PINES  
 COMMUNITY REGION

**STD. PLAN**  
 RS-22  
 SHT 1 OF 2

**GENERAL NOTES:**

Changed "R" to "B"

1. SIDEWALKS MAY BE REQUIRED TO PROVIDE CONTINUOUS PEDESTRIAN ROUTES.
2. BASIC CRITERIA:  
 12' TRAVEL LANES FOR VOLUMES GREATER THAN 500 ADT.  
 10' MINIMUM TRAVEL LANES FOR VOLUMES LESS THAN 500 ADT.  
 ROADWAY WIDTH, ~~R~~, SHALL BE 50' WITHIN 100' OF CURB RETURN OF AN INTERSECTION WITH A HIGHER CLASSIFICATION ROAD. CURB & GUTTER TRANSITION SHALL BE CONSTRUCTED BETWEEN 100' & 140' FROM CURB RETURN. FOR NON-RESIDENTIAL ROADWAYS, AND LOCAL COLLECTOR ROADWAYS, PAVEMENT CROWLINE SHALL BE CENTERED BETWEEN CURBS.
3. MINIMUM STREET FLOW LINE GRADE SHALL BE 0.5%, REVERSE GRADE VERTICAL CURVES EXCEPTED.
4. SEE STANDARD PLAN MC-01 FOR SIDEWALK DETAILS. SIDEWALK LOCATION MAY VARY. MAINTAIN MIN. 6" CLEARANCE FROM R/W LINE.
5. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL UNLESS A GEOTECHNICAL ENGINEER DETERMINES THAT A STEEPER SLOPE WILL BE SAFE FOR THE INTENDED USE AND WILL NOT BE SUSCEPTIBLE TO EROSION. SLOPES CONSTRUCTED FOUR HORIZONTAL TO ONE VERTICAL OR FLATTER DO NOT REQUIRE SLOPE EASEMENTS.
6. STRUCTURAL SECTION SHALL BE BASED ON "R" VALUE AND "T.I.". DESIGN TO BE SUBMITTED TO DOT FOR REVIEW AND APPROVAL.
7. HOT MIX ASPHALT (HMA) SHALL BE TYPE A, 1/2"; AGGREGATE BASE (AB) SHALL BE CLASS 2, 3/4".
8. THE TOP 6" OF SUBGRADE AND ALL BASE AND SUB-BASE SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
9. SUBGRADE ENHANCEMENT GEOTEXTILE SHOULD BE CONSIDERED FOR NATIVE SOIL R-VALUES LESS THAN 20.
10. SLOPES OVER FIVE HORIZONTAL TO ONE VERTICAL SHALL BE KEYED WHEN PLACING EMBANKMENT FILL. KEYS PER GRADING REQUIREMENTS.
11. SLOPE AND DRAINAGE EASEMENTS (S&DE) SHALL EXTEND 5' BEYOND HINGE POINTS, TOE OF SLOPES, AND DRAINAGE STRUCTURES.
12. DESIGN SPEED FOR LOCAL STREETS WITH RESIDENTIAL FRONTAGE SHALL BE 25 MILES PER HOUR. DESIGN SPEED FOR STREETS WITHOUT RESIDENTIAL FRONTAGE SHALL BE 35 MILES PER HOUR. STREET ALIGNMENT AND PROFILE SHALL COMPLY WITH THE CRITERIA FOR SAFE STOPPING SIGHT DISTANCE FOR THESE DESIGN SPEEDS.
13. STREET SYSTEMS SHOULD BE LAID OUT TO DISCOURAGE TRAVEL AT HIGHER THAN DESIGN SPEEDS BY INCORPORATING CURVES, KNUCKLES AND "T" INTERSECTIONS AT NO MORE THAN 1000' INTERVALS, DEPENDING ON TERRAIN. CONTINUOUS STRAIGHT STREETS CONNECTING TWO ARTERIAL HIGHWAYS, WHICH WOULD ACT AS A "SHORTCUT" THROUGH A RESIDENTIAL AREA, SHALL BE AVOIDED.
14. STREETS SHALL INTERSECT AT RIGHT ANGLES WHEREVER POSSIBLE. STREETS SHALL NOT INTERSECT AT GREATER THAN 20° SKEW TO RIGHT ANGLE. FOUR-LEGGED INTERSECTIONS SHALL BE AVOIDED EXCEPT AT SIGNALIZED LOCATIONS. INTERSECTIONS SHALL HAVE ADEQUATE SIGHT DISTANCE IN CONFORMANCE WITH STD PLAN ~~MC~~-40. INTERSECTIONS ON CREST VERTICAL CURVES OR ON THE INSIDE OF HORIZONTAL CURVES SHALL BE AVOIDED. THE MINIMUM DISTANCE BETWEEN INTERSECTIONS ON SHALL BE 300 FEET ON COLLECTOR ROADWAYS AND 250 FEET ON LOCAL ROADWAYS MEASURED FROM CENTERLINE.
15. THE LOCATION OF ANY INTERSECTION SHALL BE REVIEWED BY THE COUNTY ENGINEER TO DETERMINE SAFETY AND COMPATIBILITY FOR SIGNAL PROGRESSION. TRAFFIC AT ANY INTERSECTION MAY BE ULTIMATELY RESTRICTED TO RIGHT TURN IN AND OUT ONLY.
16. A FUELS REDUCTION ZONE, OF 20 FEET ON EITHER SIDE OF THE ROAD CENTERLINE, MUST BE CLEARED INCLUDING THE FOLLOWING:
  - ALL BRUSH REMOVED.
  - ALL TREES LIMBED UP TO 10 FEET.
  - WEEDS AND GRASS MOWED TO A 2 INCH STUBBLE.
  - 15 FOOT VERTICAL CLEARANCE CREATED DIRECTLY ABOVE THE HORIZONTALLY CLEARED AREA.

Added per EDAC request prior to 10/28/10 P/C Mtg.

Changed "MC" to "RS"

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
 DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_


**EL DORADO COUNTY**  
 DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



LOCAL ROADS  
 CAMINO/POLLOCK PINES  
 COMMUNITY REGION

**STD. PLAN**  
 RS-22

SHT 2 OF 2



LEGEND	
A	= WIDTH OF RIGHT OF WAY IN FEET
B	= WIDTH OF ROADWAY IN FEET

- \* SPECIAL CONDITIONS MAY REQUIRE CURB AND GUTTER
- \*\* ALTERNATE DITCH SECTIONS MAY BE APPROVED OR REQUIRED

AVG DAILY TRAFFIC	CLASSIFICATION	TYPICAL ACCESS BY:	RESIDENTIAL FRONTAGE ALLOWED	MINIMUM DESIGN SPEED	A	B	MAX GRADE $\blacklozenge$
4000-10,000	NON-RES. COLLECTOR	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	40	70	54	10%
400-4,000	NON-RES. LOCAL	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	40	60	44	10%
<400	NON-RES. LOCAL	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	25	60	44	10%
4000-10,000	COLLECTOR	LOCAL STREETS	NONE	40	60	40	10%
2500-4000	COLLECTOR	LOCAL STREETS	NONE	40	60	36	12%
500-2500	LOCAL	LOCAL STREETS AND DRIVEWAY BOTH SIDES	BOTH SIDES	40	50	28	12%
<500	LOCAL	DRIVEWAY BOTH SIDES	BOTH SIDES	25	50	24	12%

$\blacklozenge$  MAXIMUM GRADE FOR ALL STREETS ABOVE 3000' ELEVATIONS = 10%

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



LOCAL ROADS  
RURAL REGIONS  
& RURAL CENTERS

**STD. PLAN**

RS-23

SHT 1 OF 2

**GENERAL NOTES:**

Changed "R" to "B"

1. SIDEWALKS MAY BE REQUIRED TO PROVIDE CONTINUOUS PEDESTRIAN ROUTES.
2. BASIC CRITERIA:  
 12' TRAVEL LANES FOR VOLUMES GREATER THAN 500 ADT.  
 10' MINIMUM TRAVEL LANES FOR VOLUMES LESS THAN 500 ADT.  
 ROADWAY WIDTH, ~~R~~, SHALL BE 50' WITHIN 100' OF CURB RETURN OF AN INTERSECTION WITH A HIGHER CLASSIFICATION ROAD. CURB & GUTTER TRANSITION SHALL BE CONSTRUCTED BETWEEN 100' & 140' FROM CURB RETURN. FOR NON-RESIDENTIAL ROADWAYS, AND LOCAL COLLECTOR ROADWAYS, PAVEMENT CROWNLINER SHALL BE CENTERED BETWEEN CURBS.
3. MINIMUM STREET FLOW LINE GRADE SHALL BE 0.5%. REVERSE GRADE VERTICAL CURVES EXCEPTED.
4. SEE STANDARD PLAN MC-01 FOR SIDEWALK DETAILS. SIDEWALK LOCATION MAY VARY. MAINTAIN MIN. 6" CLEARANCE FROM R/W LINE.
5. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL, UNLESS A GEOTECHNICAL ENGINEER DETERMINES THAT A STEEPER SLOPE WILL BE SAFE FOR THE INTENDED USE AND WILL NOT BE SUSCEPTIBLE TO EROSION. SLOPES CONSTRUCTED FOUR HORIZONTAL TO ONE VERTICAL OR FLATTER DO NOT REQUIRE SLOPE EASEMENTS.
6. STRUCTURAL SECTION SHALL BE BASED ON "R" VALUE AND "T.I.". DESIGN TO BE SUBMITTED TO DOT FOR REVIEW AND APPROVAL.
7. HOT MIX ASPHALT (HMA) SHALL BE TYPE A, 1/2"; AGGREGATE BASE (AB) SHALL BE CLASS 2, 3/4".
8. THE TOP 6" OF SUBGRADE AND ALL BASE AND SUB-BASE SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
9. SUBGRADE ENHANCEMENT GEOTEXTILE SHOULD BE CONSIDERED FOR NATIVE SOIL R-VALUES LESS THAN 20.
10. SLOPES OVER FIVE HORIZONTAL TO ONE VERTICAL SHALL BE KEYED WHEN PLACING EMBANKMENT FILL. KEYS PER GRADING REQUIREMENTS.
11. SLOPE AND DRAINAGE EASEMENTS (S&DE) SHALL EXTEND 5' BEYOND HINGE POINTS, TOE OF SLOPES, AND DRAINAGE STRUCTURES.
12. DESIGN SPEED FOR LOCAL STREETS WITH RESIDENTIAL FRONTAGE SHALL BE 25 MILES PER HOUR. DESIGN SPEED FOR STREETS WITHOUT RESIDENTIAL FRONTAGE SHALL BE 35 MILES PER HOUR. STREET ALIGNMENT AND PROFILE SHALL COMPLY WITH THE CRITERIA FOR SAFE STOPPING SIGHT DISTANCE FOR THESE DESIGN SPEEDS.
13. STREET SYSTEMS SHOULD BE LAID OUT TO DISCOURAGE TRAVEL AT HIGHER THAN DESIGN SPEEDS BY INCORPORATING CURVES, KNUCKLES AND "T" INTERSECTIONS AT NO MORE THAN 1000' INTERVALS, DEPENDING ON TERRAIN. CONTINUOUS STRAIGHT STREETS CONNECTING TWO ARTERIAL HIGHWAYS, WHICH WOULD ACT AS A "SHORTCUT" THROUGH A RESIDENTIAL AREA, SHALL BE AVOIDED.
14. STREETS SHALL INTERSECT AT RIGHT ANGLES WHEREVER POSSIBLE. STREETS SHALL NOT INTERSECT AT GREATER THAN 20° SKEW TO RIGHT ANGLE. FOUR-LEGGED INTERSECTIONS SHALL BE AVOIDED EXCEPT AT SIGNALIZED LOCATIONS. INTERSECTIONS SHALL HAVE ADEQUATE SIGHT DISTANCE IN CONFORMANCE WITH STD PLAN ~~MC~~-40. INTERSECTIONS ON CREST VERTICAL CURVES OR ON THE INSIDE OF HORIZONTAL CURVES SHALL BE AVOIDED. THE MINIMUM DISTANCE BETWEEN INTERSECTIONS ON SHALL BE 300 FEET ON COLLECTOR ROADWAYS AND 250 FEET ON LOCAL ROADWAYS MEASURED FROM CENTERLINE.
15. THE LOCATION OF ANY INTERSECTION SHALL BE REVIEWED BY THE COUNTY ENGINEER TO DETERMINE SAFETY AND COMPATIBILITY FOR SIGNAL PROGRESSION. TRAFFIC AT ANY INTERSECTION MAY BE ULTIMATELY RESTRICTED TO RIGHT TURN IN AND OUT ONLY.
16. A FUELS REDUCTION ZONE, OF 20 FEET ON EITHER SIDE OF THE ROAD CENTERLINE, MUST BE CLEARED INCLUDING THE FOLLOWING:
  - ALL BRUSH REMOVED.
  - ALL TREES LIMBED UP TO 10 FEET.
  - WEEDS AND GRASS MOWED TO A 2 INCH STUBBLE.
  - 15 FOOT VERTICAL CLEARANCE CREATED DIRECTLY ABOVE THE HORIZONTALLY CLEARED AREA.

Added per EDAC request prior to 10/28/10 P/C Mtg.

Changed "MC" to "RS"

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
 DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
 DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**




LOCAL ROADS  
 RURAL REGIONS  
 & RURAL CENTERS

**STD.  
 PLAN**

RS-23

SHT 2 OF 2



LEGEND	
A	= WIDTH OF RIGHT OF WAY IN FEET
B	= WIDTH OF ROADWAY IN FEET

\* ROLLED CURB AND GUTTER SHALL BE COUNTY TYPE 1.  
SPECIAL CONDITIONS MAY REQUIRE OTHER TYPES OR ROADSIDE DITCHES

AVG DAILY TRAFFIC	CLASSIFICATION	TYPICAL ACCESS BY:	RESIDENTIAL FRONTAGE ALLOWED	MINIMUM DESIGN SPEED	A	B	MAX GRADE
4000-10,000	NON-RES. COLLECTOR	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	35	70	54	10%
<4,000	NON-RES. LOCAL	NON-RES. LOCAL STREETS AND DRIVEWAY BOTH SIDES	N/A	25	60	44	10%
4000-10,000	COLLECTOR	LOCAL STREETS	NONE	35-45	60	40	10%
2500-4000	COLLECTOR	LOCAL STREETS	NONE	35	60	36	10%
500-2500	LOCAL	LOCAL STREETS AND DRIVEWAY BOTH SIDES	BOTH SIDES	25	50	32	10%
<500	LOCAL	DRIVEWAY BOTH SIDES	BOTH SIDES	25	50	28	10%

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



LOCAL ROADS  
TAHOE REGION

**STD.**  
**PLAN**

RS-25

SHT 1 OF 2



**GENERAL NOTES:**


Changed "R" to "B"


1. SIDEWALKS MAY BE REQUIRED TO PROVIDE CONTINUOUS PEDESTRIAN ROUTES.
2. BASIC CRITERIA:  
 12' TRAVEL LANES FOR VOLUMES GREATER THAN 500 ADT.  
 10' MINIMUM TRAVEL LANES FOR VOLUMES LESS THAN 500 ADT.  
 ROADWAY WIDTH, ~~R~~, SHALL BE 50' WITHIN 100' OF CURB RETURN OF AN INTERSECTION WITH A HIGHER CLASSIFICATION ROAD. CURB & GUTTER TRANSITION SHALL BE CONSTRUCTED BETWEEN 100' & 140' FROM CURB RETURN. FOR NON-RESIDENTIAL ROADWAYS, AND LOCAL COLLECTOR ROADWAYS, PAVEMENT CROWLINE SHALL BE CENTERED BETWEEN CURBS.
3. MINIMUM STREET FLOW LINE GRADE SHALL BE 0.5%, REVERSE GRADE VERTICAL CURVES EXCEPTED.
4. SEE STANDARD PLAN MC-01 FOR SIDEWALK DETAILS. SIDEWALK LOCATION MAY VARY. MAINTAIN MIN. 6" CLEARANCE FROM R/W LINE.
5. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL, UNLESS A GEOTECHNICAL ENGINEER DETERMINES THAT A STEEPER SLOPE WILL BE SAFE FOR THE INTENDED USE AND WILL NOT BE SUSCEPTIBLE TO EROSION. SLOPES CONSTRUCTED FOUR HORIZONTAL TO ONE VERTICAL OR FLATIER DO NOT REQUIRE SLOPE EASEMENTS.
6. STRUCTURAL SECTION SHALL BE BASED ON "R" VALUE AND "T.I.". DESIGN TO BE SUBMITTED TO DOT FOR REVIEW AND APPROVAL.
7. HOT MIX ASPHALT (HMA) SHALL BE TYPE A, 1/2"; AGGREGATE BASE (AB) SHALL BE CLASS 2, 3/4".
8. THE TOP 6" OF SUBGRADE AND ALL BASE AND SUB-BASE SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
9. SUBGRADE ENHANCEMENT GEOTEXTILE SHOULD BE CONSIDERED FOR NATIVE SOIL R-VALUES LESS THAN 20.
10. SLOPES OVER FIVE HORIZONTAL TO ONE VERTICAL SHALL BE KEYED WHEN PLACING EMBANKMENT FILL. KEYS PER GRADING REQUIREMENTS.
11. SLOPE AND DRAINAGE EASEMENTS (S&DE) SHALL EXTEND 5' BEYOND HINGE POINTS, TOE OF SLOPES, AND DRAINAGE STRUCTURES.
12. DESIGN SPEED FOR LOCAL STREETS WITH RESIDENTIAL FRONTAGE SHALL BE 25 MILES PER HOUR. DESIGN SPEED FOR STREETS WITHOUT RESIDENTIAL FRONTAGE SHALL BE 35 MILES PER HOUR. STREET ALIGNMENT AND PROFILE SHALL COMPLY WITH THE CRITERIA FOR SAFE STOPPING SIGHT DISTANCE FOR THESE DESIGN SPEEDS.
13. STREET SYSTEMS SHOULD BE LAID OUT TO DISCOURAGE TRAVEL AT HIGHER THAN DESIGN SPEEDS BY INCORPORATING CURVES, KNUCKLES AND "T" INTERSECTIONS AT NO MORE THAN 1000' INTERVALS, DEPENDING ON TERRAIN. CONTINUOUS STRAIGHT STREETS CONNECTING TWO ARTERIAL HIGHWAYS, WHICH WOULD ACT AS A "SHORTCUT" THROUGH A RESIDENTIAL AREA, SHALL BE AVOIDED.
14. STREETS SHALL INTERSECT AT RIGHT ANGLES WHEREVER POSSIBLE. STREETS SHALL NOT INTERSECT AT GREATER THAN 20° SKEW TO RIGHT ANGLE. FOUR-LEGGED INTERSECTIONS SHALL BE AVOIDED EXCEPT AT SIGNALIZED LOCATIONS. INTERSECTIONS SHALL HAVE ADEQUATE SIGHT DISTANCE IN CONFORMANCE WITH STD PLAN MC-40. INTERSECTIONS ON CREST VERTICAL CURVES OR ON THE INSIDE OF HORIZONTAL CURVES SHALL BE AVOIDED. THE MINIMUM DISTANCE BETWEEN INTERSECTIONS ON SHALL BE 300 FEET ON COLLECTOR ROADWAYS AND 250 FEET ON LOCAL ROADWAYS MEASURED FROM CENTERLINE.
15. THE LOCATION OF ANY INTERSECTION SHALL BE REVIEWED BY THE COUNTY ENGINEER TO DETERMINE SAFETY AND COMPATIBILITY FOR SIGNAL PROGRESSION. TRAFFIC AT ANY INTERSECTION MAY BE ULTIMATELY RESTRICTED TO RIGHT TURN IN AND OUT ONLY.
16. A FUELS REDUCTION ZONE, OF 20 FEET ON EITHER SIDE OF THE ROAD CENTERLINE, MUST BE CLEARED INCLUDING THE FOLLOWING:
  - ALL BRUSH REMOVED.
  - ALL TREES LIMBED UP TO 10 FEET.
  - WEEDS AND GRASS MOWED TO A 2 INCH STUBBLE.
  - 15 FOOT VERTICAL CLEARANCE CREATED DIRECTLY ABOVE THE HORIZONTALLY CLEARED AREA.

Added per EDAC request prior to 10/28/10 P/C Mtg.

Changed "MC" to "RS"

NOT TO SCALE

<p>APPROVED BY:</p> <p>_____                  JAMES W. WARE, P.E. NO. C61036                  DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION</p> <p>DATE: _____</p> <p>BOARD OF SUPERVISOR'S RESOLUTION NO. _____</p>	<p><b>EL DORADO COUNTY</b>                  DEPARTMENT OF TRANSPORTATION</p> <hr/> <p><b>DESIGN STANDARDS</b></p>		<p>LOCAL ROADS                  TAHOE REGIONS</p>	<p><b>STD. PLAN</b></p> <p>RS-25</p> <p>SHT 2 OF 2</p>
----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------	-------------------------------------------------------	--------------------------------------------------------



ADT	RW	ROADWAY WIDTH	SHOULDER WIDTH	DESIGN SPEED	MAX GRADE	STRUCTURAL SECTION
1-150	50'	20'	1' (EACH SIDE)	20 MPH	15% PAVED	6" CLASS 2 AB (SEE NOTE 10)
151-600	50'	20'	2' (EACH SIDE)	25 MPH	12% UNPAVED (SEE NOTE 5) *	
601-1500	60'	20'	5' (EACH SIDE)	40 MPH	13% *	SEE NOTE 7
1501-2500	60'	22'	6' (EACH SIDE)	40 MPH		SEE NOTE 7

\* 15% WITH COUNTY ENGINEER'S APPROVAL (NOT TO EXCEED 600 L.F.)

NO DESIGN EXCEPTION OR WAIVER WILL BE ALLOWED FOR ROADWAY WIDTH LESS THAN 20'

NOT TO SCALE

APPROVED BY:

JAMES W. WARE, P.E. NO. C61036  
DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



PRIVATE ROADS  
RURAL REGIONS &  
RURAL CENTERS

**STD.  
PLAN**

RS-30

SHT 1 OF 2

**NOTES:**

1. THIS STANDARD PLAN (RS-30) REPLACES PRIOR STANDARD PLAN 101C. STANDARD PLAN RS-23 SHALL BE USED FOR ALL COUNTY MAINTAINED LOCAL ROADS IN RURAL REGIONS AND RURAL CENTERS. COUNTY MAINTAINED LOCAL ROADS WITHIN COMMUNITY REGIONS SHALL USE STANDARD PLAN RS-20 THROUGH 22, AS APPROPRIATE.
2. ADT DATA SHOWN IN THE TABLE ARE THE FORECASTED FOR 20-YEAR OUT DAILY VOLUMES.
3. ROADS ABOVE 3000 FT ELEVATION SHALL BE PAVED REGARDLESS OF ADT.
4. MAXIMUM ROAD GRADE IS 15%. ROADS STEEPER THAN 12% SHALL BE PAVED REGARDLESS OF ADT OR LOCATION.
5. DOUBLE-CHIP SEAL MAY BE SUBSTITUTED FOR 2" OF AB FOR ROADS WITH ADT BELOW 601.
6. WIDENING OF EXISTING ON-SITE ROADS SHALL COMPLY WITH STRUCTURAL SECTION REQUIRED AND MEET OR EXCEED THE SURFACING OF THE EXISTING ROAD.
7. STRUCTURAL SECTION SHALL BE BASED ON "R" VALUE AND "T.I.". DESIGN TO BE SUBMITTED TO DOT FOR REVIEW AND APPROVAL. ALL ROADS SHALL BE CAPABLE OF SUPPORTING LEGAL WEIGHT VEHICLES AND EXEMPT VEHICLES PURSUANT TO SECTION 35550 et.seq. OF THE CALIFORNIA VEHICLE CODE.
8. HOT MIX ASPHALT (HMA) SHALL BE TYPE A, 1/2"; AGGREGATE BASE (AB) SHALL BE CLASS 2, 3/4".
9. THE TOP 6" OF SUBGRADE AND ALL BASE AND SUB-BASE SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
10. SUBGRADE ENHANCEMENT GEOTEXTILE SHOULD BE CONSIDERED FOR NATIVE SOIL R-VALUES LESS THAN 20.
11. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL, UNLESS A GEOTECHNICAL ENGINEER DETERMINES THAT A STEEPER SLOPE WILL BE SAFE FOR THE INTENDED USE AND WILL NOT BE SUSCEPTIBLE TO EROSION. SLOPES CONSTRUCTED FOUR HORIZONTAL TO ONE VERTICAL OR FLATTER DO NOT REQUIRE SLOPE EASEMENTS.
12. SLOPE & DRAINAGE EASEMENTS (S&DE) SHALL EXTEND 5' BEYOND HINGE POINTS, TOE OF SLOPES, AND DRAINAGE STRUCTURES.
13. SHOULDERS SHALL BE DRIVABLE SURFACES BUT DO NOT REQUIRE PAVING.
14. DEAD END ROADS IN EXCESS OF 500' SHALL HAVE A MINIMUM ROADWAY WIDTH OF 26', NOT INCLUDING THE SHOULDER WIDTH REQUIREMENT SHOWN IN THE TABLE, FOR THE ENTIRE LENGTH OF THE ROAD. THIS REQUIREMENT CANNOT BE MODIFIED BY DESIGN EXCEPTION OR WAIVER.
15. A FUELS REDUCTION ZONE, OF 20 FEET ON EITHER SIDE OF THE ROAD CENTERLINE, MUST BE CLEARED INCLUDING THE FOLLOWING:
  - ALL BRUSH REMOVED.
  - ALL TREES LIMBED UP TO 10 FEET.
  - WEEDS AND GRASS MOWED TO A 2 INCH STUBBLE.
  - 15 FOOT VERTICAL CLEARANCE CREATED DIRECTLY ABOVE THE HORIZONTALLY CLEARED AREA.
  - THIS REQUIREMENT CANNOT BE MODIFIED BY DESIGN EXCEPTION OR WAIVER.

**APPROVED BY:**

JAMES W. WARE, P.E. NO. C61036  
 DIRECTOR, EL DORADO COUNTY DEPARTMENT OF TRANSPORTATION

DATE:

BOARD OF SUPERVISOR'S RESOLUTION NO. \_\_\_\_\_

**EL DORADO COUNTY**  
 DEPARTMENT OF TRANSPORTATION  
**DESIGN STANDARDS**



PRIVATE ROADS  
 RURAL REGIONS &  
 RURAL CENTERS

**STD.  
 PLAN**

RS-30

SHT 2 OF 2