



EL DORADO COUNTY

DEPARTMENT OF TRANSPORTATION

<http://www.edcgov.us/DOT/>

PLACERVILLE OFFICES:

MAIN OFFICE:
2850 Fairlane Court, Placerville, CA 95667
(530) 621-5900 / (530) 626-0387 Fax

CONSTRUCTION & MAINTENANCE:
2441 Headington Road, Placerville, CA 95667
(530) 642-4909 / (530) 642-0508 Fax

LAKE TAHOE OFFICES:

ENGINEERING:
924 B Emerald Bay Road, South Lake Tahoe, CA 96150
(530) 573-7900 / (530) 541-7049 Fax

MAINTENANCE:
1121 Shakori Drive, South Lake Tahoe, CA 96150
(530) 573-3180 / (530) 577-8402 Fax

DATE: March 31, 2020

TO: All Prospective Bidders

SUBJECT: **Addendum No. 2**
Hanks Exchange Road at Squaw Hollow Creek Bridge Replacement Project
Contract No. 3916, Project No. 77135

Submit proposals for this work with the understanding and full consideration of this Addendum No. 2. The revisions declared in this Addendum are essential parts of the Contract.

ITEM NO.	LOCATION, PAGE, OR DRAWING NO.	DESCRIPTION OF CHANGE
2.01	SP § 3.33E(1)	<p>Bidders are instructed to add the following after item 1 in section 12-3.33E(1) in the Special Provisions:</p> <p style="text-align: center;">2. Solar power with remote monitoring</p>
2.02		<p>Bidders are instructed to add the following section on Page SP-32 of the Special Provisions:</p> <p style="text-align: center;">12-3.33E(4) Remote Monitoring</p> <p>If a generator can not be supplied as back up to the solar power for the PTSS, then a Remote Monitoring System (RMS) must be implemented. The RMS must be capable of reporting signal location, battery voltage / batter history and system default. The RMS shall include a password protected web site viewable from any computer with internet capability. In the event of a system default the RMS shall provide specific information concerning the cause of the system default. The RMS shall be equipped with a mechanism capable of immediately contacting a minimum of three previously designated individuals via text messaging and/or email upon a default.</p> <p>The running program operating the PTSS system shall be available and viewable through the RMS website at all times. The RMS shall maintain a history of the operating system in each signal including operating hours and events and the location of the PTSS trailer.</p>

ITEM NO.	LOCATION, PAGE, OR DRAWING NO.	DESCRIPTION OF CHANGE
		In the event of a voltage drop the designated individual must respond to the project site within 24 hours and charge the battery on the PTSS.
2.03	Agreement page C-12	Bidders are instructed to replace page C-12 in the agreement with the attached page C-12 REV.
2.04	Proposal page P-4	Bidders are instructed to replace page P-4 in the Proposal with the attached page P-4REV.
2.05	Notice to Bidders Page N-1	<p>Bidders are instructed to add the following to the end of the first paragraph on page N-1 of the Notice to Bidders:</p> <p>In response to social distancing due to the COVID-19 virus, the front counter of 2850 Fairlane Court, Building C, Placerville, California is not currently staffed. If a contractor needs to submit their bid earlier than 12:30 PM on April 10, 2020, please contact Brian Franklin at 916-880-8535 to make bid submittal arrangements prior to arrival at the County Building. Department of Transportation (DOT) staff will be onsite at the front doors of the lobby at the above address to accept and time stamp bids received between 12:30 PM and 1:30 PM on April 10, 2020. Bids will be opened and read by DOT in the breezeway in front of the County Building at the above address, date, and time.</p>

Indicate receipt of this Addendum No. 2 by filling in the number of this Addendum in the space provided on the signature page of the Proposal. Holders who have already mailed their Proposal can contact Brian Franklin at 530-621-5311 (email: brian.franklin@edcgov.us) to arrange return of their Proposal. Inform all suppliers and subcontractors as necessary. The Community Development Services, Department of Transportation is only sending this Addendum by posting on QuestCDN's website at: <https://www.questcdn.com/>. You must be a Contract Documents holder on the Quest Plan Holder Report and comply with the requirements of this Addendum No. 2 when submitting your bid.

End of Addendum No. 2


John Kahling
Digitally signed by John Kahling
 DN: cn=John Kahling, o=El Dorado
 County Department of Transportation,
 ou=Headington Engineering Unit,
 email=john.kahling@edcgov.us, c=US
 Date: 2020.03.31 13:38:58 -0700

3-31-20

Recommended by:
 John Kahling, Deputy Director
 Headington Engineering Unit

Date

 FOR:



Approved by:
 Rafael Martinez, Director
 Community Development Services
 Department of Transportation

Date

ITEM NO.	ITEM CODE		ITEM DESCRIPTION	UNIT OF MEASURE	ESTIMATED QUANTITY	UNIT PRICE (IN FIGURES)	ITEM TOTAL (IN FIGURES)
20	141000A		TEMPORARY FENCE (TYPE ESA)	LF	2,000		
21	149001A		PREPARE FUGITIVE DUST CONTROL PLAN	LS	1		
22	170103		CLEARING AND GRUBBING (LS)	LS	1		
23	170703A		REMOVE TREE	EA	66		
24	190101	F	ROADWAY EXCAVATION	CY	1,670		
25	192020	F	STRUCTURE EXCAVATION (TYPE D)	CY	341		
26	192035	F	STRUCTURE EXCAVATION (ROCK)	CY	26		
27	193003	F	STRUCTURE BACKFILL (BRIDGE)	CY	245		
28	198010	F	IMPORTED BORROW (CY)	CY	2,260		
29	210280		ROLLED EROSION CONTROL PRODUCT (BLANKET)	SQFT	11,934		
30	210430		HYDROSEED	SQFT	11,934		
31	260203		CLASS 2 AGGREGATE BASE (CY)	CY	583		
32	390132		HOT MIX ASPHALT (TYPE A)	TON	835		
33	394074		PLACE HOT MIX ASPHALT DIKE (TYPE C)	LF	190		
34	394077		PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	224		
35	394090A		PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA) (OVERSIDE DRAIN)	SQYD	2		
36	394090B		PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA) (V-DITCH))	SQYD	111		
37	398200		COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	55		
38	490604		30" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	173		
39	490683		24" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	60		
40	500001	P	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	1		
41	510051	F	STRUCTURAL CONCRETE, BRIDGE FOOTING	CY	68		

ITEM NO.	ITEM CODE		ITEM DESCRIPTION	UNIT OF MEASURE	ESTIMATED QUANTITY	UNIT PRICE (IN FIGURES)	ITEM TOTAL (IN FIGURES)
23	170703A		REMOVE TREE	EA	66		
24	190101	F	ROADWAY EXCAVATION	CY	1,670		
25	192020	F	STRUCTURE EXCAVATION (TYPE D)	CY	341		
26	192035	F	STRUCTURE EXCAVATION (ROCK)	CY	26		
27	193003	F	STRUCTURE BACKFILL (BRIDGE)	CY	245		
28	198010	F	IMPORTED BORROW (CY)	CY	2,260		
29	210280		ROLLED EROSION CONTROL PRODUCT (BLANKET)	SQFT	11,934		
30	210430		HYDROSEED	SQFT	11,934		
31	260203		CLASS 2 AGGREGATE BASE (CY)	CY	583		
32	390132		HOT MIX ASPHALT (TYPE A)	TON	835		
33	394074		PLACE HOT MIX ASPHALT DIKE (TYPE C)	LF	190		
34	394077		PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	224		
35	394090A		PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA) (OVERSIDE DRAIN)	SQYD	2		
36	394090B		PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA) (V-DITCH))	SQYD	111		
37	398200		COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	55		
38	490604		30" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	173		
39	490683		24" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	60		
40	500001		PRESTRESSING CAST-IN-PLACE CONCRETE	LS	1		
41	510051	F	STRUCTURAL CONCRETE, BRIDGE FOOTING	CY	68		
42	510053	F	STRUCTURAL CONCRETE, BRIDGE	CY	109		
43	510054	F	STRUCTURAL CONCRETE, BRIDGE (POLYMER FIBER)	CY	132		
44	510094		STRUCTURAL CONCRETE, DRAINAGE INLET	CY	4		
45	519088	P	JOINT SEAL (MR=1")	LF	77		

Hanks Exchange Road at Squaw Hollow Creek Bridge Replacement
Contract No. 3916, CIP No. 77135
February 25, 2020

County of El Dorado
Proposal
Page P-4REV