

**Initial Study/
Mitigated Negative Declaration**

for the

**Hazel Valley Road at
El Dorado Canal Bridge (25C0092)
Replacement Project**

April 2015

**El Dorado County
Community Development Agency
Transportation Division
2850 Fairlane Court
Placerville, CA 95667**

[THIS PAGE INTENTIONALLY BLANK]

Table of Contents

1.	Project Information	1
2.	Introduction.....	3
3.	Project Description.....	4
3.1	Location.....	4
3.2	Project Purpose and Objectives.....	4
3.3	Project Description.....	5
3.4	Construction Contract	17
3.5	Project Schedule.....	18
4.	Initial Study Checklist and Supporting Documentation	19
4.1	Initial Study Checklist.....	19
4.2	Setting, Impacts, and Mitigation Measures	20
4.2.1	Aesthetics.....	20
4.2.2	Agricultural and Forestry Resources	21
4.2.3	Air Quality	23
4.2.4	Biological Resources	27
4.2.5	Cultural Resources	32
4.2.6	Geology and Soils.....	33
4.2.7	Greenhouse Gas Emissions.....	37
4.2.8	Hazards and Hazardous Materials	39
4.2.9	Hydrology and Water Quality.....	41
4.2.10	Land Use and Planning	43
4.2.11	Mineral Resources	44
4.2.12	Noise	44
4.2.13	Population and Housing.....	47
4.2.14	Public Services.....	48
4.2.15	Recreation	48
4.2.16	Transportation/Traffic.....	49
4.2.17	Utilities/ Service Systems	50
4.2.18	Mandatory Findings of Significance.....	51
5.	Determination	53

5.1	Environmental Factors Potentially Affected	53
6.	Report Preparation and References.....	54
6.1	Report Preparation.....	54
6.2	References	54

Appendices

Appendix A: Mitigation Monitoring and Reporting Plan

Appendix B: Comments and Responses

Figures

Figure 1.	Project Location Map	7
Figure 2.	Aerial Photograph.....	9
Figure 3.	Project Map	11
Figure 4.	Proposed Bridge Profile	13
Figure 5.	Proposed Roadway Plan and Profile	15

Tables

Table 1.	Construction Equipment and Use Assumptions.	25
Table 2.	Estimated Construction Emissions	26
Table 3.	Natural Communities in the Project area.....	28
Table 4.	Bird Species Protection Areas	30
Table 5.	Maximum allowable noise exposure for transportation noise sources (General Plan Table 6-1).....	45

1. Project Information

1. Project Title: Hazel Valley Road at El Dorado Canal Bridge (25C0092) Replacement Project
2. Lead Agency Name and Address: El Dorado County Community Development Agency, Transportation Division 2850 Fairlane Court Placerville, CA 95667
3. Contact Person and Phone Number: Ms. Janet Postlewait, Principal Planner 530/ 621-5993 janet.postlewait@edcgov.us
4. Project Location: <p>The Project is located along Hazel Valley Road approximately 0.5 mile south of Highway 50 and 5 miles east of the community of Pollock Pines in central El Dorado County, CA. The bridge is located approximately 1,000 ft due west of Esmeralda Creek on the Riverton USGS topographic quad (T11N, R13E, Section 35) and occurs in the South Fork American hydrologic unit (hydrologic unit code 18020129). Elevation in the Project area ranges from approximately 3,850 ft to 3,865 ft above sea level.</p> <p>The Project area includes portions of Hazel Valley Road, Ponderosa pine forest, and a segment of the concrete lined El Dorado Canal. The El Dorado Canal flows south through the Project area. The Project area is bound by Ponderosa pine forest on all sides. The General Plan land use designation for the parcel (APN 009-060-29-100) surrounding the Project area is natural resources and the zoning is timberland preserve.</p>
5. Description of Project: <p>El Dorado County Community Development Agency, Transportation Division, in conjunction with Caltrans and FHWA, is proposing to replace the Hazel Valley Road Bridge at the El Dorado Canal (25C0092). Hazel Valley Road in the Project area is a one lane rural road in mixed conifer forest on the west slope of the Sierra Nevada. The existing bridge built in 1940 is a single-span structure with a timber deck on steel girders and concrete abutments. The existing bridge is approximately 27.5 ft long and 10.8 ft wide (curb to curb).</p> <p>The proposed replacement bridge will be an approximately 54 ft long, 28 ft wide concrete slab bridge. The bridge will be installed on concrete abutments with cast in drilled hole (CIDH) piles. Concrete bridge rails are proposed. The new bridge will meet the AASHTO minimum standards for a “Resource Recovery Road” or a “Minor Access Road” (AASHTO 2001).</p> <p>The road will remain open during construction and motorists will make use of the existing bridge or a temporary bridge during construction. Pedestrian access along the canal berm will be maintained to facilitate canal inspection. The El Dorado Canal is owned and operated by the El Dorado Irrigation District (EID). The County will continue its coordination with EID prior to and during construction.</p>

6. General plan designation:

Natural Resources (NR, 1 DU per 40 ac below 3,000 ft elevation, 1 DU per 160 ac above 3,000 ft elevation)

7. Zoning:

Timberland Preserve Zone (TPZ)

8. Surrounding Land Uses and Setting:

Adjacent land use includes timber production. Hazel Valley Road is classified as an off-system, two-lane, local rural road in El Dorado County. The El Dorado Canal is a 22.3-mile long canal owned and operated by EID as part of the El Dorado Hydroelectric Project licensed by the Federal Energy Regulatory Commission (FERC). The El Dorado Canal is a manmade concrete-lined canal with a maximum flow capacity of 165 cubic feet per second that passes under Hazel Valley Road in the project area.

9. Other Public Agencies Whose Approval May Be Required (e.g., permits, financing approval, or participation agreement):

The Project may require permits or approvals from the following:

- Caltrans — National Environmental Policy Act (NEPA) Categorical Exclusion
- El Dorado County Air Quality Management District — Fugitive Dust Plan Approval

2. Introduction

The El Dorado County Community Development Agency, Transportation Division, (Transportation) intends to replace the existing Hazel Valley Road Bridge at the El Dorado Canal (25C0092) located in unincorporated El Dorado County. The existing single lane timber bridge structure was constructed in 1940.

El Dorado County is the local lead agency and prepared this Initial Study to consider the significance of potential project impacts pursuant to the California Environmental Quality Act (CEQA) of 1970, as amended (Public Resources Code, Section 21000, et seq.). This Initial Study was prepared in accordance with the State CEQA Guidelines (14 California Administrative Code, Section 14000 et seq.).

Based on the results of this Initial Study, the County has determined that the Project would have less than significant impacts on the environment with the incorporation of mitigation measures. The County may approve the Project with the certification of a Mitigated Negative Declaration (MND).

The remainder of this document is organized into the following sections:

- **Section 3, Project Description:** Provides a detailed description of the proposed Project;
- **Section 4, Initial Study Checklist and Supporting Documentation:** Provides CEQA Initial Study Resource impact checklists and supporting documentation. Identifies the thresholds of significance, evaluates potential impacts, and describes mitigation necessary to reduce impact significance;
- **Section 5, Initial Study Findings:** Provides a determination of the County's CEQA findings;
- **Section 6, Supporting Information Sources:** Identifies the personnel responsible for the preparation of this document and provides a list of the references cited throughout the document.
- **Appendix A, Mitigation Monitoring and Reporting Plan:** Contains the Mitigation Monitoring and Reporting Plan prepared for the proposed project. The Mitigation Monitoring and Reporting Plan includes a list of required mitigation measures and includes information regarding the County's policies and procedures for implementation and monitoring of the mitigation measures.

3. Project Description

3.1 Location

The Project area is located along Hazel Valley Road approximately 0.5 mile south of Highway 50 and 5 miles east of the community of Pollock Pines in central El Dorado County (Figures 1 and 2). The bridge crosses the El Dorado Canal between Ditch Camp Three and Ditch Camp Four and is approximately 1,000 ft west of Esmeralda Creek. The Project occurs on the Riverton USGS topographic quad (T11N, R13E, Section 35) and is in the South Fork American hydrologic unit (hydrologic unit code 18020129). Elevation in Project area ranges from approximately 3,850 ft to 3,865 ft above sea level.

3.2 Project Purpose and Objectives

The purpose of the Project is to replace the existing Hazel Valley Road Bridge (25C0092) at EID Canal. Project objectives include improving roadway safety, reducing annual maintenance costs, increase the life of the bridge, compliance with the American Association of State Highway and Transportation Officials (AASHTO) guidelines, and compliance with El Dorado County standards. This Project is identified in the El Dorado County Capital Improvement Program as project # 77125 (El Dorado County 2013).

Replacement of the structure is necessary due to the following deficiencies (El Dorado County 2014a):

- **Service Life:** The existing bridge is 74 years old (at present). The assumed service life is 75 years.
- **Unknown Abutment Reinforcement/Strength:** The type and strength of the existing abutment supports is unknown.
- **Sub-Standard Width/Functionally Obsolete Classification:** The 2013 Caltrans bridge inspection report states the bridge is “Functionally Obsolete” because the existing clear width between railings is 10-feet 10-inches which is less than the two way existing approach roadway widths of 20-feet
- **Substandard Wheel Guards and Railings:** As noted in the 2013 Caltrans bridge inspection report and County bridge maintenance reports the existing timber wheel guards and timber railings and posts are hit by vehicles numerous times each year and require repair by County Bridge Maintenance staff at least twice a year historically.
- **Gravel, Dirt Debris and Accelerating Dry Rot Issues:** Vehicles using the bridge track dirt and debris onto the bridge deck. The gravel and dirt tend to retain moisture thus accelerating dry rot and shortening the design life of the timber. Dirt and debris also filters down through the openings in the timber deck which contributes to the corrosion of the supporting I-beam superstructure.
- **Substandard Approach Roadway Geometrics and Sight Distance:** The approach roadway does not meet AASHTO requirements for minimum horizontal and vertical curve radius and sight distance.
- **Seismic Analysis and Retrofit:** The Hazel Valley Road Bridge was constructed before modern bridge seismic codes had been developed. Bridges constructed during this time typically were not designed to satisfy current seismic requirements.



3.3 Project Description

The existing bridge built in 1940 is a single-span structure with a timber deck on steel girders and concrete abutments. The existing bridge is approximately 27.5 ft long and 10.8 ft wide (curb to curb). The proposed replacement bridge will be an approximately 54 ft long, 28 ft wide concrete slab bridge. The bridge will be installed on concrete abutments with cast in drilled hole (CIDH) piles. The piles may be 10 ft deep, depending on the results of the geotechnical study. Concrete bridge rails are proposed. Figure 3 shows the proposed project and Figures 4 and 5 include the current proposed plan and profile design sheet. The new bridge will meet the AASHTO minimum standards for a “Resource Recovery Road” or a “Minor Access Road” (AASHTO 2001).

The road will remain open during construction and motorists will make use of the existing bridge or a temporary bridge during construction. The County is evaluating several alignments for the new bridge. The replacement bridge may be constructed along its existing alignment, requiring the installation of a temporary bridge (likely to the south of the existing bridge); or the replacement bridge may be constructed north of its existing alignment, allowing the existing bridge to serve as access during construction. Both alignments will have similar environmental impacts; neither alignment will encroach on the canal. Pedestrian access along the canal berm will be maintained to facilitate canal inspection. The El Dorado Canal is owned and operated by the El Dorado Irrigation District (EID). The County will continue its coordination with EID prior to and during construction.

The demolition of the existing bridge will be completed by the construction contractor. The contractor will likely use jack-hammers, excavators, and/or cranes. Netting, tarps or platforms may be used during demolition to prevent debris from entering the canal. Debris will be removed from the project area and disposed of properly.


[THIS PAGE INTENTIONALLY BLANK]



Hazel Valley Road Bridge (25C-0092)
 at El Dorado Canal
 El Dorado County, CA
 19 September 2014

Figure 1. Location Map

● Project Location




Riverton, CA (Revised 1973)
 USGS 7.5' Quadrangle DRG
 CASIL California Digital Raster Graphics,
 7.5 Minute (C) Series, Albers Nad83 Mosaics (MrSID)

[THIS PAGE INTENTIONALLY BLANK]



Hazel Valley Road Bridge (25C-0092)
 at El Dorado Canal
 El Dorado County, CA
 19 September 2014




● Project Location

Aerial Photograph: 14 August 2011
 UC-G Imagery, US-CA-Placerville, Microsoft
 ESRI ArcGIS Basemap Layer

Figure 2. Aerial Photograph


[THIS PAGE INTENTIONALLY BLANK]



Hazel Valley Road Bridge (25C-0092)
 at El Dorado Canal
 El Dorado County, CA
 1 October 2014

Figure 3. Proposed Project Map


- Biological Study Area (BSA)
- Natural Community Boundary
- Permanent Impacts
- Temporary Impacts
- Road and Bridge Improvements
- Limits of Grading
- ESA Fence
- PPF Ponderosa Pine Forest



Proposed Road and Bridge Alignment:
 Master.dwg (24 September 2014)
 El Dorado County Dept. of Transportation
 Aerial Photograph: 14 August 2011
 UC-G, UC-CA-Placerville, Microsoft Imagery
 Basemap Layers: El Dorado County
 GIS Parcel and Road datasets

[THIS PAGE INTENTIONALLY BLANK]

FOR REDUCED PLANS: SCALE: 1" = 10' HORIZES
 COUNTY OF EL DORADO, HAZEL VALLEY AT EID CANAL, PROJECT # 2011-001, DRAWING # 2011-001-001, DATE: 03/20/14, 3:55pm, D:\elc\elc



PROFILE
BRIDGE No. 25C-0092

NOTES:
 EXISTING BRIDGE-10x26
 BRIDGE REPLACEMENT-26x48

Figure 4: Proposed Bridge Profile

NO.	DATE	DESCRIPTION	BY

PRELIMINARY

BRIDGE No. 25C-0092
SCALE: 1" = 2'

PREPARED UNDER THE SUPERVISION OF: REGISTERED CIVIL ENGINEER	DESIGNED: MP CHECKED: MP DRAWN: RR DATE: 1/28/14 DRAW NUMBER: 2-603		COUNTY OF EL DORADO COMMUNITY DEVELOPMENT AGENCY TRANSPORTATION DIVISION	HAZEL VALLEY ROAD AT EID CANAL BRIDGE REPLACEMENT	SHEET EXHIBIT 1 OF 1 77125
---	---	--	--	--	--

[THIS PAGE INTENTIONALLY BLANK]

[THIS PAGE INTENTIONALLY BLANK]

3.4 Construction Contract

Transportation would retain a construction contractor to construct the proposed improvements. The contractor would be responsible for compliance with all applicable rules, regulations, and ordinances associated with proposed Project activities and for implementing construction-related mitigation measures. Transportation would provide construction contractor oversight and management and would be responsible for verifying implementation of the mitigation measures. The contractor would construct the proposed Project in accordance with the Public Contract Code of the State of California, the State of California Department of Transportation Standard Plans and Standard Specifications, and the Contract, Project Plans, and Project Special Provisions under development by Transportation. The following are a combination of standard and project-specific procedures/requirements applicable to Project construction:

- Construction contract special provisions will require that a Traffic Management Plan be prepared. The Traffic Management Plan will include construction staging and traffic control measures to be implemented during construction to maintain and minimize impacts to traffic during construction. The Traffic Management Plan will address the coordination issues;
- Contract special provisions will require compliance with El Dorado County Air Quality Management District (AQMD) Rules 223, 223-1, and 223-2 to minimize fugitive dust emissions;
- Contract provisions will require notification of Transportation and compliance with California Health and Safety Code Section 7050.5 and California Public Resources Code Sections 5097.5, 5097.9 et seq., regarding the discovery and disturbance of cultural materials or human remains should any be discovered during project construction;
- Contract provisions will require implementation of best management practices (BMPs) consistent with the Caltrans Stormwater Quality Handbooks to protect water quality and minimize the potential for siltation and downstream sedimentation.
- Transportation or its construction contractors will conduct early coordination with utility service providers, law enforcement and emergency service providers to ensure minimal disruption to service during construction;
- Transportation and its construction contractors will comply with the current State of California Standard Specifications written by the State of California Department of Transportation, for public service provision; and
- The Project would comply with El Dorado County General Plan Policy 6.5.1.11 pertaining to construction noise.
- The County will install ESA fencing as shown in the Caltrans approved Cultural Resources documents.
- Contract provisions will require the existing paint system be handled in accordance with Caltrans Standard Special Provisions for removal of lead paint (Provision 14-11.08, Disturbance of Existing Paint Systems on Bridges).

- Contract provisions will require ACM be handled in accordance with Caltrans Non-Standard Special Provisions for 14-11.11, Management of Asbestos Containing Materials.

3.5 Project Schedule

Transportation expects to construct the Project in fiscal year 2017/2018.

4. Initial Study Checklist and Supporting Documentation

4.1 Initial Study Checklist

This section of the Initial Study incorporates the Environmental Checklist contained in Appendix G of the CEQA Guidelines. Each resource topic section provides a determination of potential impact and an explanation for the checklist impact questions. The following 18 environmental categories are addressed in this section:

• Aesthetics	• Land Use and Planning
• Agricultural and Forestry Resources	• Mineral Resources
• Air Quality	• Noise
• Biological Resources	• Population and Housing
• Cultural Resources	• Public Services
• Geology and Soils	• Recreation
• Greenhouse Gas Emission	• Transportation/Traffic
• Hazards and Hazardous Materials	• Utilities/ Service Systems
• Hydrology and Water Quality	• Mandatory Findings of Significance

Each of the above listed environmental categories was fully evaluated and one of the following four determinations was made for each checklist question:

- **“No Impact”** means that no impact to the environment would occur as a result of implementing the Project.
- **“Less than Significant Impact”** means that implementation of the Project would not result in a substantial and/or adverse change to the environment and no mitigation is required.
- **“Potentially Significant Unless Mitigation is Incorporated”** means that the incorporation of one or more mitigation measures would reduce the impact from potentially significant to less than significant.
- **“Potentially Significant Impact”** means that there is either substantial evidence that a project-related effect would be significant or, due to a lack of existing information, could have the potential to be significant.

4.2 Setting, Impacts, and Mitigation Measures

4.2.1 Aesthetics

	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
I. AESTHETICS—Would the project:				
a) Have a substantial adverse effect on a scenic vista?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b) Substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c) Substantially degrade the existing visual character or quality of the site and its surroundings?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d) Create a new source of substantial light or glare which would adversely affect day or nighttime views in the area?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Environmental Setting

The Project occurs in the Sierra Nevada, at an elevation ranging from of approximately 3,850 ft to 3,865 ft above sea level. The Project is located in rural setting in unincorporated El Dorado County. The Project area includes unpaved/ ruderal areas, paved portions Hazel Valley Road, Ponderosa pine forest, and a segment of the concrete lined El Dorado Canal.

Potential Environmental Effects

- a) ***Less Than Significant Impact.*** Visual resources consist of two categories: scenic views and scenic resources. As per CEQA Checklist, Scenic resources are described as specific features of a viewing area (or viewshed) such as trees, rock outcroppings, and historic buildings. Scenic views are elements of the broader view shed such as mountain ranges, valleys, and ridgelines. A scenic vista refers to the view of an area that is visually or aesthetically pleasing.

Table 5.3-1 of the General Plan EIR identifies multiple scenic views and resources in the County (El Dorado County 2004a). Hazel Valley Road is not identified in Table 5.3-1 of the General Plan EIR. Hazel Valley Road is not a state designated scenic highway.

U.S. 50 is a State designated scenic highway from Placerville to South Lake Tahoe. At its closest, U.S. 50 is 0.48 mi from the Hazel Valley Road Bridge. The bridge is over 400 ft higher in elevation than the highway. It cannot be seen from the highway due to terrain and tall trees.

The Project consists of replacement of an existing bridge. The replacement bridge will be visually consistent with the existing structure and other transportation infrastructure in the vicinity of the Project. Impacts to the scenic resources are considered less-than significant.

- b) ***Less Than Significant Impact.*** See discussion of a) above.
- c) ***Less Than Significant Impact.*** See discussion of a) and b) above.
- d) ***No Impact.*** The Project does not introduce any new source of light or glare.

4.2.2 Agricultural and Forestry Resources

II. AGRICULTURE AND FORESTRY—In determining whether impacts to agricultural resources are significant environmental effects, lead agencies may refer to the California Agricultural Land Evaluation and Site Assessment Model (1997) prepared by the California Dept. of Conservation as an optional model to use in assessing impacts on agriculture and farmland. In determining whether impacts to forest resources, including timberland, are significant environmental effects, lead agencies may refer to information compiled by the California Department of Forestry and Fire Protection regarding the state’s inventory of forest land, including the Forest and Range Assessment Project and the Forest Legacy Assessment project; and forest carbon measurement methodology provided in Forest Protocols adopted by the California Air Resources Board. Would the project::

	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less Than Significant Impact	No Impact
a) Convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Conflict with existing zoning for agricultural use, or a Williamson Act contract?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Conflict with existing zoning for, or cause rezoning of, forest land (as defined in Public Resources Code section 12220(g)), timberland (as defined by Public Resources Code section 4526), or timberland zoned Timberland Production (as defined by Government Code section 51104(g))?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Result in the loss of forest land or conversion of forest land to non-forest use?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
e) Involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use or conversion of forest land to non-forest use?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Environmental Setting

The Project is located in a rural area in the Sierra Nevada. The Project area is mapped as ‘Other Land’ by the States Farmland Mapping and Monitoring Program (California Department of Conservation 2014c). ‘Other Land’ is ‘land not included in any other mapping category. Common examples include low density rural developments, brush, timber, wetland, and riparian areas not suitable for livestock grazing...’. No Prime Farmland, Unique Farmland, Farmland of Statewide Importance, or lands under Williamson Act contracts occur in the project area. The Project area is located in the area identified as ‘Timber Production Zone’ on Exhibit 5.2-4 (Timber Production Zones) of the County General Plan EIR (El Dorado County 2004a).

Potential Environmental Effects

- a) ***No Impact.*** No Prime Farmland, Unique Farmland, Farmland of Statewide Importance, or lands under Williamson Act contracts occur in the project area.
- b) ***No Impact.*** See response for item a).
- c) ***No Impact.*** The Project area is located in the area identified as ‘Timber Production Zone’ on Exhibit 5.2-4 (Timber Production Zones) of the County General Plan EIR (El Dorado County 2004a). County General Plan policies applicable to the project include:

“Policy 8.3.1.1: Lands suitable for timber production which are designated Natural Resource (NR) on the General Plan land use map and zoned Timber Production Zone (TPZ) or Forest Resource (FR) are to be maintained for the purposes of protecting and encouraging the production of timber and associated activities.

Policy 8.3.2.1: Lands zoned Timber Production Zone (TPZ) shall not be subdivided into parcels containing less than 160 acres.

Policy 8.4.2.1: The County Agricultural Commission shall evaluate all discretionary development applications involving identified timber production lands which are designated Natural Resource or lands zoned Timberland Production Zone (TPZ) or lands adjacent to the same and shall make recommendations to the approving authority. Prior to granting an approval, the approving authority shall make the following findings:

- A. The proposed use will not be detrimental to that parcel or to adjacent parcels for long-term forest resource production value or conflict with forest resource production in that general area;
- B. The proposed use will not intensify existing conflicts or add new conflicts between adjacent proposed uses and timber production and harvesting activities;
- C. The proposed use will not create an island effect wherein timber production lands located between the project site and other non-timber production lands are negatively affected;
- D. The proposed use will not hinder timber production and harvesting access to water and public roads or otherwise conflict with the continuation or development of timber production harvesting; and
- E. The proposed use will not significantly reduce or destroy the buffering effect of existing large parcel sizes adjacent to timber production lands.”

The proposed Project is consistent with the existing zoning, General Plan policies 8.3.1.1, 8.3.2.1, and 8.4.2.1, and does not include any rezoning activities.

- d) ***Less Than Significant Impact.*** The proposed Project will result in temporary and permanent impacts forest land (as defined in Public Resources Code section 12220(g)). Temporary impact to approximately 0.348 ac of forest land will result from trees and vegetation removal to allow construction access. Approximately 0.057 ac of Ponderosa pine forest will be permanently affected by construction of the replacement bridge. The permanent loss of less than one-tenth of

an acre (0.057 ac) of forest land (as defined in Public Resources Code section 12220(g)) is considered less than significant.

- e) **No Impact.** Excluding vegetation impacts the project is not anticipated to involve other changes in the existing environment that could result in conversion of farmland or forest land.

4.2.3 Air Quality

III. AIR QUALITY— Where available, the significance criteria established by the applicable air quality management or air pollution control district may be relied upon to make the following determinations. Would the project:

	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
a) Conflict with or obstruct implementation of the applicable air quality plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Violate any air quality standard or contribute substantially to an existing or projected air quality violation?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c) Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard (including releasing emissions which exceed quantitative thresholds for ozone precursors)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Expose sensitive receptors to substantial pollutant concentrations?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
e) Create objectionable odors affecting a substantial number of people?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Environmental Setting

The project area is located in the Mountain Counties Air Basin (MCAB). The San Francisco Bay Area Air Basin and the Sacramento Valley Air Basin are located to the west, and the San Joaquin Valley Air Basin is located to the south. Climate in the MCAB relate to elevation and proximity to the Sierra Ridge. Precipitation is greater and temperatures are lower at higher elevations. Summer temperatures in the project area are in the mid- to upper nineties. Winter temperatures are in the upper thirties to lower forties.

The air quality of a region is determined by the air pollutant emissions (quantities and type of pollutants measured by weight) and by ambient air quality (the concentration of pollutants within a specified volume of air). Air pollutants are characterized as primary and secondary pollutants. Primary pollutants are those emitted directly into the air, for example carbon monoxide (CO), and can be traced to a single pollutant source. Secondary pollutants are those pollutants that form through chemical reactions in the atmosphere, for example reactive organic gasses (ROG) and nitrogen oxides (NO_x) combine to form ground level ozone, or smog.

Congress established much of the basic structure of the Clean Air Act in 1970, and made major revisions in 1977 and 1990. The Federal Clean Air Act established national ambient air quality standards (NAAQS). These standards are divided into primary and secondary standards. Primary standards are designed to protect public health and secondary standards are designed to protect other values. Because of

the health-based criteria identified in setting the NAAQS, the air pollutants are termed “criteria” pollutants. California has adopted its own, more stringent, ambient air quality standards (CAAQS).

The Mountain Counties Air Basin portion of El Dorado County is currently nonattainment for the national 8-hour ozone and PM 2.5 standards. The Mountain Counties Air Basin portion of El Dorado County is nonattainment for the following CAAQS: 8-Hour Ozone, 1-Hour Ozone, and 24-Hour PM10.

The El Dorado County Air Quality Management District (AQMD) administers the state and federal Clean Air Acts in accordance with state and federal guidelines. The AQMD regulates air quality through its district rules and permit authority. It also participates in planning review of discretionary project applications and provides recommendations. The following District rules apply to the Project:

- **Rule 205 (Nuisance):** Prohibits the discharge of air containments which cause injury, detriment, nuisance, or annoyance.
- **Rule 207 (Particulate Matter):** Limits the quantity of PM through concentration limits.
- **Rule 215 (Architectural Coatings):** Defines the quantities of reactive organic compounds permitted for use in new construction.
- **Rule 223 (Fugitive Dust):** The purpose of this rule is to reduce the amount of particulate matter entrained in the ambient air as a result of anthropogenic (man-made) fugitive dust sources by requiring actions to prevent, reduce or mitigate fugitive dust emissions.
- **Rule 223-1 (Fugitive Dust – Construction):** Requires a Fugitive Dust Control Plan be prepared and submitted to the El Dorado County AQMD prior to ground disturbing activities. Pursuant to Rule 610, the El Dorado County AQMD charges a fee to review the Fugitive Dust Control Plan required by Rule 223-1.
- **Rule 223-2 (Fugitive Dust – Asbestos Hazard Mitigation):** The purpose of this Rule is to reduce the amount of asbestos particulate matter entrained in the ambient air as a result of any construction or construction related activities, that disturbs or potentially disturbs naturally occurring asbestos by requiring actions to prevent, reduce or mitigate asbestos emissions.
- **Rule 224 (Cutback and Emulsified Asphalt Paving Materials):** Limits emissions of ROG's from the use of cutback and emulsified asphalt paving materials, paving, and maintenance operations.
- **Rule 233 (Stationary Internal Combustion Engines):** Limits emissions of NOx and CO from stationary internal combustion engines. (This rule applies to any stationary internal combustion engine rated at more than 50 brake horsepower, operated on any gaseous fuel or liquid fuel, including liquid petroleum gas (LPG), gasoline, or diesel fuel.)

El Dorado County AQMD’s Guide to Air Quality Assessment (2002) specifies specific daily emissions thresholds that can be used to determine the significance of project emissions. The El Dorado County AQMD considers a significant cumulative impact to occur if the project requires a change in the existing land use designation (i.e., general plan) and would individually exceed the project-level thresholds of significance. Thresholds of significance for specific pollutants of concern are as follows:

- ROG: 82 lbs/day
- NOx: 82 lbs/day
- PM10: AAQS

Potential Environmental Effects

As recommended in the *El Dorado County AQMD Guide to Air Quality Assessment* construction emissions were estimated for the Project using the Sacramento Metropolitan Air Quality Management District’s *Road Construction Emissions Model (RCEM), Version 7.1.5.1*. The RCEM was developed to estimate emissions from linear projects types including road and bridge construction. The RCEM divides the project into four ‘Construction Periods:

- Grubbing/ Land Clearing
- Grading/Excavation
- Drainage/Utilities/Sub-Grade
- Paving

Based on similar County road and bridge projects the assumptions presented in Table 1, regarding type of construction equipment and use duration, were used in the RCEM. Other Project assumptions used in the RCEM include a total four month construction schedule starting in 2018, use of water trucks, and a daily soil import/ export volume of 100 cubic yards. Results of the RCEM based on the Project assumptions are in Table 2.

Table 1. Construction Equipment and Use Assumptions.

Construction Period	Equipment		Hours per Day Used	Days In Use During Construction Period (Applies to all Equipment)
	Quantity	Type		
Grubbing/ Land Clearing	1	Excavator	5	8
	1	Backhoe	2	
	1	Bulldozer	4	
	1	Dump Truck	4	
	1	Signal Board	8	
Grading/Excavation	1	Excavator	5	8
	1	Backhoe	2	
	1	Bulldozer	4	
	1	Signal Board	8	
Drainage/Utilities/Sub-Grade	1	Backhoe	2	5
	1	Roller	4	
	1	Water Truck	4	
	1	Signal Board	8	
Paving	1	Roller	4	5
	1	Water Truck	4	
	1	Signal Board	8	

Table 2. Estimated Construction Emissions

Project Phases	ROG lbs/day	CO lbs/day	NOx lbs/day	PM10 lbs/day	Exhaust PM10 lbs/day	Fugitive Dust PM10 lbs/day
Grubbing/land clearing	1.0	6.4	8.7	31.2	0.4	15.0
Grading/excavation	1.1	8.0	11.1	31.3	0.5	15.0
Drainage/utilities/sub-grade	2.1	13.4	14.0	31.8	1.0	15.0
Paving	1.1	8.6	8.6	0.5	0.5	-
Maximum lbs/day	2.1	13.4	14.0	31.8	1.0	15.0
Significance Threshold	82	AAQS	82	AAQS	N/A	N/A
Significant?	No	No	No	No	N/A	N/A

Notes: Data entered to emissions model: Project Start Year: 2018; Project Length (months): 4; Total Project Area (acres): 3.088; Total Soil Imported/Exported (yd³/day): 100. PM10 estimates assume 50% control of fugitive dust from watering and associated dust control measures. Total PM10 emissions are the sum of *exhaust* and *fugitive dust* emissions.

- a) **No Impact.** The proposed Project is identified in the Sacramento Council of Governments’ *Metropolitan Transportation Plan/Sustainable Communities Strategy 2035* (Sacramento Council of Governments 2012). Projects included in the Metropolitan Transportation Plan have been determined to be consistent with the planning goals of the State Implementation Plan.
- b) **Less Than Significant Impact.** El Dorado County is in nonattainment status for both federal and state ozone standards and the state PM10 standard. Construction activities would result in short-term increases in emissions from the use of heavy equipment that generate dust, exhaust, and tire-wear emissions and from paints and coatings.

Project construction would create short-term increases in ROG, NOx, and PM10 emissions from vehicle and equipment operation. The RCEM estimates are below the County’s significance threshold of 82 lbs/ day each for of ROG and NOx. As per Chapter 4 of the *El Dorado County AQMD Guide to Air Quality Assessment*, if ROG and NOx emissions are below the threshold values (not significant) then CO and PM10 emissions from construction equipment, and exhaust emissions of all constituents from worker commute vehicles are also not significant. The Project would not generate additional traffic on Hazel Valley Road. No operational emissions will result from the Project.
- c) **No Impact.** Cumulative net increases of criteria pollutants have been evaluated in the *Metropolitan Transportation Plan/Sustainable Communities Strategy 2035* (SACOG 2012). This Project is referenced and evaluated in the *Metropolitan Transportation Plan/Sustainable Communities Strategy 2035*. Also see the response for item b.
- d) **Less Than Significant Impact.** The Project is located in a rural area and no sensitive receptors (people, or facilities that generally house people; schools, hospitals, residences, etc.) are known to occur within 0.25 mile of the Project. Impacts are considered less than significant due to the limited nature of the Project and short-term construction period.

The Project is not located within an area known to contain naturally occurring asbestos (NOA) or an area “more likely to contain naturally occurring asbestos” (California Department of Conservation 2000, El Dorado County 2005).

- e) **Less Than Significant Impact.** Construction activities would involve the use of construction equipment and asphalt paving, which have distinctive odors. Odors are considered less than significant because of the limited number of the public affected and the short-term nature of the emissions.

4.2.4 Biological Resources

IV. BIOLOGICAL RESOURCES—Would the project:	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less Than Significant Impact	No Impact
a) Have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Game or U.S. Fish and Wildlife Service?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
b) Have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Game or US Fish and Wildlife Service?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Have a substantial adverse effect on federally protected wetlands as defined by Section 404 of the Clean Water Act (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d) Interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
e) Conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f) Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Environmental Setting

Potential impacts to biological and wetlands resources were evaluated in the Project’s Natural Environment Study Minimal Impacts (NES MI; Sycamore Environmental 2014). The NES MI is a standard Caltrans report format for documenting and evaluating the potential Project impacts to biological resources from projects of limited scope and impact. The NES MI concludes the following regarding biological resources:

- The Project area does not provide habitat for federal-listed wildlife or plant species. There is no critical habitat in the Project area and the Project will not affect critical habitat.
- The Project area does not provide habitat for federal-listed anadromous salmonids.
- The Project area does not contain essential fish habitat (EFH) for Pacific salmon.
- The Project will not result in the ‘take’ of state-listed species or species proposed for listing.
- The Project area provides suitable habitat for birds of prey and birds protected under the Migratory Bird Treaty Act (MBTA).
- The Project area provides suitable habitat for 3 special-status plants ranked by the California Native Plant Society (CNPS). No rare plants were observed during a botanical survey conducted during the evident and identifiable period for special-status plants with potential to occur in the Project area.
- The Project will not impact potential Clean Water Act, Section 404 jurisdictional wetlands or waters of the U.S.

Biological communities that occur in the Project area are shown in Table 3 (Sycamore Environmental 2014). No sensitive natural communities occur in the Project area. A seasonal wetland occurs approximately 10 feet south of and outside the southern Project boundary.

Table 3. Natural Communities in the Project area

Biological Community	Acreage ¹	Temporary Impact (ac)	Permanent Impact (ac)
Ponderosa Pine Forest <i>Pinus ponderosa</i> Forest Alliance CDFW Alliance Code 87.010.000 (G5S4) ²	2.122	0.348	0.057
El Dorado Canal	0.155	--	--
Unpaved/ Ruderal	0.579	0.253	0.056
Paved Roads	0.221	--	--
Total	3.077	0.601	0.113

¹ Acres calculated using AutoCAD® functions.

² Alliance code and rarity rank (G5S4) are from the most recent CDFW list of vegetation alliances and natural communities. State (S) ranks of 1-3 are considered highly imperiled by CDFW (2010b).

The seasonal wetland located adjacent to and outside the southern Project boundary is approximately 20 foot by 20 foot. Small arroyo willows grow in and around the seasonal wetland and the understory is dominated by fragile-sheathed sedge and cutleaf blackberry.

The Ponderosa pine forest community in the Project Area contains black oak trees. El Dorado County General Plan Policy 7.4.4.4 regulates oak canopy including oak trees occurring outside of oak woodlands.

Public road safety projects, including the Hazel Valley Road at the El Dorado Canal Bridge Replacement Project are exempt from Policy 7.4.4.4.

Potential Environmental Effects

- a) ***Potentially Significant Unless Mitigation Incorporated.*** The Project area does not provide habitat for federal-listed wildlife or plant species. There is no critical habitat in the Project area and the Project will not affect critical habitat. The Project will not result in the ‘take’ of state-listed species or species proposed for listing.

The Project area provides potential nesting habitat for birds of prey and birds listed by the Migratory Bird Treaty Act (MBTA) of 1918 (16 U.S.C. 703-711). BIO-1 will be implemented to avoid impacts to birds of prey and birds listed by the MBTA.

Measure BIO-1

Under the MBTA, nests that contain eggs or unfledged young are not to be disturbed during the breeding season. Nesting or attempted nesting by migratory birds and birds-of-prey is anticipated from 1 February through 31 August.

Swallow

In California, bridge-nesting swallows typically arrive in mid-February, increase in numbers until late March, and remain until October. Nesting begins in April, peaks in June, and continues into August. Measures should be taken to prevent establishment of cliff swallow nests prior to construction. Techniques to prevent nest establishment include using exclusion devices, removing and disposing of partially constructed and unoccupied nests of migratory or nongame birds on a regular basis to prevent their occupation, or perform any combination of these. This can be done by:

- *The contractor can visit the site weekly and remove partially completed nests using either hand tools or high pressure water; and/or*
- *Hang netting from the bridge before nesting begins. If this technique is used, netting should be in place from late February until project construction begins.*

Birds of Prey and Birds Protected by the Migratory Bird Treaty Act

- *If construction begins outside the 1 February to 31 August breeding season, there will be no need to conduct a preconstruction survey for active nests.*
- *Trees scheduled for removal should be removed during the non-breeding season from 1 September to 31 January.*
- *If construction is scheduled to begin between 1 February and 31 August, a biologist shall conduct a survey for active bird of prey nests within 250 ft and active MTBA bird nests within 100 ft of the BSA from publicly accessible areas within one week prior to construction. The measures listed below shall be implemented based on the survey results.*

No Active Nests Found:

- *If no active nest of a bird of prey, MBTA bird, or other CDFW protected bird is found, then no further avoidance and minimization measures are necessary.*

Active Nests Found:

- *If an active nest of a bird of prey, MBTA bird, or other CDFW protected bird is discovered that may be adversely affected by construction activities or an injured or killed bird is found, immediately:*
 1. *Stop all work within a 100-ft radius of the discovery.*
 2. *Notify the Engineer.*
 3. *Do not resume work within the 100-ft radius until authorized.*
- *The biologist shall establish a minimum 250-ft Environmentally Sensitive Area (ESA) around the nest if the nest is of a bird of prey, and a minimum 100-ft ESA around the nest if the nest is of an MBTA bird other than a bird of prey.*

Table 4. Bird Species Protection Areas

<i>Protected Bird Type</i>	<i>Size of Protection Area (ESA)</i>
<i>Bird of prey</i>	<i>250 ft no-disturbance buffer</i>
<i>MBTA protected bird (not bird of prey)</i>	<i>100 ft no-disturbance buffer</i>

- *Activity in the ESA will be restricted as follows:*
 1. *Do not enter the ESA unless authorized.*
 2. *If the ESA is breached, immediately:*
 - a. *Secure the area and stop all operations within 60 feet of the ESA boundary.*
 - b. *Notify the Engineer.*
 3. *If the ESA is damaged, County determines what efforts are necessary to remedy the damage and who performs the remedy.*
- *No construction activity will be allowed in the ESA until the biologist determines that the nest is no longer active, or unless monitoring determines that a smaller ESA will protect the active nest.*
- *The size of an ESA may be reduced if the biologist monitors the construction activities and determines that no disturbance to the active nest is occurring. Reduction of ESA size depends on the species of bird, the location of the nest relative to the project, project activities during the time the nest is active, and other project-specific factors.*
- *Between 1 February and 31 August, if additional trees or shrubs need to be trimmed and/or removed after construction has started, a survey will be conducted for active nests in the area to be affected. If an active nest is found, the above measures will be implemented.*
- *If an active nest is identified in or adjacent to the construction zone after construction has started, the above measures will be implemented to ensure construction is not causing disturbance to the nest.*

The Project area provides suitable habitat for 3 special-status plants ranked by the California Native Plant Society (CNPS). These species were not observed in the Project during a botanical survey conducted during the evident and identifiable period. No impact will occur.

- b) **No Impact.** No sensitive natural communities occur in the Project area. The Project will not impact potential Clean Water Act, Section 404 jurisdictional wetlands or waters of the U.S.
- c) **Less Than Significant Impact.** The Project has been designed to avoid impacts to potential water of the U.S. including wetlands as defined by Section 404 of the Clean Water Act. The seasonal wetland located adjacent to and outside the southern Project boundary will be avoided and no impacts are anticipated. Implementation of BIO-2 will further reduce potential impacts to the seasonal wetland located adjacent to an outside the southern Project boundary.

Measure BIO-2

- *Temporary fencing will be installed between the construction limits and the seasonal wetland.*
 - *Signs will be posted on the fencing notifying the construction crew that the area beyond is an Environmentally Sensitive Area (ESA) and that no personnel or equipment pass beyond the fencing.*
 - *Water-permeable erosion control measures will be installed along the temporary fence line to ensure that sediment does not migrate south of the fence.*
 - *The temporary fencing and water-permeable erosion control measures will be in place prior to commencement of construction.*
- d) **Less Than Significant Impact.** The Project area is not located within a County-designated Important Biological Corridor (El Dorado County 2004b). Construction of the project could temporarily disrupt movement of native wildlife species that occur in or adjacent to the Project area. Daytime construction activities will result in minimal disruption of nocturnal wildlife movement. If nighttime construction activities would alleviate traffic congestion and safety hazards it would comply with the noise standards for construction activities General Plan Policy 6.5.1.11. The lack of nearby development provides ample space for wildlife to easily avoid the construction site. Although construction disturbance may temporarily hinder wildlife movements within the project area, the impact is less than significant due to its short-term nature.
 - e) **No Impact.** The Project area does not include oak woodlands. The Ponderosa pine forest community in the Project Area contains black oak trees. El Dorado County General Plan Policy 7.4.4.4 regulates oak canopy including oak trees occurring outside of oak woodlands. Public road safety projects, including the Hazel Valley Road at the El Dorado Canal Bridge Replacement Project are exempt from Policy 7.4.4.4.
 - f) **No Impact.** The Project is not located in an area covered by a habitat or natural community conservation plan. El Dorado County is currently preparing an Integrated Natural Resources Management Plan to identify important habitats in the county and establish a program for the management and preservation of these areas. The plan is still in process and is not anticipated to be adopted until after this Project has been completed.

4.2.5 Cultural Resources

V. CULTURAL RESOURCES—Would the project:	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less Than Significant Impact	No Impact
a) Cause a substantial adverse change in the significance of a historical resource as defined in §15064.5?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Cause a substantial adverse change in the significance of an archaeological resource pursuant to §15064.5?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c) Directly or indirectly destroy a unique paleontological resource or site or unique geologic feature?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Disturb any human remains, including those interred outside of formal cemeteries?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Environmental Setting

Tremaine & Associates, Inc. (Tremaine) prepared an Archaeological Survey Report (ASR) for the Project (Tremaine 2014). The ASR included a records search and literature review, an intensive pedestrian survey, and consultation with the Native American community and local preservation societies.

The archaeological Area of Potential Effects (APE) occupies approximately 3.08 acres, which includes a paved portion of Hazel Valley Road, a segment of the El Dorado Canal, unpaved graded areas, and unpaved vegetation areas. Because ground-disturbing work will occur as a result of implementing the proposed project, the proposed project has the potential to affect historic and prehistoric cultural resources, including any historic properties within the APE, if present.

The existing bridge was built in 1940 and is classified as structurally deficient. Mead & Hunt prepared a draft Historical Resources Evaluation Report (HRER) for the Project (Mead & Hunt 2015). The purpose of the HRER is to identify built environment resources that are 50 or more years old within the APE and evaluate eligibility for listing in the National Register of Historical Places (National Register) and California Register of Historical Resources. Based on archival research and field investigation, three properties were identified in the APE for evaluation. The report concludes that one of the properties, the EID Canal (historically known as the El Dorado Canal), was previously determined not eligible for listing in the National Register of Historic Places (National Register) by the California State Historic Preservation Office (SHPO) in 2008. Hazel Valley Road has been evaluated during a previous study of roads associated with the El Dorado Canal and determined not eligible. The existing bridge 25C-0092 was evaluated and was recommended not eligible for listing in the National Register or the California Register (Mead & Hunt 2015).

An intensive pedestrian survey was conducted of the APE on 23 October 2013. The presence of a previously recorded archaeological site, an 1870–1920 ditch maintenance camp, was confirmed during the survey. This site will be treated as eligible for the purposes of the proposed project. No other archeological or historic resources were observed.

Potential Environmental Effects

- a) **No Impact.** An intensive pedestrian survey and records search were conducted in support of the ASR. No historic resources were discovered in the Project area (Tremaine 2014). The existing bridge was built in 1940 and is classified as structurally deficient. No eligible built environment resources occur in the Project area (Mead & Hunt 2015).
- b) **Less Than Significant Impact.** The presence of one previously recorded archaeological site was confirmed during the pedestrian survey. No excavation is planned to occur in the exiting staging area located in the southeast portion of the Project area. The use of the existing regularly graded staging area during construction of the proposed Project will not have any effect on the previously recorded archaeological site. As a precautionary measure to ensure avoidance of the previously recorded archaeological resource the County will implement CULT-1 as described below.

Measure CULT-1

- *The County will install ESA fencing as shown in the Caltrans approved ESA Action Plan.*

- c) **No Impact.** Paleontological resources in El Dorado County are associated with limestone cave deposits, occurrences of the Mehrten formation, and Pleistocene channel deposits (El Dorado County 2004a). Because these resources do not occur in the project area, no impact will occur. The site does not contain any other unique geologic features.
- d) **Less Than Significant Impact.** The Project ASR documents that no known cemeteries or burials occur within the project study area (Tremaine 2014). Should human remains be discovered during the excavation portion of the Project, the project description includes contract provisions that will require notification of Transportation and compliance with California Health and Safety Code Section 7050.5 and California Public Resources Code Section 5097.9 et seq.

4.2.6 Geology and Soils

	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
VI. GEOLOGY AND SOILS—Would the project:				
a) Expose people or structures to potential substantial adverse effects, including the risk of loss, injury, or death involving:				
i) Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
ii) Strong seismic ground shaking?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
iii) Seismic-related ground failure, including liquefaction?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
iv) Landslides?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Result in substantial soil erosion or the loss of topsoil?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c) Be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the project, and	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

potentially result in on or off-site landslide, lateral spreading, subsidence, liquefaction or collapse?

- | | | | | |
|--|--------------------------|--------------------------|-------------------------------------|-------------------------------------|
| d) Be located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code (1994), creating substantial risks to life or property? | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| e) Have soils incapable of adequately supporting the use of septic tanks or alternative waste water disposal systems where sewers are not available for the disposal of waste water? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

Environmental Setting

Regional Geology: El Dorado County is located in the Sierra Nevada geomorphic province of California, east of the Great Valley province and west of the Range and Basin provinces. Steep-sided hills and narrow rocky stream channels characterize the Sierra Nevada province. This province consists of Pliocene and older deposits that have been uplifted as a result of plate tectonics, granitic intrusion, and volcanic activity. Subsequent glaciations and additional volcanic activity are factors that led to the east-west orientation of stream channels. (El Dorado County 2004a).

The southwestern foothills of El Dorado County are composed of rocks of the Mariposa Formation that include amphibolite, serpentine, and pyroxenite. The northwestern areas of the county consist of the Calaveras Formation, which includes metamorphic rock such as chert, slate, quartzite, and mica schist. The higher peaks in the County consist primarily of igneous and metamorphic rocks with granite intrusions, a main soil parent material at the higher elevations (El Dorado County 2004a).

Seismicity: Seismicity is defined as the geographic and historical distribution of earthquake activity. Seismic activity may result in geologic and seismic hazards including seismically induced fault displacement and rupture, ground shaking, liquefaction, lateral spreading, landslides and avalanches, and structural hazards. Based on historical seismic activity and fault and seismic hazards mapping, El Dorado County is considered to have relatively low potential for seismic activity, and is located beyond the highly active fault zones of the coastal areas of California. The County's fault systems and associated seismic hazards are described below (El Dorado County 2004a).

Fault Systems: Earthquakes are associated with the fault systems in a particular area. The distribution of known faults in El Dorado County is concentrated in the western portion of the county, with several isolated faults in the central county area and the Lake Tahoe Basin. Fault systems mapped in western El Dorado County include the West Bear Mountains Fault; the East Bear Mountains Fault; the Maidu Fault Zone; the El Dorado Fault; the Melones Fault Zone of the Clark, Gillis Hill Fault; and the Calaveras–Shoo Fly Thrust. No fault traces, landslides, or other geologic hazards are mapped crossing or directly adjacent to the project site (Taber 2014).

No active faults have been identified in El Dorado County. One fault, part of the Rescue Lineament–Bear Mountains fault zone, is classified as a well located late-Quaternary fault; therefore, it represents the only potentially active fault in the county. All other faults located in El Dorado County are classified as pre-Quaternary (inactive).

Soils: Soils on the west slope of El Dorado County consist of well-drained silt and gravelly loams divided into two physiographic regions, the Lower and Middle Foothills and the Mountainous Uplands. There are a total of eight soil associations in western El Dorado County.

The only mapped soil unit in the Project area Josephine gravelly loam, 9 to 15 percent slopes. The Josephine soil series consists of well-drained, acidic soils that are underlain by vertically tilted schist, slates, and contact metamorphic rocks (Sycamore Environmental 2014).

Potential Environmental Effects

- a) ***a-i) No Impact.*** No active faults have been identified in El Dorado County. Therefore, the Project will not rupture a fault mapped on the most recent Alquist-Priolo Earthquake Fault Zoning Map.
- a-ii) No Impact.*** The Project is not in a seismic hazard zone (California Department of Conservation 2014b).
- a-iii) No Impact.*** No portion of El Dorado County occurs in a Seismic Hazard Zone (i.e., regulatory zones that encompass areas prone to liquefaction and earthquake-induced landslides) based on the Seismic Hazards Mapping Program administered by the California Geologic Survey (CGS). Consequently, El Dorado County and the Project site are not considered to be at risk from liquefaction hazards.
- Soils observed during test borings on-site were generally dense and contained significant fines. Groundwater encountered was near the top of rock surface. Based on these observations the potential for liquefaction is considered low (Taber 2014).
- a-iv) No Impact.*** No portion of El Dorado County occurs in a Seismic Hazard Zone (i.e., regulatory zones that encompass areas prone to liquefaction and earthquake-induced landslides) based on the Seismic Hazards Mapping Program administered by the California Geologic Survey (CGS). Consequently, El Dorado County and the Project site are not considered to be at risk from earthquake-induced landslides. No fault traces, landslides, or other geologic hazards are mapped crossing or directly adjacent to the project site (Taber 2014).
- b) ***Less Than Significant Impact.*** Measure *Hydro-1* will require implementation of best management practices (BMPs) consistent with the Caltrans Stormwater Quality Handbooks to protect water quality and minimize the potential for siltation and downstream sedimentation. Construction activities will include implementation of stormwater runoff best management practices (BMPs). Application of these requirements and measures would prevent substantial erosion or topsoil loss. Areas temporarily disturbed will be revegetated and reseeded with native grasses and other native herbaceous annual and perennial species. No seed of nonnative species will be used unless certified to be sterile.
- c) ***No Impact.*** The project area is underlain by granitic bedrock of Mesozoic age (California Department of Conservation 2014a). No fault traces, landslides, or other geologic hazards are mapped crossing or directly adjacent to the project site (Taber 2014). Soils on site are not susceptible to landslide, lateral spreading, subsidence, liquefaction, or collapse. No impacts are anticipated from unstable soil.
- d) ***Less Than Significant Impact.*** The gravelly loam soils in the Project area have a low shrink-swell potential (NRCS 1974).
- e) ***No Impact.*** The proposed Project is a surface transportation project. Septic tanks and alternative wastewater disposal systems are not part of the Project.

4.2.7 Greenhouse Gas Emissions

VII. GREENHOUSE GAS EMISSIONS—Would the project:	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less Than Significant Impact	No Impact
a) Generate greenhouse gas emissions, either directly or indirectly, that may have a significant impact on the environment?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b) Conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of greenhouse gases?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Environmental Setting

Greenhouse gases (GHGs) are recognized by wide consensus among the scientific community to contribute to global warming/climate change and associated environmental impacts. The major GHGs that are released from human activity include carbon dioxide, methane, and nitrous oxide (OPR 2008). The primary sources of GHGs are vehicles (including planes and trains), energy plants, and industrial and agricultural activities (such as dairies and hog farms).

Greenhouse gas emissions for transportation projects can be divided into those produced during operations and those produced during construction. The proposed Project does not increase the capacity of Hazel Valley Road and would not increase operational GHG levels. The discussion below therefore focuses on construction related GHG emissions of the Project.

The El Dorado County Air Quality Management District’s (EDCAQMD) has not adopted GHG emissions significance thresholds for development projects. Given the lack of locally adopted GHG emissions significance thresholds the EDCAQMD recommends using significance criteria adopted by the San Luis Obispo Air Pollution Control District (SLOAPCD) to determine the significance of GHG emissions for CEQA. SLOAPCD developed the GHG Emissions Significance Thresholds table below. Projects to “screen out” those below the thresholds as their impacts would be less than significant.

SLOAPCD GHG Emissions Significance Thresholds.

Significance Determination Thresholds	
GHG Emission Source Category	Operational Emissions
Non-stationary Sources	1,150 MTCO ₂ e/yr OR 4.9 MT CO ₂ e/SP/yr
Stationary Sources	10,000 MTCO ₂ e/yr

SP = service population, which is resident population plus employee population of the project

Potential Environmental Effects

- a) ***Less Than Significant Impact.*** The proposed Project does not increase the capacity of Hazel Valley Road and would not increase operational GHG levels. Construction of the proposed Project

would generate short-term emissions of greenhouse gases. The Sacramento Metropolitan Air Quality Management District (SMAQMD's) *Roadway Construction Emissions Model* (RCEM) *Version 7.1.5.1* was used to estimate reactive organic gasses (ROG) and CO₂ emissions from the proposed Project. The same RCEM assumptions used in the air quality analysis were used here.

GHG emissions generated by Project construction would be primarily in the form of CO₂. Emission of other GHGs, such as CH₄ and N₂O, are important with respect to global climate change but the emissions levels of these other GHGs from on and off-road vehicles used during construction are relatively small compared to the level of CO₂ emissions, even when factoring in the relatively larger global warming potential of CH₄ and N₂O. Therefore the primary focus of this analysis is the level of CO₂ emissions from construction of the Project.

The EPA's 'Greenhouse Gas Equivalencies Calculator' provides users a means to convert various emissions data into CO₂ equivalencies (CO₂e). Results from the Roadway Construction Emissions Model were entered into the EPA calculator to determine the total estimated Project CO₂e. The Project will require a total construction period of approximately 4 months or 122 days to complete. The total CO₂e estimate was then converted to provide a yearly CO₂e estimate. Based on the Roadway Construction Emissions Model Project construction is estimated to produce approximately:

- ROG = 0.1 MT for Project.
- CO₂ = 94.2 MT for Project

Using the EPA CO₂e calculator the total estimated Project CO₂e is approximately 96.7 MT. On a yearly basis this equals approximately 32 MTCO₂e. The County has not yet quantified thresholds for construction activities. However, the construction emissions would be well below the lowest SLOAPCD threshold (1,150 MTCO₂e/yr) for non-stationary sources. Project impacts are considered less than significant.

It is important to note that the SLOAPCD threshold was developed to evaluate operational GHG emissions and does not specifically apply to construction emissions. Since construction emissions are temporary, as opposed to annual, utilizing the SLOAPCD operational threshold represents a conservative assessment of potential construction impacts.

- b) ***Less Than Significant Impact.*** EDCAQMD has not yet adopted a qualified plan, policy, or regulation to reduce GHG emissions. Therefore, the most applicable plan, policy, or regulation adopted for the purpose of reducing GHG emissions is Assembly Bill (AB) 32, which codified the State's future GHG emissions reduction targets.

ARB adopted the AB 32 Scoping Plan as a framework for achieving AB 32. The Scoping Plan outlines a series of technologically feasible and cost-effective measures to reduce statewide GHG emissions. These strategies are geared towards sectors and activities that generate significant amounts of GHGs. For example, the majority of measures address building, energy, waste and wastewater generation, goods movement, on-road transportation, water usage, and high global warming potential gases. Activities associated with the Project are not considered by the AB 32 Scoping Plan as having a high potential to emit GHGs. This statement is substantiated by the project-level emissions analysis, which demonstrates that the GHG emissions are well below the lowest SLOAPCD threshold (1,150 MTCO₂e/yr) for non-stationary sources. Consequently, none

of the AB 32 reduction strategies are applicable to construction of the project. Implementation of the Project would not conflict with implementation of AB 32.

4.2.8 Hazards and Hazardous Materials

VIII. HAZARDS AND HAZARDOUS MATERIALS—Would the project:	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less Than Significant Impact	No Impact
a) Create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b) Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
c) Emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project result in a safety hazard for people residing or working in the project area?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f) For a project within the vicinity of a private airstrip, would the project result in a safety hazard for people residing or working in the project area?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g) Impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
h) Expose people or structures to a significant risk of loss, injury or death involving wildland fires, including where wildlands are adjacent to urbanized areas or where residences are intermixed with wildlands?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Environmental Setting

A regulatory agency database review for locations included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 (The Cortese list⁷) was conducted as part of the Project scoping process. No listed hazardous materials or waste sites were reported within or near the project site. Based on County records, regulatory database searches, and site visits, there are no signs of or any known hazardous materials in or adjacent to the project site. The existing bridge paint system may contain lead and the concrete abutments could possibly contain asbestos material.

Potential Environmental Effects

- a) ***Less Than Significant Impact.*** Small amounts of hazardous materials would be used during construction activities (i.e., equipment maintenance, fuel, solvents, roadway resurfacing and re-striping materials). Hazardous materials would only be used during construction of the Project, and any hazardous material uses would be required to comply with all applicable local, state, and federal standards associated with the handling and storage of hazardous materials. Use of hazardous materials in accordance with applicable standards ensures that any exposure of the public to hazard materials would have a less-than-significant impact.
- b) ***Potentially Significant Unless Mitigation Incorporated.*** Based on County records, regulatory database searches, and site visits, there are no signs of or any known hazardous materials. The existing bridge paint system may contain lead and the concrete abutments could possibly include asbestos containing material (ACM). Implementation of HAZ-1 will reduce potential impacts to less than significant
- Measure HAZ-1***
- *Contract provisions will require testing of the existing concrete abutments for asbestos containing material (ACM) and the existing paint system for lead prior to bridge demolition and removal.*
 - *Contract provisions will require the existing paint system be handled in accordance with Caltrans Standard Special Provisions for removal of lead paint (Provision 14-11.08, Disturbance of Existing Paint Systems on Bridges).*
 - *Contract provisions will require ACM be handled in accordance with Caltrans Non-Standard Special Provisions for 14-11.11, Management of Asbestos Containing Materials.*
- c) ***No Impact.*** No existing or proposed schools occur within 0.25 mile of the Project site. The closest schools are located in Pollock Pines approximately 5 miles west of the Project site. As noted above, the Project would involve the short- term handling of hazardous materials during construction. Handling and storage of hazardous materials during construction would comply with all applicable local, state, and federal standards.
- d) ***No Impact.*** No listed hazardous materials or waste sites occur within or near the project site.
- e) ***No Impact.*** The Project is not located within two miles of a public airport or public use airport and no private air strips occur in close proximity to the Project.
- f) ***No Impact.*** See response of item e) above.
- g) ***Less Than Significant Impact.*** The Project will not require a detour. Hazel Valley Road will remain open during construction and motorists will make use of a temporary bridge or the existing bridge during construction. Pedestrian access along the canal berm will be maintained to facilitate canal inspection. The County will continue its coordination with EID prior to and during construction. Project construction activities would be coordinated with local law enforcement and emergency services providers.
- h) ***Less Than Significant Impact.*** The completed Project will not expose people or structures to a new or increased significant risk of loss, injury or death involving wildland fires. Project

construction activities would be coordinated with local law enforcement and emergency services providers.

4.2.9 Hydrology and Water Quality

IX. HYDROLOGY AND WATER QUALITY—Would the project:	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
a) Violate any water quality standards or waste discharge requirements?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b) Substantially deplete groundwater supplies or interfere substantially with groundwater recharge such that there would be a net deficit in aquifer volume or a lowering of the local groundwater table level (e.g., the production rate of pre-existing nearby wells would drop to a level which would not support existing land uses or planned uses for which permits have been granted)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, in a manner which would result in substantial erosion or siltation on- or off-site?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d) Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, or substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or off-site?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
e) Create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
f) Otherwise substantially degrade water quality?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g) Place housing within a 100-year flood hazard area as mapped on a federal Flood Hazard Boundary or Flood Insurance Rate Map or other flood hazard delineation map?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
h) Place within a 100-year flood hazard area structures which would impede or redirect flood flows?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
i) Expose people or structures to a significant risk of loss, injury or death involving flooding, including flooding as a result of the failure of a levee or dam?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
j) Inundation by seiche, tsunami, or mudflow?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Environmental Setting

The Project is located in the in the South Fork American Hydrologic Unit (hydrologic unit code 18020129). The American River has been extensively dammed and diverted downstream of the Project area for hydroelectricity production as part of the Sacramento Municipal Utility District’s (SMUD) Upper American River Project.

The Project includes the replacement of the existing bridge over the El Dorado Canal which is owned and operated by the El Dorado Irrigation District (EID). The Project has been designed to avoid affecting the El Dorado Canal. The Project site is not listed as occurring in a 100-year floodplain. According to the FEMA/FIRM index panel for El Dorado County the project site falls within non-printed community panel no. 06017C0575E in an area where flood hazards are undetermined but possible.

Potential Environmental Effects

- a) ***Less Than Significant Impact.*** The bridge replacement will not violate water quality or waste discharge requirements. The Project will disturb less than one acre of soil and does not require a Section 402 NPDES permit. Implementation of BIO-2 and the revegetation measures and water quality BMPs in HYDRO-1 will ensure long-term soil stabilization and protect water quality during construction.

Measure HYDRO-1

- *Areas temporarily disturbed will be revegetated and reseeded with native grasses and other native herbaceous annual and perennial species in accordance with Appendix F of the Project NES MI. Reseeded areas will be covered with a biodegradable erosion control fabric to prevent erosion and downstream sedimentation. The project engineer will determine the specifications needed for erosion control fabric (e.g., shear strength) based on anticipated maximum flow velocities and soil types. The seed type will consist of commercially available native grass and herbaceous species. No seed of nonnative species will be used unless certified to be sterile.*
 - *Contract provisions will require implementation of best management practices (BMPs) consistent with the Caltrans Stormwater Quality Handbooks to protect water quality and minimize the potential for siltation and downstream sedimentation.*
- b) ***No Impact.*** The Project would not involve any withdrawals from an aquifer or groundwater table.
- c) ***Less Than Significant Impact.*** The Project is the replacement of an existing structure and will not alter the course of the El Dorado Canal and will not substantially change rate or amount of surface runoff present.
- d) ***Less Than Significant Impact.*** See response to item a) and c) above.
- e) ***Less Than Significant Impact.*** The Project would not provide additional sources of runoff compared with the existing bridge. The minor increase of impervious surface area resulting from construction of the approaches and wider bridge deck is not expected to contribute to a substantial increase in water runoff from the site.
- f) ***No Impact.*** No additional impacts other than those discussed above are anticipated.
- g) ***No Impact.*** The Project is a bridge replacement project, and no housing development is associated with the Project.
- h) ***Less Than Significant Impact.*** The Project site is not listed as occurring in a 100-year floodplain. According to the FEMA/FIRM index panel for El Dorado County the project site falls within non-printed community panel no. 06017C0575E in an area identified as Zone D where flood hazards are undetermined but possible.

- i) **No Impact.** The Project will not expose people to higher levels of risk involving flooding. General Plan Policy 6.4.2.2 protects the life and property of County residents below dams by not allowing new critical or high occupancy structures (e.g., schools, hospitals) to be located within the inundation area resulting from failure of dams. The bridge is not a critical or high occupancy structure.
- j) **No Impact.** The Project is not in an area subject to seiche or tsunami.

4.2.10 Land Use and Planning

X. LAND USE AND PLANNING—Would the project:	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
a) Physically divide an established community?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Conflict with any applicable land use plan, policy, or regulation of an agency with jurisdiction over the project (including, but not limited to the general plan, specific plan, local coastal program, or zoning ordinance) adopted for the purpose of avoiding or mitigating an environmental effect?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Conflict with any applicable habitat conservation plan or natural community conservation plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Environmental Setting

The 2004 El Dorado County General Plan is the relevant land use plan for the project area. The General Plan designation of the parcel in the Project area is Natural Resources (NR, 1 DU per 40 ac below 3,000 ft elevation, 1 DU per 160 ac above 3,000 ft elevation) and the zoning designation is Timberland Preserve Zone (TPZ) (El Dorado County 2004b).

Potential Environmental Effects

- a) **No Impact.** The Project proposes to replace the existing bridge on substantially the same alignment and would not physically divide an established community.
- b) **No Impact.** The Project would not conflict with the goals, objectives or policies intended to mitigate environmental impacts adopted in the 2004 El Dorado County General Plan. Replacement of the existing bridge is identified as a needed improvement (project number 77125) in the El Dorado County Community Development Agency, Transportation Division’s 2013 Adopted Capital Improvement Program (El Dorado County 2013).
- c) **No Impact.** The Project does not occur in an area covered by a habitat or natural community conservation plan. El Dorado County is currently preparing an Integrated Natural Resources Management Plan to identify important habitats in the County and establish a program for the management and preservation.

4.2.11 Mineral Resources

	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
XI. MINERAL RESOURCES—Would the project:				
a) Result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Result in the loss of availability of a locally important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Environmental Setting

El Dorado County is considered a mining region capable of producing a wide variety of mineral resources. Metallic mineral deposits, gold in particular, are considered the most significant extractive mineral resource. Other metallic minerals found in the county include silver, copper, nickel, chromite, zinc, tungsten, mercury, titanium, platinum, and iron. Nonmetallic mineral resources include building stone, limestone, slate, clay, marble, soapstone, sand, and gravel (El Dorado County 2004a). The Project area is not located in an area mapped as an ‘Important Mineral Resource Area’ (El Dorado County 2004b).

Potential Environmental Effects

- a) **No Impact.** The Project area is not located in an area mapped as an ‘Important Mineral Resource Area’ (El Dorado County 2004b). The Project would not impact the availability of mineral resources that are locally important or would be of value to the state.
- b) **No Impact.** See response to item a).

4.2.12 Noise

	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
XII. NOISE—Would the project:				
a) Exposure of persons to or generation of noise levels in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b) Exposure of persons to or generation of excessive ground-borne vibration or ground-borne noise levels?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c) A substantial permanent increase in ambient noise levels in the project vicinity above levels existing without the project?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) A substantial temporary or periodic increase in ambient noise levels in the project vicinity above levels existing without the project?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
e) For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the project	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

expose people residing or working in the project area to excessive noise levels?

- f) For a project within the vicinity of a private airstrip, would the project expose people residing or working in the project area to excessive noise levels?

Environmental Setting

The July 2004 El Dorado County General Plan Public Health, Safety, and Noise Element establishes policies and standards for noise exposures at noise sensitive land uses. The relevant policies are listed below:

Policy 6.5.1.9 Noise created by new transportation noise sources, excluding airport expansion but including roadway improvement projects, shall be mitigated so as not to exceed the levels specified in Table 6-1 at existing noise-sensitive land uses.

Table 5 below includes Table 6-1 of the County General Plan.

- Policy 6.5.1.12** When determining the significance of impacts and appropriate mitigation for new development projects, the following criteria shall be taken into consideration.
- A. Where existing or projected future traffic noise levels are less than 60 dBA L_{dn} at the outdoor activity areas of residential uses, an increase of more than 5 dBA L_{dn} caused by a new transportation noise source will be considered significant;
 - B. Where existing or projected future traffic noise levels range between 60 and 65 dBA L_{dn} at the outdoor activity areas of residential uses, an increase of more than 3 dBA L_{dn} caused by a new transportation noise source will be considered significant; and
 - C. Where existing or projected future traffic noise levels are greater than 65 dBA L_{dn} at the outdoor activity areas of residential uses, an increase of more than 1.5 dBA L_{dn} caused by a new transportation noise will be considered significant.

Table 5. Maximum allowable noise exposure for transportation noise sources (General Plan Table 6-1).

TABLE 6-1 MAXIMUM ALLOWABLE NOISE EXPOSURE FOR TRANSPORTATION NOISE SOURCES			
Land Use	Outdoor Activity Areas ¹ $L_{dn}/CNEL, dB$	Interior Spaces	
		$L_{dn}/CNEL, dB$	L_{eq}, dB ²
Residential	60 ³	45	--
Transient Lodging	60 ³	45	--
Hospitals, Nursing Homes	60 ³	45	--
Theaters, Auditoriums, Music Halls	--	--	35
Churches, Meeting Halls, Schools	60 ³	--	40
Office Buildings	--	--	45
Libraries, Museums	--	--	45

Playgrounds, Neighborhood Parks	70	--	--
<p>Notes:</p> <p>¹ In Communities and Rural Centers, where the location of outdoor activity areas is not clearly defined, the exterior noise level standard shall be applied to the property line of the receiving land use. For residential uses with front yards facing the identified noise source, an exterior noise level criterion of 65 dB L_{dn} shall be applied at the building facade, in addition to a 60 dB L_{dn} criterion at the outdoor activity area. In Rural Regions, an exterior noise level criterion of 60 dB L_{dn} shall be applied at a 100 foot radius from the residence unless it is within Platted Lands where the underlying land use designation is consistent with Community Region densities in which case the 65 dB L_{dn} may apply. The 100-foot radius applies to properties which are five acres and larger; the balance will fall under the property line requirement.</p> <p>² As determined for a typical worst-case hour during periods of use.</p> <p>³ Where it is not possible to reduce noise in outdoor activity areas to 60 dB L_{dn} /CNEL or less using a practical application of the best-available noise reduction measures, an exterior noise level of up to 65 dB L_{dn} /CNEL may be allowed provided that available exterior noise level reduction measures have been implemented and interior noise levels are in compliance with this table.</p>			

County General Plan Policy 6.5.1.11 outlines standards for daytime construction and would apply to construction-related noise associated with the Project. General Plan Policy 6.5.1.11 notes that night time construction activities are allowed if it can be shown that nighttime construction activities would alleviate traffic congestion and safety hazards. The significance of noise impacts associated with operation of transportation facilities is normally measured using General Plan Policy 6.5.1.12, which takes into account the existing (ambient) noise environment. Because the Project is not capacity increasing and would not result in an increase of the number of vehicles passing through the roadway corridor, the ambient condition is not expected to change as a result of the Project.

Potential Environmental Effects

- a) **(Construction Noise) Less Than Significant Impact.** Construction activities could increase noise levels temporarily in the vicinity of the Project. Actual noise levels would depend on the type of construction equipment involved, distance to the source of the noise, time of day, and similar factors. These increases would be temporary. Daytime construction would comply with noise standards for construction activities outlined in General Plan Policy 6.5.1.11, and any nighttime work would be allowed if nighttime construction activities would alleviate traffic congestion and safety hazards. Given that the Project contractor would adhere to applicable County construction-related noise standards, this impact considered less than significant.

(Operational Traffic Related Noise) No Impact. The Project does not increase the capacity of Hazel Valley Road. The post project noise levels in the Project vicinity will be substantially unchanged from the pre-project condition
- b) **Less Than Significant Impact.** Project construction includes activities, such as operation of large pieces of equipment (e.g., heavy trucks) which may result in the periodic, temporary generation of ground-borne vibration. Because the Project would not expand the roadway or change the way in which it is used, an increase in ground-borne vibration associated with use of the road would not change from the current condition. Given the nature of any potential ground-borne vibration and

given that any impacts would be temporary and periodic, potential impacts are less than significant.

- c) **No Impact.** The Project is not traffic- or growth inducing and would not change the way in which the roadway is used. The Project would not contribute to a substantial permanent increase in the ambient noise level in the project vicinity.
- d) **Less Than Significant Impact.** Construction activities would increase noise levels temporarily in the vicinity of the Project. Actual noise levels would depend on the type of construction equipment involved, distance to the source of the noise, weather, time of day, and other factors. However, these increases would be temporary. Daytime construction activity would comply with noise standards for construction activities outlined in General Plan Policy 6.5.1.11, and any nighttime work would be allowed if nighttime construction activities would alleviate traffic congestion and safety hazards. Because the Project contractor would be required to comply with applicable County construction-related noise standards, this impact is considered less than significant.
- e) **No Impact.** The Project is not located within an airport land use plan area or within two miles of a public or public use airport.
- f) **No Impact.** The Project is not located within the vicinity of a private airstrip.

4.2.13 Population and Housing

XIII. POPULATION AND HOUSING—Would the project:	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
a) Induce substantial population growth in an area, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Displace substantial numbers of existing housing, necessitating the construction of replacement housing elsewhere?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Displace substantial numbers of people, necessitating the construction of replacement housing elsewhere?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Environmental Setting

The Project is the replacement of an existing bridge and will not increase the capacity of the Hazel Valley Road.

Potential Environmental Effects

- a) **No Impact.** The Project will not result in population growth, the displacement of existing any housing, or a need for new housing.
- b) **No Impact.** See response to item a).
- c) **No Impact.** See response to item a).

4.2.14 Public Services

	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
XIV. PUBLIC SERVICES—Would the project:				
a) Would the project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for any of the public services:	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Fire protection?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Police protection?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Schools?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Parks?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Other public facilities?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Environmental Setting

The El Dorado County Sheriff provides general public safety and law enforcement services. The El Dorado County Fire District’s stations 17 and 18 located at 6430 Pony Express Trail and 5785 Sly Park Rd., respectively in Pollock Pines provides fire protection services and emergency services. The County maintains public facilities including the project area roadways and bridges.

Potential Environmental Effects

- a) **No Impact.** Replacement of the existing bridge would not increase human presence in the area. No new or physically altered governmental facilities would be needed.

4.2.15 Recreation

	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
XV. RECREATION:				
a) Would the project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

- b) Does the project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment?

Environmental Setting

There are no designated recreation facilities within or adjacent to the proposed project area.

Potential Environmental Effects

- a) **No Impact.** The Project would not increase the use of existing parks in the area and does not include the construction of any recreational facilities.
- b) **No Impact.** The proposed Project staging area is used by people to park their vehicles and access the banks of the canal to walk or run. The proposed Project staging area is not a designated recreation area or parking area. Other smaller pull out areas along Hazel Valley Road in the vicinity of the Project area provide similar parking and access opportunities. The Project does not include the construction of any recreational facilities and would not require the expansion of existing recreational facilities.

4.2.16 Transportation/Traffic

XVI. TRANSPORTATION/TRAFFIC—Would the project:	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
a) Cause an increase in traffic which is substantial in relation to the existing traffic load and capacity of the street system (i.e., result in a substantial increase in either the number of vehicle trips, the volume to capacity ratio on roads, or congestion at intersections)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Exceed, either individually or cumulatively, a level of service standard established by the county congestion management agency for designated roads or highways?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Result in a change in air traffic patterns, including either an increase in traffic levels or a change in location that results in substantial safety risks?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d) Substantially increase hazards due to a design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e) Result in inadequate emergency access?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
f) Result in inadequate parking capacity?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g) Conflict with adopted policies, plans, or programs supporting alternative transportation (e.g., bus turnouts, bicycle racks)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Environmental Setting

Hazel Valley Road in the Project area is an off-system two lane rural road in El Dorado County. The bridge has an average daily traffic count of less than 100 vehicles per day (El Dorado County 2014a). The Hazel Valley Road Bridge is primarily used by El Dorado Irrigation District (EID) service trucks and Sierra Pacific Industries (wood products).

Potential Environmental Effects

- a) **No Impact.** Replacement of the existing one lane bridge would not change the amount of traffic on Hazel Valley Road because it is not a new development or growth inducing project. The Project will not require a detour. Project construction activities would be coordinated with local law enforcement and emergency services providers.
- b) **No Impact.** The bridge replacement would not change the amount of traffic on Hazel Valley Road.
- c) **No Impact.** The Project would not result in a change in air traffic patterns.
- d) **No Impact.** The Project objectives include improving roadway safety and compliance with the American Association of Highway and Transportation Officials (AASHTO) guidelines and El Dorado County standards.
- e) **Less than Significant.** Hazel Valley Road will remain open during construction and motorists will make use of the existing bridge or a temporary bridge during construction. The Project will not require a detour. Project construction activities would be coordinated with local law enforcement and emergency services providers.
- f) **No Impact.** The Project would not result in an increase in demand for parking in the vicinity of the Project.
- g) **No Impact.** The Project is identified in the El Dorado County Capital Improvement Program (CIP) as project # 77125 (El Dorado County 2013). The CIP is coordinated with the Five-Year major review of the General Plan (including the Transportation and Circulation Element) and is also included in the annual General Plan review. The Transportation and Circulation Element address alternative transportation systems.

4.2.17 Utilities/ Service Systems

XVII. UTILITIES AND SERVICE SYSTEMS—Would the project:	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
a) Exceed wastewater treatment requirements of the applicable Regional Water Quality Control Board?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b) Require or result in the construction of new water or wastewater treatment facilities or expansion of existing facilities, the construction of which could cause significant environmental effects?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c) Require or result in the construction of new storm water drainage facilities or expansion of existing facilities, the construction of which could cause significant environmental effects?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| d) Have sufficient water supplies available to serve the project from existing entitlements and resources, or are new or expanded entitlements needed? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| e) Result in a determination by the wastewater treatment provider which serves or may serve the project that it has adequate capacity to serve the project's projected demand in addition to the provider's existing commitments? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| f) Be served by a landfill with sufficient permitted capacity to accommodate the project's solid waste disposal needs? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| g) Comply with federal, state, and local statutes and regulations related to solid waste? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

Environmental Setting

Utilities in the Project area include a private 2-inch diameter water line attached to the bridge. No other overhead or underground utilities were observed at the Project site (Taber 2014).

Potential Environmental Effects

- a) ***No Impact.*** The Project would not produce additional wastewater and would not exceed the applicable wastewater treatment requirements.
- b) ***No Impact.*** The Project would not increase the demand on existing water or wastewater treatment facilities.
- c) ***Less than Significant Impact.*** The Project may involve minor reconfiguration of the roadside drainage system within the project area. The facilities will retain approximately the same capacity as the existing system.
- d) ***No Impact.*** The Project would not require water service.
- e) ***No Impact.*** The Project would not produce wastewater.
- f) ***No Impact.*** Solid waste generated by the Project would be limited to construction debris, including asphalt and concrete, generated by the excavation of existing roadway and construction of the proposed improvements. Solid waste disposal would occur in accordance with federal, state, and local regulations. Disposal would occur at permitted landfills. Therefore, the Project would not generate the need for new solid waste facilities.
- g) ***No Impact.*** The Project would conform to all applicable state and federal solid waste regulations.

4.2.18 Mandatory Findings of Significance

XVIII. MANDATORY FINDINGS OF SIGNIFICANCE (To be filled out by Lead Agency if required)	<i>Potentially Significant Impact</i>	<i>Potentially Significant Unless Mitigation Incorporated</i>	<i>Less Than Significant Impact</i>	<i>No Impact</i>
a) Does the project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

plant or animal community, reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?

b) Does the project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects)?

c) Does the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?

- a) **Potentially Significant Unless Mitigation Incorporated.** Through the use of Best Management Practices and the mitigation measures noted previously, the Project will not degrade the quality of the environment.
- b) **Less than Significant.** The Project is consistent with the General Plan and would not result in individually limited but collectively significant impacts. Therefore, the project would not cause any additional environmental effects or significantly contribute to a cumulative impact.
- c) **Less than Significant.** The Project would not result in substantial direct or indirect adverse effects from noise, either during project construction or operation, nor would it result in impacts to air quality, water quality or utilities and public services. Therefore the Project would not cause substantial adverse effects on human beings.

5. Determination

5.1 Environmental Factors Potentially Affected

This Initial Study has determined that in the absence of mitigation the proposed Project could have the potential to result in significant impacts associated with the factors checked below. Mitigation measures are identified in this Initial Study that would reduce all potentially significant impacts to less-than-significant levels.

<input type="checkbox"/> Aesthetics	<input type="checkbox"/> Mineral Resources
<input type="checkbox"/> Agricultural Resources	<input type="checkbox"/> Noise
<input type="checkbox"/> Air Quality	<input type="checkbox"/> Population and Housing
<input checked="" type="checkbox"/> Biological Resources	<input type="checkbox"/> Public Services
<input checked="" type="checkbox"/> Cultural Resources	<input type="checkbox"/> Recreation
<input type="checkbox"/> Geology and Soils	<input type="checkbox"/> Transportation/Traffic
<input type="checkbox"/> Greenhouse Gas Emissions	<input type="checkbox"/> Utilities and Service Systems
<input checked="" type="checkbox"/> Hazards and Hazardous Materials	<input checked="" type="checkbox"/> Mandatory Findings of Significance
<input checked="" type="checkbox"/> Hydrology and Water Quality	<input type="checkbox"/> None Identified
<input type="checkbox"/> Land Use and Planning	


On the basis of this initial evaluation:


- I find that the proposed project COULD NOT have a significant effect on the environment, and a NEGATIVE DECLARATION will be prepared.
- I find that although the proposed project could have a significant effect on the environment, there will not be a significant effect in this case because the project-specific mitigation measures described in Section III have been added to the project. A MITIGATED NEGATIVE DECLARATION will be prepared.
- I find that the proposed project MAY have a significant effect on the environment, and an ENVIRONMENTAL IMPACT REPORT is required.
- I find that the Project MAY have a "Potentially significant impact" or "potentially significant unless mitigated" impact on the environment, but at least one effect 1) has been adequately analyzed in an earlier document pursuant to applicable legal standards, and 2) has been addressed by mitigation measures based on the earlier analysis as described on attached sheets. An ENVIRONMENTAL IMPACT REPORT is required, but it must analyze only the effects that remain to be addressed.
- I find that although the Project could have a significant effect on the environment, because all potentially significant effects (a) have been analyzed adequately in an earlier EIR or NEGATIVE DECLARATION pursuant to applicable standards, and (b) have been avoided or mitigated pursuant to that earlier EIR or NEGATIVE DECLARATION, including revisions or mitigation measures that are imposed upon the proposed project, nothing further is required.

Signature:

Date:

Name and Title: Janet Postlewait, Principal Planner


Initial Study/MND
March 2015


Hazel Valley Road at El Dorado Canal Bridge (25C0092) Replacement Project
El Dorado County Community Development Agency, Transportation Division

6. Report Preparation and References

6.1 Report Preparation

El Dorado County Community Development Agency, Transportation Division– CEQA Lead Agency

Chandra Ghimire, P.E.	Senior Civil Engineer
Monika Pedigo	Associate Civil Engineer
Janet Postlewait	Principal Planner

Sycamore Environmental Consultants, Inc.

Jeffery Little	Vice President, Principal In Charge, Consulting Planner, Project Manager
Adam Forbes	Biologist
Aramis Respoll	CAD/GIS Analyst

Tremaine & Associates, Inc.

Kim Tremaine, M.A., Ph.C., RPA	Principal Investigator
Trish Fernandez, M.A	Principal Investigator

6.2 References

- California Department of Conservation. August 2000. A general location guide for ultramafic rocks in California – Areas more likely to contain naturally occurring asbestos. Division of Mines and Geology, open-file report 2000-19. ftp://ftp.consrv.ca.gov/pub/dmg/pubs/ofr/ofr_2000-019.pdf
- California Department of Conservation. Accessed October 2014 (2014a). 2010 Geologic Map of California. <http://www.quake.ca.gov/gmaps/GMC/stategeologicmap.html>.
- California Department of Conservation. Accessed October 2014 (2014b). CGS Seismic Hazard Zonation Program (SHZP) Data Access Page. <http://gmw.consrv.ca.gov/shmp/MapProcessor.asp?Action=SHMP&Location=All&Version=5&Browser=Netscape&Platform=Win>
- California Department of Conservation. Accessed October 2014 (2014c). Farmland Mapping and Monitoring Program. El Dorado County important farmland. El Dorado, CA.
- California Department of Fish and Wildlife (CDFW). February 2010 (2010a). A status review of the fisher (*Martes pennanti*) in California. Report to the Fish and Game Commission.
- California Department of Fish and Wildlife (CDFW). September 2010 (2010b). Vegetation classification and mapping program: Natural Communities – List. Biogeographic Data Branch, Sacramento, CA.

- California Department of Fish and Wildlife (CDFW). September 2010. Vegetation classification and mapping program: Natural Communities – List. Biogeographic Data Branch, Sacramento, CA.
- California Environmental Quality Act (CEQA) Statutes. 1970. Public Resources Code Section 21000, et seq.
- El Dorado County Air Quality Management District (AQMD). February 2002. Guide to air quality assessment, determining significance of air quality impacts under the California Environmental Quality Act.
- El Dorado County. 2005. El Dorado County Asbestos Review Areas Western Slope, County of El Dorado. El Dorado County Surveyor/G.I.S. Division, G.I.S. Project Id: 3089a.
- El Dorado County. January 2004, Certified 19 July 2004 (2004a). El Dorado County general plan, final environmental impact report (EIR). Resolution No. 234-2004, State Clearinghouse No. 2001082030. Prepared by EDAW.
- El Dorado County. Adopted 19 July 2004 (2004b). El Dorado County general plan, a plan for managed growth and open roads; a plan for quality neighborhoods and traffic relief. El Dorado County Planning Department, Placerville, CA.
- El Dorado County, Community Development Agency, Transportation Division. 24 June 2013 (Accessed: October 2014). Adopted 2013 Capital Improvement Programs for: West Slope Road/Bridge, Capital Overlay and Rehabilitation, Environmental Improvement Program, Airports, Road Maintenance Program, National Pollutant Discharge Elimination System. Available: <http://www.edcgov.us/Government/DOT/CIP.aspx>. . .
- El Dorado County, Community Development Agency, Transportation Division. 21 July 2014 (2014a). Hazel Valley Rd/ EID Canal Bridge, Bridge No. 25C0092, Replacement vs Rehabilitation Report. Prepared by Monika Pedigo and David R. Friestad.
- Governor’s Office of Planning and Research (OPR). 19 June 2008. Technical advisory: CEQA and climate change: Addressing climate change through California Environmental Quality Act (CEQA) Review. Sacramento, CA. <http://www.opr.ca.gov/ceqa/pdfs/june08-ceqa.pdf>.
- Mead & Hunt, Inc. 17 February 2015. Historical Resources Evaluation Report, Hazel Valley Road Bridge (25C-0092) Project, Hazel Valley Road at EID Canal El Dorado County, California. Prepared for: El Dorado County Department of Transportation Project.
- Natural Resources Conservation Service (NRCS; formerly known as Soil Conservation Service). April 1974. Soil survey of El Dorado Area, California. USDA – Soil Conservation Service.
- Sacramento Area Council of Governments. 2012. *Metropolitan Transportation Plan/Sustainable Communities Strategy 2035*. Available: <http://www.sacog.org/2035/mtpscs/>. Accessed: October 2014.
- Sycamore Environmental Consultants, Inc. May 2014. Natural Environment Study (Minimal Impacts), Hazel Valley Road at the El Dorado Canal Bridge (25C0092) Replacement, El Dorado County, CA.
- Taber Consultants. 14 January 2014. Draft Foundation Report, Hazel Valley Road/EID Canal Bridge Replacement. Prepared for: El Dorado County, Community Development Agency, Transportation Division
- Tremaine & Associates, Inc. November 2014. Archaeological Survey Report, Bridge No. 25C0092, Hazel Valley Road over El Dorado Canal Replacement Project.
- U.S. Environmental Protection Agency (EPA). Accessed September 2014. Overview of Greenhouse Gases. <http://www.epa.gov/climatechange/ghgemissions/gases.html>.

[THIS PAGE INTENTIONALLY BLANK]

Appendix A: Mitigation Monitoring and Reporting Plan

[THIS PAGE INTENTIONALLY BLANK]

**MITIGATION MONITORING AND REPORTING PLAN
HAZEL VALLEY ROAD AT THE EL DORADO CANAL
BRIDGE (25C0092) REPLACEMENT PROJECT**

**CEQA LEAD AGENCY:
El Dorado County**

**PREPARED:
April 2015**

ADOPTED BY BOARD OF SUPERVISORS ON: _____

[THIS PAGE INTENTIONALLY BLANK]

Introduction

Purpose

The El Dorado County Community Development Agency, Transportation Division, (Transportation) intends to replace the existing Hazel Valley Road at the El Dorado Canal Bridge (25C0092) located in unincorporated El Dorado County. The Project is located along Hazel Valley Road approximately 5 mi east of Pollock Pines.

As described in the IS/MND, the Project itself incorporates a number of measures to minimize adverse effects on the environment. The IS/MND also identified several mitigation measures that are required to reduce potentially significant impacts to levels that are less than significant. This Mitigation Monitoring and Reporting Plan (MMRP) describes a program for ensuring that these mitigation measures are implemented in conjunction with the Project. El Dorado County Transportation, as the lead agency under the California Environmental Quality Act (CEQA), is responsible for overseeing the implementation and administration of this MMRP. The County will designate a staff member to manage the MMRP. Duties of the staff member responsible for program coordination will include conducting routine inspections and reporting activities, coordinating with the Project construction contractor, coordinating with regulatory agencies, and ensuring enforcement measures are taken.

Regulatory Framework

California Public Resources Code Section 21081.6 and California Code of Regulations Title 14, Chapter 3, Section 15097 require public agencies to adopt mitigation monitoring or reporting plans when they approve projects under a MND. The reporting and monitoring plans must be adopted when a public agency makes its findings pursuant to CEQA so that the mitigation requirements can be made conditions of Project approval.

Format of This Plan

The MMRP summarizes the impacts and mitigation measures identified and described in the Project IS/MND. Each of the impacts discussed within this MMRP is numbered based on the sequence in which they are discussed in the IS/MND. A summary of each impact with the corresponding specific mitigation measures are provided. Mitigation measures are followed by an implementation description, the criteria used to determine the effectiveness of the mitigation, the timeframe for implementation, and the party responsible for monitoring the implementation of the measure.

Implementation of mitigation measures is ultimately the responsibility of Transportation; during construction, the delegated responsibility is shared by Transportation's contractors. Each mitigation measure in this plan contains a "Verified By" signature line, which will be signed by the Transportation Project manager when the measure has been fully implemented and no further actions or monitoring are necessary for the implementation or effectiveness of the measure.

Impacts and Associated Monitoring or Reporting Measures

IV. BIOLOGICAL RESOURCES

Impact (a): Have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special-status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Game or U.S. Fish and Wildlife Service.

Birds Of Prey and Migratory Bird Treaty Act

The Project area provides potential nesting habitat for birds of prey and birds listed by the Migratory Bird Treaty Act (MBTA) of 1918 (16 U.S.C. 703-711). BIO-1 will be implemented to avoid impacts to birds of prey and birds listed by the MBTA.

Measure BIO-1

Under the MBTA, nests that contain eggs or unfledged young are not to be disturbed during the breeding season. Nesting or attempted nesting by migratory birds and birds-of-prey is anticipated from 1 February through 31 August.

Swallow

In California, bridge-nesting swallows typically arrive in mid-February, increase in numbers until late March, and remain until October. Nesting begins in April, peaks in June, and continues into August. Measures should be taken to prevent establishment of cliff swallow nests prior to construction. Techniques to prevent nest establishment include using exclusion devices, removing and disposing of partially constructed and unoccupied nests of migratory or nongame birds on a regular basis to prevent their occupation, or perform any combination of these. This can be done by:

- *The contractor can visit the site weekly and remove partially completed nests using either hand tools or high pressure water; and/or*
- *Hang netting from the bridge before nesting begins. If this technique is used, netting should be in place from late February until project construction begins.*

Birds of Prey and Birds Protected by the Migratory Bird Treaty Act

- *If construction begins outside the 1 February to 31 August breeding season, there will be no need to conduct a preconstruction survey for active nests.*
- *Trees scheduled for removal should be removed during the non-breeding season from 1 September to 31 January.*
- *If construction is scheduled to begin between 1 February and 31 August, a biologist shall conduct a survey for active bird of prey nests within 250 ft and active MTBA bird nests within 100 ft of the BSA from publicly accessible areas within one week prior to construction. The measures listed below shall be implemented based on the survey results.*

No Active Nests Found:

- *If no active nest of a bird of prey, MBTA bird, or other CDFW protected bird is found, then no further avoidance and minimization measures are necessary.*

Active Nests Found:

- *If an active nest of a bird of prey, MBTA bird, or other CDFW protected bird is discovered that may be adversely affected by construction activities or an injured or killed bird is found, immediately:*
 1. *Stop all work within a 100-ft radius of the discovery.*
 2. *Notify the Engineer.*
 3. *Do not resume work within the 100-ft radius until authorized.*
- *The biologist shall establish a minimum 250-ft Environmentally Sensitive Area (ESA) around the nest if the nest is of a bird of prey, and a minimum 100-ft ESA around the nest if the nest is of an MBTA bird other than a bird of prey.*

Bird Species Protection Areas

<i>Protected Bird Type</i>	<i>Size of Protection Area (ESA)</i>
<i>Bird of prey</i>	<i>250 ft no-disturbance buffer</i>
<i>MBTA protected bird (not bird of prey)</i>	<i>100 ft no-disturbance buffer</i>

- *Activity in the ESA will be restricted as follows:*
 1. *Do not enter the ESA unless authorized.*
 2. *If the ESA is breached, immediately:*
 - a. *Secure the area and stop all operations within 60 feet of the ESA boundary.*
 - b. *Notify the Engineer.*
 3. *If the ESA is damaged, County determines what efforts are necessary to remedy the damage and who performs the remedy.*
- *No construction activity will be allowed in the ESA until the biologist determines that the nest is no longer active, or unless monitoring determines that a smaller ESA will protect the active nest.*
- *The size of an ESA may be reduced if the biologist monitors the construction activities and determines that no disturbance to the active nest is occurring. Reduction of ESA size depends on the species of bird, the location of the nest relative to the project, project activities during the time the nest is active, and other project-specific factors.*
- *Between 1 February and 31 August, if additional trees or shrubs need to be trimmed and/or removed after construction has started, a survey will be conducted for active nests in the area to be affected. If an active nest is found, the above measures will be implemented.*

- *If an active nest is identified in or adjacent to the construction zone after construction has started, the above measures will be implemented to ensure construction is not causing disturbance to the nest.*

Implementation: The County will implement the measures as described above.
Effectiveness
Criteria: The County will prepare and keep on file documentation verifying the implementation of the above-referenced measures.
Timing: Pre-Construction Phase (Potential Construction Phase)
Verified By: _____ Date: _____
 County Project Manager

Impact (c): Have a substantial adverse effect on federally protected wetlands as defined by Section 404 of the Clean Water Act (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?

Waters of the U.S.

The seasonal wetland located adjacent to an outside the southern Project boundary will be avoided and no impacts are anticipated. Implementation of BIO-2 will further reduce potential impacts to the seasonal wetland located adjacent to an outside the southern Project boundary.

Measure BIO-2

- *Temporary fencing will be installed between the construction limits and the seasonal wetland.*
- *Signs will be posted on the fencing notifying the construction crew that the area beyond is an Environmentally Sensitive Area (ESA) and that no circumstances personnel or equipment pass beyond the fencing.*
- *Water-permeable erosion control measures will be installed along the temporary fence line to ensure that sediment does not migrate south of the fence.*
- *The temporary fencing and water-permeable erosion control measures will be in place prior to commencement of construction.*

Implementation: The County will implement the measures as described above.
Effectiveness
Criteria: The County will prepare and keep on file documentation verifying the implementation of the above-referenced measures.
Timing: Pre-Construction Phase (Potential Construction Phase)
Verified By: _____ Date: _____
 County Project Manager

V. CULTURAL RESOURCES

Impact (b): Cause a substantial adverse change in the significance of an archaeological resource pursuant to §15064.5?

Previously Recorded Cultural Resource

One previously recorded cultural resource is located adjacent to the Project area. As a precautionary measure to ensure avoidance of the previously recorded archaeological resource the County will implement the measure below.

Measure CULT-1

- *The County will install ESA fencing as shown in the Caltrans approved ESA Action Plan.*

Implementation: The County will implement the measures as described above.

Effectiveness Criteria: The County will prepare and keep on file documentation verifying the implementation of the above-referenced measures.

Timing: Pre-Construction and Potential Construction Phases

Verified By: _____ Date: _____
County Project Manager

VIII. HAZARDS AND HAZARDOUS MATERIALS

Impact (b): Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?

Lead Based Paint and Asbestos Containing Material

The existing bridge paint system may contain lead and the concrete abutments could possibly include asbestos containing material (ACM). Implementation of HAZ-1 will reduce potential impacts to less than significant

Measure HAZ-1

- *Contract provisions will require testing of the existing concrete abutments for asbestos containing material (ACM) and the existing paint system for and lead prior before bridge demolition and removal.*
- *Contract provisions will require the existing paint system be handled in accordance with Caltrans Standard Special Provisions for removal of lead paint (Provision 14-11.08, Disturbance of Existing Paint Systems on Bridges).*
- *Contract provisions will require ACM be handled in accordance with Caltrans Non-Standard Special Provisions for 14-11.11, Management of Asbestos Containing Materials.*

Implementation: The County will implement the measures as described above.
Effectiveness Criteria: The County will prepare and keep on file documentation verifying the implementation of the above-referenced measures.
Timing: Pre-Construction and Potential Construction Phases
Verified By: _____ Date: _____
County Project Manager

IX. Hydrology and Water Quality

Impact (a): Violate any water quality standards or waste discharge requirements?

Soil Stabilization & Erosion Control

Implementation of BIO-2 and the revegetation measures and water quality BMPs in HYDRO-1 will ensure long-term soil stabilization and protect water quality during construction.

Measure HYDRO-1

- *Areas temporarily disturbed will be revegetated and reseeded with native grasses and other native herbaceous annual and perennial species in accordance with Appendix F of the Project NES MI. Reseeded areas will be covered with a biodegradable erosion control fabric to prevent erosion and downstream sedimentation. The project engineer will determine the specifications needed for erosion control fabric (e.g., shear strength) based on anticipated maximum flow velocities and soil types. The seed type will consist of commercially available native grass and herbaceous species. No seed of nonnative species will be used unless certified to be sterile.*
- *Contract provisions will require implementation of best management practices (BMPs) consistent with the Caltrans Stormwater Quality Handbooks to protect water quality and minimize the potential for siltation and downstream sedimentation.*

- **Implementation:** The County will implement the measures as described above.
Effectiveness Criteria: The County will prepare and keep on file documentation verifying the implementation of the above-referenced measures.
Timing: Construction Phases
Verified By: _____ Date: _____
County Project Manager

Appendix B: Comments and Responses

Hazel Valley Road at El Dorado Canal Bridge (25C0092) Replacement Project (SCH # 2015032009)

Section 1. List of Comment Letters Received

Six (6) comment letters were received. Table 1 lists the names of the individuals, organizations, and agencies that provided comments on the Initial Study/Mitigated Negative Declaration. The letters are included, followed by a response to the comment(s).

Table 1. Comment Letters Received

Letter	Commenter
1	California Department of Fish & Wildlife (North Central Region)
2	Central Valley Regional Water Quality Control Board
3	State Clearinghouse
4	Hugh H. Lewis
5	Nina Poole
6	Heather Gehr

[THIS PAGE INTENTIONALLY BLANK]

Section 2. Responses to Comments

Comment Letter 1: California Department of Fish & Wildlife (North Central Region)

[THIS PAGE INTENTIONALLY BLANK]



Janet Postlewait <janet.postlewait@edcgov.us>

CEQA Review: Hazel Valley Road Bridge IS/MND (SCH 2015032009)

1 message

Calderaro, Angela@Wildlife <Angela.Calderaro@wildlife.ca.gov> Thu, Apr 2, 2015 at 1:51 PM
To: "janet.postlewait@edcgov.us" <janet.postlewait@edcgov.us>
Cc: Wildlife R2 CEQA <R2CEQA@wildlife.ca.gov>

Good morning Ms. Postlewait,

The California Department of Fish and Wildlife (Department) is providing comments on the Initial Study/Mitigated Negative Declaration (IS/MND) for the Hazel Valley Road at El Dorado Canal Bridge Replacement Project (project) as both a trustee agency and responsible agency under the California Environmental Quality Act (CEQA). As trustee for the State's fish and wildlife resources, the Department has jurisdiction over the conservation, protection, and management of fish, wildlife, native plants, and the habitat necessary for biologically sustainable populations of such species (Guidelines § 15386). The Department may also be a responsible agency for a project affecting biological resources where we will exercise our discretion after the lead agency to approve or carry out a proposed project or some facet thereof (CEQA Guidelines § 15096).

Nesting Birds and Raptors

The project has the potential to disturb bird species or nests protected under the Migratory Bird Treaty Act (MBTA), FGC §3503 and 3503.5. Construction is planned for the summer of 2016. Since project activities will occur during the nesting season (determined by region, species, and climate), construction activities could result in disturbance to nesting raptors and other migratory birds. Raptors and other migratory birds are protected under the MBTA and FGC §3503.5; therefore, potential impacts may be considered potentially significant unless adequate avoidance, minimization and/or mitigation is incorporated. If nests are identified on or adjacent to the project site, implementation of the project may adversely impact the success of the nest site and/or take a bird, their eggs and/or nest.

Mitigation measure BIO-1 identifies no-work *Environmentally Sensitive Area (ESA)* buffers between 100 and 250 feet. For particularly sensitive birds, 100 or 250 feet may not be the appropriate distance depending on the project activity and level of disturbance. All measures to protect birds should be performance-based. While some birds may tolerate disturbance within 100 or 250 feet of construction activities, other birds may have a different disturbance threshold and "take" (FGC §86) could occur if the no-work buffers are not designed to reduce stress to that individual pair. The Department recommends including performance-based protection measures for avoiding all nests protected under the Migratory Bird Treaty Act and FGC §3503.5. A 100-foot or 250-foot no-work buffer may be sufficient; however, that buffer may need to be increased based on the birds' tolerance level

to the disturbance. Below is an example of a performance-based protection measure:

Should construction activities cause the nesting bird to vocalize, make defensive flights at intruders, get up from a brooding position, or fly off the nest, then the exclusionary buffer will be increased such that activities are far enough from the nest to stop this agitated behavior. The exclusionary buffer will remain in place until the chicks have fledged or as otherwise determined by a qualified biologist.

2 In addition, the Department recommends that pre-construction nest surveys are conducted no more than **3 days** prior to the start of construction. If there is a break in construction for more than one week, then nest surveys should be completed again. The results of the nest surveys should be submitted to the Department or another qualified biologist at the County for approval.

3 The Department does not recommend the use of netting to deter swallows from nesting on the bridge. If not installed properly or maintained, the nets may cause more harm by trapping and killing birds. The Department instead recommends that nests area removed by hand scraping or hydropower before they are a 1/3 complete. If the nests are more than 1/3 complete, a qualified biologist needs to confirm that no eggs are present prior to removal. A Migratory Bird Protection Plan which outlined the measures taken to avoid take of a nest should be in place if swallows have the potential to continue to nest at the site during construction activities.

Please let me know if you have any questions or concerns or would like to discuss further. Thank you for allowing the Department the opportunity to comment on the CEQA document.

Kindly,

Angela Calderaro

Senior Environmental Scientist (Specialist)

Habitat Conservation Branch

California Department of Fish and Wildlife, North Central Region

1701 Nimbus Road, Rancho Cordova CA 95670

Office: 916-358-2920

Fax: 916-358-2912

Angela.Calderaro@wildlife.ca.gov

www.wildlife.ca.gov

-

To report a violation please notify the Californians Turn in Poachers and Polluters (CallTIP) program by calling 1-888-DFG-Calltip or texting "tip411" (numerically, 847411 – Start message with "Calltip") You can even send photos via text. Also, the CallTIP App can be downloaded for free via the Google Play Store and iTunes App Store.

[This page intentionally blank]

Response 1: California Department of Fish & Wildlife (CDFW, North Central Region)

Response to CDFW Comment 1

Mitigation Measure BIO-1 is performance based as illustrated by the following excerpts from the measure:

- *'If construction is scheduled to begin between 1 February and 31 August, a biologist shall conduct a survey for active bird of prey nests within 250 ft and active MBTA bird nests within 100 ft of the BSA from publicly accessible areas within one week prior to construction. The measures listed below shall be implemented based on the survey results.'*

'No Active Nests Found:

- *If no active nest of a bird of prey, MBTA bird, or other CDFW protected bird is found, then no further avoidance and minimization measures are necessary.*

Active Nests Found:

- *If an active nest of a bird of prey, MBTA bird, or other CDFW protected bird is discovered that may be adversely affected by construction activities or an injured or killed bird is found, immediately:*
 4. *Stop all work within a 100-ft radius of the discovery.*
 5. *Notify the Engineer.*
 6. *Do not resume work within the 100-ft radius until authorized.'*
- *'No construction activity will be allowed in the ESA until the biologist determines that the nest is no longer active, or unless monitoring determines that a smaller ESA will protect the active nest.'*
- *'The size of an ESA may be reduced if the biologist monitors the construction activities and determines that no disturbance to the active nest is occurring. Reduction of ESA size depends on the species of bird, the location of the nest relative to the project, project activities during the time the nest is active, and other project-specific factors.'*
- *'Between 1 February and 31 August, if additional trees or shrubs need to be trimmed and/or removed after construction has started, a survey will be conducted for active nests in the area to be affected. If an active nest is found, the above measures will be implemented.'*

Mitigation Measure BIO-1 provides the following performance based direction based on the results of the preconstruction survey:

- *'The biologist shall establish a minimum 250-ft Environmentally Sensitive Area (ESA) around the nest if the nest is of a bird of prey, and a minimum 100-ft ESA around the nest if the nest is of an MBTA bird other than a bird of prey.'*

This measure defines the minimum ESA radius to be established for both birds of prey and MBTA protected birds. The buffer radii described in the measure may be adjusted based at the discretion of the biologist monitoring the construction activities.

Response to CDFW Comment 2

Mitigation Measure BIO-1 requires:

- *'The contractor can visit the site **weekly** and remove partially completed nests using either hand tools or high pressure water; and/or'*
- *'If construction is scheduled to begin between 1 February and 31 August, a biologist shall conduct a survey for active bird of prey nests within 250 ft and active MTBA bird nests within 100 ft of the BSA from publicly accessible areas **within one week prior to construction**. The measures listed below shall be implemented based on the survey results.'*
- *'Between 1 February and 31 August, if additional trees or shrubs need to be trimmed and/or removed after construction has started, a survey will be conducted for active nests in the area to be affected. If an active nest is found, the above measures will be implemented.'*
- *'If an active nest is identified in or adjacent to the construction zone after construction has started, the above measures will be implemented to ensure construction is not causing disturbance to the nest.'*

BIO-1 requires a pre-construction survey one week prior to the start of construction and is consistent with prior direction provided by CDFW on other El Dorado County Projects. CDFW has required a pre-construction bird survey ranging from one week to 15 days prior to initiation of construction on other County Projects.

Response to CDFW Comment 3

Mitigation Measure BIO-1 includes several other options besides the use of netting to remove partially completed nests of swallows and other bridge nesting birds. The contractor may select one or the various alternatives to exclude bridge nesting birds.

Comment Letter 2: Central Valley Regional Water Quality Control Board

[THIS PAGE INTENTIONALLY BLANK]



REC'D
DOT
3/16/15



EDMUND G. BROWN JR.
GOVERNOR

MATTHEW RODRIGUEZ
SECRETARY FOR
ENVIRONMENTAL PROTECTION

Central Valley Regional Water Quality Control Board

27 March 2015

Janet Postlewait
El Dorado County
Community Development Agency
2850 Fairlane Court
Placerville, CA 95667

CERTIFIED MAIL
7014 2120 0001 3978 4894

COMMENTS TO REQUEST FOR REVIEW FOR THE MITIGATED NEGATIVE DECLARATION, HAZEL VALLEY ROAD AT EL DORADO CANAL BRIDGE (25C0092) REPLACEMENT PROJECT, SCH# 2015032009, EL DORADO COUNTY

Pursuant to the State Clearinghouse's 4 March 2015 request, the Central Valley Regional Water Quality Control Board (Central Valley Water Board) has reviewed the *Request for Review for the Mitigated Negative Declaration* for the Hazel Valley Road at El Dorado Canal Bridge (25C0092) Replacement Project, located in El Dorado County.

Our agency is delegated with the responsibility of protecting the quality of surface and groundwaters of the state; therefore our comments will address concerns surrounding those issues.

Construction Storm Water General Permit

Dischargers whose project disturb one or more acres of soil or where projects disturb less than one acre but are part of a larger common plan of development that in total disturbs one or more acres, are required to obtain coverage under the General Permit for Storm Water Discharges Associated with Construction Activities (Construction General Permit), Construction General Permit Order No. 2009-009-DWQ. Construction activity subject to this permit includes clearing, grading, grubbing, disturbances to the ground, such as stockpiling, or excavation, but does not include regular maintenance activities performed to restore the original line, grade, or capacity of the facility. The Construction General Permit requires the development and implementation of a Storm Water Pollution Prevention Plan (SWPPP).

For more information on the Construction General Permit, visit the State Water Resources Control Board website at:
http://www.waterboards.ca.gov/water_issues/programs/stormwater/constpermits.shtml.



Phase I and II Municipal Separate Storm Sewer System (MS4) Permits¹

The Phase I and II MS4 permits require the Permittees reduce pollutants and runoff flows from new development and redevelopment using Best Management Practices (BMPs) to the maximum extent practicable (MEP). MS4 Permittees have their own development standards, also known as Low Impact Development (LID)/post-construction standards that include a hydromodification component. The MS4 permits also require specific design concepts for LID/post-construction BMPs in the early stages of a project during the entitlement and CEQA process and the development plan review process.

For more information on which Phase I MS4 Permit this project applies to, visit the Central Valley Water Board website at:

http://www.waterboards.ca.gov/centralvalley/water_issues/storm_water/municipal_permits/.

For more information on the Phase II MS4 permit and who it applies to, visit the State Water Resources Control Board at:

http://www.waterboards.ca.gov/water_issues/programs/stormwater/phase_ii_municipal.shtml

Industrial Storm Water General Permit

Storm water discharges associated with industrial sites must comply with the regulations contained in the Industrial Storm Water General Permit Order No. 97-03-DWQ.

For more information on the Industrial Storm Water General Permit, visit the Central Valley Water Board website at:

http://www.waterboards.ca.gov/centralvalley/water_issues/storm_water/industrial_general_permits/index.shtml.

Clean Water Act Section 404 Permit

If the project will involve the discharge of dredged or fill material in navigable waters or wetlands, a permit pursuant to Section 404 of the Clean Water Act may be needed from the United States Army Corps of Engineers (USACOE). If a Section 404 permit is required by the USACOE, the Central Valley Water Board will review the permit application to ensure that discharge will not violate water quality standards. If the project requires surface water drainage realignment, the applicant is advised to contact the Department of Fish and Game for information on Streambed Alteration Permit requirements.

If you have any questions regarding the Clean Water Act Section 404 permits, please contact the Regulatory Division of the Sacramento District of USACOE at (916) 557-5250.

¹ Municipal Permits = The Phase I Municipal Separate Storm Water System (MS4) Permit covers medium sized Municipalities (serving between 100,000 and 250,000 people) and large sized municipalities (serving over 250,000 people). The Phase II MS4 provides coverage for small municipalities, including non-traditional Small MS4s, which include military bases, public campuses, prisons and hospitals.

Clean Water Act Section 401 Permit – Water Quality Certification

If an USACOE permit (e.g., Non-Reporting Nationwide Permit, Nationwide Permit, Letter of Permission, Individual Permit, Regional General Permit, Programmatic General Permit), or any other federal permit (e.g., Section 9 from the United States Coast Guard), is required for this project due to the disturbance of waters of the United States (such as streams and wetlands), then a Water Quality Certification must be obtained from the Central Valley Water Board prior to initiation of project activities. There are no waivers for 401 Water Quality Certifications.

Waste Discharge Requirements

If USACOE determines that only non-jurisdictional waters of the State (i.e., "non-federal" waters of the State) are present in the proposed project area, the proposed project will require a Waste Discharge Requirement (WDR) permit to be issued by Central Valley Water Board. Under the California Porter-Cologne Water Quality Control Act, discharges to all waters of the State, including all wetlands and other waters of the State including, but not limited to, isolated wetlands, are subject to State regulation.

For more information on the Water Quality Certification and WDR processes, visit the Central Valley Water Board website at:

http://www.waterboards.ca.gov/centralvalley/help/business_help/permit2.shtml.

Regulatory Compliance for Commercially Irrigated Agriculture

If the property will be used for commercial irrigated agricultural, the discharger will be required to obtain regulatory coverage under the Irrigated Lands Regulatory Program.

There are two options to comply:

1. **Obtain Coverage Under a Coalition Group.** Join the local Coalition Group that supports land owners with the implementation of the Irrigated Lands Regulatory Program. The Coalition Group conducts water quality monitoring and reporting to the Central Valley Water Board on behalf of its growers. The Coalition Groups charge an annual membership fee, which varies by Coalition Group. To find the Coalition Group in your area, visit the Central Valley Water Board's website at: http://www.waterboards.ca.gov/centralvalley/water_issues/irrigated_lands/app_approval/index.shtml; or contact water board staff at (916) 464-4611 or via email at IrrLands@waterboards.ca.gov.
2. **Obtain Coverage Under the General Waste Discharge Requirements for Individual Growers, General Order R5-2013-0100.** Dischargers not participating in a third-party group (Coalition) are regulated individually. Depending on the specific site conditions, growers may be required to monitor runoff from their property, install monitoring wells, and submit a notice of intent, farm plan, and other action plans regarding their actions to comply with their General Order. Yearly costs would include State administrative fees (for example, annual fees for farm sizes from 10-100 acres are currently \$1,084 + \$6.70/Acre); the cost to prepare annual monitoring reports; and water quality monitoring costs. To enroll as an Individual Discharger under the Irrigated Lands Regulatory

Program, call the Central Valley Water Board phone line at (916) 464-4611 or e-mail board staff at IrrLands@waterboards.ca.gov.


Low or Limited Threat General NPDES Permit

If the proposed project includes construction dewatering and it is necessary to discharge the groundwater to waters of the United States, the proposed project will require coverage under a National Pollutant Discharge Elimination System (NPDES) permit. Dewatering discharges are typically considered a low or limited threat to water quality and may be covered under the General Order for *Dewatering and Other Low Threat Discharges to Surface Waters* (Low Threat General Order) or the General Order for *Limited Threat Discharges of Treated/Untreated Groundwater from Cleanup Sites, Wastewater from Superchlorination Projects, and Other Limited Threat Wastewaters to Surface Water* (Limited Threat General Order). A complete application must be submitted to the Central Valley Water Board to obtain coverage under these General NPDES permits.

For more information regarding the Low Threat General Order and the application process, visit the Central Valley Water Board website at:
http://www.waterboards.ca.gov/centralvalley/board_decisions/adopted_orders/general_orders/r5-2013-0074.pdf

For more information regarding the Limited Threat General Order and the application process, visit the Central Valley Water Board website at:
http://www.waterboards.ca.gov/centralvalley/board_decisions/adopted_orders/general_orders/r5-2013-0073.pdf

If you have questions regarding these comments, please contact me at (916) 464-4684 or tcleak@waterboards.ca.gov.



Trevor Cleak
Environmental Scientist

cc: State Clearinghouse unit, Governor's Office of Planning and Research, Sacramento

Response 2: Central Valley Regional Water Quality Control Board

This letter reiterates standard requirements that are included in the MND document and mitigation measures. No response is necessary.

[THIS PAGE INTENTIONALLY BLANK]

Comment Letter 3: State Clearinghouse

[THIS PAGE INTENTIONALLY BLANK]



EDMUND G. BROWN JR.
GOVERNOR

STATE OF CALIFORNIA
GOVERNOR'S OFFICE of PLANNING AND RESEARCH
STATE CLEARINGHOUSE AND PLANNING UNIT



KEN ALEX
DIRECTOR

April 3, 2015

Janet Postlewait
El Dorado County
2850 Fairlane Court
Placerville, CA 95667

Subject: Hazal Valley Road at El Dorado Canal Bridge (25C0092) Replacement Project
SCH#: 2015032009

Dear Janet Postlewait:

The State Clearinghouse submitted the above named Mitigated Negative Declaration to selected state agencies for review. The review period closed on April 2, 2015, and no state agencies submitted comments by that date. This letter acknowledges that you have complied with the State Clearinghouse review requirements for draft environmental documents, pursuant to the California Environmental Quality Act.

Please call the State Clearinghouse at (916) 445-0613 if you have any questions regarding the environmental review process. If you have a question about the above-named project, please refer to the ten-digit State Clearinghouse number when contacting this office.

Sincerely,

Scott Morgan
Director, State Clearinghouse

FILED
DOT

**Document Details Report
State Clearinghouse Data Base**

SCH# 2015032009
Project Title Hazel Valley Road at El Dorado Canal Bridge (25C0092) Replacement Project
Lead Agency El Dorado County

Type MND Mitigated Negative Declaration
Description The El Dorado County Community Development Agency intends to replace the Hazel Valley Road Bridge at the El Dorado Canal (25C0092). The existing 27.5 ft long and 10.8 ft wide (curb to curb) bridge built in 1940 is a single span structure with a timber deck on steel girders and concrete abutments. The proposed replacement bridge will be an approximately 54 ft long, 28 ft wide concrete slab bridge. The new bridge will meet the AASHTO minimum standards for a "Resource Recovery Road" or a "Minor Access Road". The road will remain open during construction and motorists will make use of the existing bridge or a temporary bridge during construction.

Lead Agency Contact

Name Janet Postlewait
Agency El Dorado County
Phone 530 621 5993 **Fax**
email
Address 2850 Fairlane Court
City Placerville **State** CA **Zip** 95667

Project Location

County El Dorado
City
Region
Lat / Long 38° 45' 34.1" N / 120° 29' 32.1" W
Cross Streets US Hwy 50
Parcel No. 009-060-29-100 and County ROW
Township 11N **Range** 13E **Section** 35 **Base**

Proximity to:

Highways US 50
Airports
Railways
Waterways South Fork of the American River & Esmeralda Creek
Schools
Land Use El Dorado County right-of-way; GPD; Natural Resources; Z: Timberland Preserve Zone (TPZ)

Project Issues Archaeologic-Historic; Biological Resources; Soil Erosion/Compaction/Grading; Toxic/Hazardous; Vegetation; Water Quality; Wetland/Riparian

Reviewing Agencies Resources Agency; Department of Fish and Wildlife, Region 2; Office of Historic Preservation; Department of Parks and Recreation; Department of Water Resources; Office of Emergency Services, California; California Highway Patrol; Caltrans, District 3 S; Air Resources Board, Transportation Projects; Regional Water Quality Control Bd., Region 5 (Sacramento); Native American Heritage Commission; State Lands Commission

Date Received 03/04/2015 **Start of Review** 03/04/2015 **End of Review** 04/02/2015

Note: Blanks in data fields result from insufficient information provided by lead agency.

Response 3: State Clearinghouse

This letter transmits to El Dorado County comment letters the State Clearinghouse received. No response is necessary.

[THIS PAGE INTENTIONALLY BLANK]

Comment Letter 4: Hugh H. Lewis

[THIS PAGE INTENTIONALLY BLANK]

Hugh H Lewis
P. O. Box 1449
Pollock Pines, CA, 95726

Ref: Replacement of Hazel Valley Road at El Dorado Canel Bridge (25C0092)


Ms Janet Postlewait, Principle Planner

1 I do not understand why a one lane bridge on a one lane road needs to be replaced with a two lane bridge, the traffic on Hazel Valley is very minimum.

2 I live at 3041 Hazel Valley Road and my neighbor the Rhodes at 3087, our water supply follows the road on the south side about 1/4 mile. The spring is on the south side but it comes from the north side, I know this for DOT used a grader to clean the drainage ditch on the north side and the bank got wet and my spring decreased in flow. If you make the bridge two lanes I am afraid you will want to make Hazel Valley two lanes cover my spring and cut off my water. The spring also feeds a seasonal creek on the south side of the road.

3 A couple years ago, I heard of a plan to rerouts logging trucks off Sly Park to Park Creek, to Plum Creek, to Hazel Valley, to Hwy 50. Sly Park has a interchange to get on 50, at Hazel Valley it is difficult to go west bound during the summer. I understand when they log up behind me it is my turn in the barrel and that is part of life up here. The logging traffic off Iron Mountain should stay on Sly Park which I believe was built with timber tax money. People cannot buy by a airport and complain of the noise, they knew it was there when they bought. I do not know if the new bridge is part of that plan, but it seams to fit.

Thank You



Hugh H Lewis

(530) 644-6744

[This page intentionally blank]

Response 4: Hugh H. Lewis

Response to Hugh H. Lewis Comment 1

The purpose of the Project is to replace the existing Hazel Valley Road Bridge (25C0092) at EID Canal. Project objectives include improving roadway safety, reducing annual maintenance costs, increase the life of the bridge, compliance with the American Association of State Highway and Transportation Officials (AASHTO) guidelines, and compliance with El Dorado County standards. This Project is identified in the El Dorado County Capital Improvement Program as project # 77125.

Replacement of the structure is necessary due to the following deficiencies:

- **Service Life:** The existing bridge is 74 years old (at present). The assumed service life is 75 years.
- **Unknown Abutment Reinforcement/Strength:** The type and strength of the existing abutment supports is unknown.
- **Sub-Standard Width/Functionally Obsolete Classification:** The 2013 Caltrans bridge inspection report states the bridge is “Functionally Obsolete” because the existing clear width between railings is 10-feet 10-inches which is less than the two way existing approach roadway widths of 20-feet
- **Substandard Wheel Guards and Railings:** As noted in the 2013 Caltrans bridge inspection report and County bridge maintenance reports the existing timber wheel guards and timber railings and posts are hit by vehicles numerous times each year and require repair by County Bridge Maintenance staff at least twice a year historically.
- **Gravel, Dirt Debris and Accelerating Dry Rot Issues:** Vehicles using the bridge track dirt and debris onto the bridge deck. The gravel and dirt tend to retain moisture thus accelerating dry rot and shortening the design life of the timber. Dirt and debris also filters down through the openings in the timber deck which contributes to the corrosion of the supporting I-beam superstructure.
- **Substandard Approach Roadway Geometrics and Sight Distance:** The approach roadway does not meet AASHTO requirements for minimum horizontal and vertical curve radius and sight distance.
- **Seismic Analysis and Retrofit:** The Hazel Valley Road Bridge was constructed before modern bridge seismic codes had been developed. Bridges constructed during this time typically were not designed to satisfy current seismic requirements.

Response to Hugh H. Lewis Comments 2

Hazel Valley Road in the Project area is an off-system two lane rural road in El Dorado County. The County does not have any current or future plans to expand Hazel Valley Road outside the proposed project area.

Response to Hugh H. Lewis Comments 3

Please see response to Comment 1 for a description of the project purpose and objectives.

[THIS PAGE INTENTIONALLY BLANK]

Comment Letter 5: Nina Poole

From: Nina Poole <npoole49@att.net>
Date: Mon, Mar 2, 2015 at 4:47 PM
Subject: Hazel Valley Road El Dorado Canal Bridge (25C0092) Replacement Project
To: janet.postlewait@edcgov.us

Dear Ms. Postlewait,

I, Nina Poole, Trustee of the Floyd Poole Trust, have received your NOTICE OF INTENT TO ADOPT A MITIGATED NEGATIVE DECLARATION for the project described as:

**Hazel Valley Road El Dorado Canal Bridge (25C0092) Replacement Project APN:
"County road right-of-way and APN 009-060-29-100".**

For the past 5 years I have received from DOT, each time from a different engineer, a written notice of the proposed bridge replacement, with a PERMIT TO ENTER form that I had to fill out and return, including a diagram of the domestic water line that runs up to, and is attached to, the bridge. Please see attachment.

I think you need to check your facts regarding "County road right-of-way".

El Dorado County DOES NOT have a "right-of-way" along Hazel Valley Road, only a PRESCRIPTIVE EASEMENT.

In County records, you will find a Record of Survey which substantiates this statement.

Also, Bob Olsen, R.C.E., 2899 Crystal Springs RD, Camino, CA 95709 Phone 530-644-1046, will verify this information.

Also, at the site of the bridge, there is a private domestic water line, encased in a metal pipe, which is attached to the existing bridge. There is no mention this in the current notice.

This will have to be addressed.

I can meet with you or someone from your office to discuss this matter.

Sincerely,

Nina Poole, Trustee of the Floyd Poole Trust

PO Box 57

Kyburz CA 95720

530-293-3177

npoole49@att.net

[THIS PAGE INTENTIONALLY BLANK]

Response 5: Nina Poole

From: Chandra Ghimire chandra.ghimire@edcgov.us
Date: Wed, Mar 4, 2015 at 10:56 AM
Subject: Re: Hazel Valley Road El Dorado Canal Bridge (25C0092) Replacement Project
To: Nina Poole <npoole49@att.net>
Cc: Janet Postlewait <janet.postlewait@edcgov.us>, Monika Pedigo <monika.pedigo@edcgov.us>, Jeannette Lyon <jeannette.lyon@edcgov.us>, John Kahling <john.kahling@edcgov.us>

Dear Ms. Poole,

It was very nice talking to you this morning. I appreciate your interest in the Hazel Valley Road at EID Canal bridge replacement project, and your outstanding cooperation to date.

The County is required to meet federal guidelines while replacing the 75-year old bridge. We will be minimizing the impact to both the environment and to the adjacent property as outlined in the environmental documents which can be viewed at <http://www.edcgov.us/Government/DOT/CEQA.aspx>.

We acknowledge that the Hazel Valley Road Right of Way is a Prescriptive Easement. The County Right-of-Way representative will work with you to perfect the roadway right of way for Hazel Valley Road in the vicinity of the bridge. We also understand that there is a private domestic water line attached to the bridge. The Initial Study/Mitigated Negative Declaration section 4.2.17, *Environmental Setting* (available at the website listed above), mentions that there is a private 2 inch existing water line attached to the bridge. We will be replacing the waterline during the construction phase of the project in close coordination with the property owner.

I hope this alleviates your concerns. I appreciate your diligent management of the trust for which you are responsible. If you have any question please contact me. I will always be happy to work with you.

Sincerely,

Chandra Ghimire, PE

Senior Civil Engineer

County of El Dorado

Community Development Agency

Transportation Division

2441 Headington Road

Placerville, CA 95667
(530) 621-5998/FAX (530) 295-2655
chandra.ghimire@edcgov.us

Comment Letter 6: Heather Gehr

[THIS PAGE INTENTIONALLY BLANK]



Janet Postlewait <janet.postlewait@edcgov.us>

Fw: bridge replacement on hazel valley rd.

1 message

bbeepsplat@wildblue.net <bbeepsplat@wildblue.net> Sun, Mar 8, 2015 at 1:23 PM
To: "janet.postlewait@edcgov.us" <janet.postlewait@edcgov.us>

Sent from Windows Mail

From: HEATHER GEHR
Sent: Sunday, March 8, 2015 12:39 PM
To: janet.postlewait@edcgov.us.

1 as a property owner up here and my water supply is spring feed and this project involves or has no right of ways, with this water supply for everyone up here, the building that has been going on up here has involved allowed well drilling which should not be allowed,due to our spring feed water supply ,now you want to disrupt

2 this creek and the wildlife habitat,for development of something that jeopardizes all of it,,,,and puts our water supply in danger,and opens the door for land management to develop and do as they want,This bridge is on private land and the county does not

3 have a right of way,its just like pg&e claiming to upgrade and clear power line trees, when all there doing is dropping big historical trees and clearing for development,cuz that's all they have done so far as we can see up here, tree no where near power pole line,they cut it down and presto a new residence or land management project, to be sold to the highest bidder after so much time, along with drilling wells,NO TO

4 THIS PROJECT,KEEP THE DEVELOPEMENT OUT OF THIS AREA, WE HAVE SPRINGS AND ENDANGERED SPECIS HERE ,,,,,deer,bear,fox,ring tailed cats, pilated woodpeckers,owls ,tree frogs,honey bees,butterfiys,salamanders,,,,,,
Sincerely ,home owner ,up In pacific house
Sent from Windows Mail

[This page intentionally blank]

Response 6: Heather Gehr

From: Chandra Ghimire <chandra.ghimire@edcgov.us>

Date: Thu, Apr 9, 2015 at 4:24 PM

Subject: Re: Fw: bridge replacement on hazel valley rd.

To: bbeepsplat@wildblue.net

Cc: Janet Postlewait <janet.postlewait@edcgov.us>, Monika Pedigo <monika.pedigo@edcgov.us>, John Kahling <john.kahling@edcgov.us>, Jeannette Lyon <jeannette.lyon@edcgov.us>

Dear Ms. Gehr-

I appreciate your interest in the Hazel Valley Road at EID Canal bridge replacement project.

The purpose of this project is to replace the 75-year old bridge with a bridge that meets current federal guidelines. We will be minimizing the impact to both the environment and to the adjacent property as outlined in the environmental documents which can be viewed at <http://www.edcgov.us/Government/DOT/CEQA.aspx>.

Hazel Valley Road is one of the County maintained roads within the County of El Dorado. We anticipate that the Hazel Valley Road right-of-way is a prescriptive easement.

Please refer to the Initial Study/Mitigated Negative Declaration section 4.2.4 (available at the website listed above) for wildlife/plant species and their habitat, & section 4.2.9 for groundwater and water quality.

This project is not a part of any land development project. The field study does not indicate any springs located within the bridge replacement project limits.

I hope this alleviates your concerns. If you have any question please contact me.

Sincerely,

Chandra Ghimire, PE
Senior Civil Engineer

County of El Dorado
Community Development Agency
Transportation Division
2441 Headington Road
Placerville, CA 95667
(530) 621-5998/FAX (530) 295-2655
chandra.ghimire@edcgov.us

[THIS PAGE INTENTIONALLY BLANK]