



RESOLUTION NO.

OF THE BOARD OF SUPERVISORS OF THE COUNTY OF EL DORADO

RESOLUTION OF NECESSITY

WHEREAS, the Country Club Drive Realignment – Bass Lake Road to Tierra de Dios Drive Project, ROW 96000, ADHOC #71360 (Project) is located in western El Dorado County in the unincorporated area along Bass Lake Road, which intersects with Highway 50 to the south and Green Valley Road to the north. This area is east of the Serrano development of El Dorado Hills and west of Cameron Park, approximately .25 miles north of US Highway 50 at Bass Lake Road;

WHEREAS, The County and Developer have entered into several agreements for the development of three residential subdivision projects in the Bass Lake Specific Plan area (Bell Woods, Bell Ranch and Hawk View), just North of Hwy. 50 in El Dorado Hills. A common condition for each project is for the Developer to perform the design, acquisition of right-of-way, and construction (or funding for construction) of the County Club Drive realignment project between Bass Lake Road and Tierra de Dios Drive. Each of the agreements also includes a provision under which the County would assist in securing the necessary right-of-way should the developer be unable to. This provision for County right-of-way acquisition is consistent with County Ordinance and State Subdivision Map Act Law. To date, the Developer has been unable to secure the right-of-way for two parcels owned by M.H. Mohanna, on the Country Club project and has asked the County to assist in the acquisition.

On September 19, 2017, the Board approved the Bell Woods Community Benefit and Development Agreement (DA)16-0002 (Item 24), the Bell Ranch DA16-0003 (Item 23), and the Hawk View DA 16-0001 (Item 22) with the Developer. Condition No. 22 of the Bell Ranch DA, Condition No. 24 of the Hawk View DA, and Condition No. 25 of the Bell Woods DA require the Developer to realign Country Club Drive (aka Tierra De Dios Drive, aka City Lights Drive). Condition No. 21 of the Bell Ranch DA, Condition No. 15 of the Hawk View DA, Condition No.24 of the Bell Woods DA, and Section 3.2.2 of the each DA provide that if the Developer does not have or cannot obtain certain interests in the property necessary to allow them to make required off-site improvements, the County may acquire the necessary rights by negotiation or through other proceedings, including eminent domain.

On July 27, 2018, The Board approved an Agreement for Funding of Right of Way Acquisition Costs, Lennar Winncrest, LLC, #18-54835.

WHEREAS, the Project is necessary to complete a connector road between Bass Lake Road and Tierra de Dios Drive improving traffic circulation consistent with the Circulation Element

of the County General Plan. The Project will improve traffic circulation within Western El Dorado County by providing for improved and additional connectivity between Tierra de Dios Drive to the west and Bass Lake Road (which connects to U.S. Highway 50) to the south. The Project will improve vehicle and pedestrian safety, and includes conversion of the existing segment of Country Club Drive into a Class I bike path/Multi-use trail, 8 feet in width.

WHEREAS, the requirements of the California Environmental Quality Act (“CEQA”) have been met. In March 1992, the Board of Supervisors certified the Bass Lake Road Study Area Program and approved the subsequent Bass Lake Hills Specific Plan EIR Addendum in November of 1995. The Board also certified the Hawk View Mitigated Negative Declaration and the Bell Woods Mitigated Negative Declaration (May 2005); The Bell Ranch Mitigated Negative Declaration (January 2006) adopted the Mitigation Monitoring and Reporting Plan; adopted the Findings of Fact; approved the Project as described in the Final Subsequent Environmental Impact Report; and authorized Transportation Division staff to proceed with final design, rights-of-way acquisition, permitting, and other activities for Project construction (April 2016).

WHEREAS, as a necessary part of the Project, it has been determined that portions of Assessor’s Parcel Number (APN) 119-080-23 and 119-080-12, unimproved land, located off City Lights Drive, within El Dorado County, as more particularly described and depicted in Exhibits “A” and “B” consisting of 47,959.56 square feet (SF) in Fee Title and 12,719.52 SF of Temporary Construction Easement over a 24 month period of APN 119-080-12; 107,375.4 SF in Fee Title, 18,369.25 SF of Permanent Public Service Easement and 41,643.36 SF of Temporary Construction Easement over a 24 month period of APN 119-080-23 (collectively referred to herein as the “Subject Properties”), are best suitable and necessary for the Project, will result in a maximum benefit to the Project, at the most reasonable cost, and with the least interference as possible to private property rights, and that there is no other reasonable, permissible location configured for the Project;

WHEREAS, it is necessary and desirable for the County to acquire the herein described portion of the Subject Properties, for the purpose of constructing the Project;

WHEREAS, the County of El Dorado is a political subdivision of the State of California and is vested with the power of eminent domain by virtue of Article 1, Section 19 of the Constitution of the State of California, Government Code section 25350.5 which authorizes the County Board of Supervisors to exercise the powers of eminent domain necessary to carry out any of the powers and functions of the County, and by virtue of California Code of Civil Procedure sections 1240.050, 1240.110, 1240.120, 1240.125, 1240.150, 1240.410, and 1240.610 and Streets and Highways Code section 943 which authorize the County Board of Supervisors to acquire any property necessary for the use and purposes of county highways;

WHEREAS, Code of Civil Procedure section 1240.410 authorizes the County to acquire any portion of the Subject Property described as an uneconomic remnant by eminent domain in accordance with that article;

WHEREAS, the Subject Properties are being acquired for a compatible use under Code of Civil Procedure section 1240.510 in that the County’s use of the Subject Properties will not

interfere with or impair any continued public use as it now exists or may reasonably be expected to exist in the future; and alternatively for a more necessary public use under Code of Civil Procedure section 1240.610 in that the County's use of the Subject Properties is a more necessary public use than any public use to which the property is appropriated;

WHEREAS, pursuant to Government Code section 7267.2, the Subject Properties were appraised by an independent real estate appraiser and an amount believed to be just compensation was established by the County;

WHEREAS, the amount of just compensation was offered to the owner pursuant to Government Code section 7267.2;

WHEREAS, pursuant to the provisions of Code of Civil Procedure section 1245.235, written notice has been duly given to all persons who could be located whose property is to be acquired by eminent domain and whose names and addresses appear on the County of El Dorado's last equalized roll, all of whom have been given a reasonable opportunity to appear and be heard before the Board of Supervisors on the following matters:

- a. Whether the public interest and necessity require the Project;
- b. Whether said Project is planned or located in the manner that will be most compatible with the greatest public good and the least private injury;
- c. Whether the Subject Properties are necessary for the Project; and
- d. Whether the offer required by Government Code section 7267.2 has been made to all owners of record;

NOW, THEREFORE, BE IT RESOLVED that the Board of Supervisors of the County of El Dorado hereby finds:

1. The public interest and necessity require the construction of the the Country Club Drive (aka City Lights Drive, aka Tierra de Dios) to Bass Lake Road Project;
2. The Project is planned and located in the manner that will be most compatible with the greatest public good and the least private injury;
3. The Subject Properties are necessary for the Project;
4. The offer required by Government Code section 7267.2 has been made to all owners of record;
5. The requirements under the California Environmental Quality Act have been satisfied;
6. The Subject Properties are being acquired for a compatible use under Code of Civil Procedure section 1240.510 in that County's and State's use of the Subject Properties will not interfere with or impair the continued public use as it now exists or may reasonably be expected to exist in the future, and alternatively, for a more necessary public use under Code of Civil Procedure section 1240.610 in that County's and

State's use of the Subject Properties is a more necessary public use than the use to which the Subject Properties are appropriated;

7. Notice and a reasonable opportunity to appear and be heard on April 9, 2019, on the matters enumerated in Code of Civil Procedure section 1240.030 was given to each of the persons whose name and address appears on the County's last equalized roll; and

BE IT FURTHER RESOLVED that outside counsel, Meyers Nave, is hereby authorized, with assistance of County Counsel, to proceed immediately with the commencement of an action for eminent domain pursuant to the Eminent Domain Law set forth in the Code of Civil Procedure, commencing with Section 1230.010 et seq., for the Subject Properties described and depicted in Exhibits "A" and "B" attached hereto.

PASSED AND ADOPTED by the Board of Supervisors of the County of El Dorado at a regular meeting of said Board, held the 9th day of April 2019, by the following vote of said Board:

Attest: Ayes:
Jim Mitrisin Noes:
Clerk of the Board of Supervisors Absent:

By: _____
Deputy Clerk

Sue Novasel, Chairman, Board of Supervisors

I CERTIFY THAT:
THE FOREGOING INSTRUMENT IS A CORRECT COPY OF THE ORIGINAL ON FILE IN
THIS OFFICE.

Attest: Jim Mitrisin, Clerk of the Board of Supervisors of the County of El Dorado, State of
California.

By: _____ Date: _____
Deputy Clerk

Exhibit 'A'

APN 119-080-12
Fee Road Right of Way

All that real property situated in the County of El Dorado, State of California, being a portion of Parcel 3, as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 48 of Parcel Maps at page 80, lying within the Southeast One-Quarter of Section 6, T. 9 N., R. 9 E., M.D.M. and being more particularly described as follows:


Commencing at a ¾" capped iron pipe, stamped "L.S. 3279", marking the Northwest corner of Parcel 'A', as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 15 of Parcel Maps at Page 53; thence along the West Line of said Parcel 'A', South 01°03'22" West, 224.10 feet; thence South 86°49'08" West, 313.01 feet; thence South 01°17'57" West, 654.84 feet to a point on the North line of said Parcel 3, and the true **Point of Beginning**; thence along the North line of said Parcel 3, along the arc of a curve to the right, having a radius of 300.00 feet, the chord of which bears South 72°42'48" East, 165.26 feet; thence South 56°43'33" East, 603.28 feet to the Northeast corner of said Parcel 3; thence along the East line of said Parcel 3, South 00°53'06" West, 83.29 feet; thence leaving said East line, along the arc of a non-tangent curve, concave to Northeast, having a radius of 802.00 feet, the chord of which bears North 59°06'53" West, 139.82 feet; thence North 54°06'50" West, 499.10 feet; thence along the arc of a curve to left, having a radius of 1360.00 feet, the chord of which bears North 58°05'03" West, 188.34 feet to a point on the North line of said Parcel 3; thence along said North line, South 88°42'03" East, 23.35 feet, to the **Point of Beginning**, containing an area of 1.101 acres, more or less.

See Exhibit 'B' attached hereto and made part of this description.

End of Description

The Basis of Bearings for this description is the California State Plane Coordinate System, Zone 2, NAD 83.

This description has been prepared by me or under my direct supervision.




Kevin A. Heeney, P.L.S. 5914



10/10/2018
Date

CTA Engineering & Surveying
3233 Monier Circle
Rancho Cordova, CA 95742
916-638-0919

Exhibit 'B'



LINE DATA TABLE		
LINE	BEARING	DISTANCE
L1	S88°42'03"E	23.35'



DATE: 10/10/2018

OWNER:
M.H. MOHANNA

A.P.N. 119-080-12

cta Engineering & Surveying
Civil Engineering • Land Surveying • Land Planning
3233 Monier Circle, Rancho Cordova, CA 95742
T (916) 838-0910 • F (916) 838-2479 • www.ctaens.net

DATE: 10/10/2018
SCALE: 1"=100'

DRAWN BY: KAH
JOB NO. 16-017-018

SHEET 1 OF 1

ROAD RIGHT OF WAY

A PORTION OF THE S.E QUARTER OF SECTION 6, T.9N., R.9E., M.D.M.
COUNTY OF EL DORADO STATE OF CALIFORNIA

Exhibit 'A'

APN 119-080-12
Temporary Construction Easement

All that real property situated in the County of El Dorado, State of California, being a portion of Parcel 3, as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 48 of Parcel Maps at page 80, lying within the Southeast One-Quarter of Section 6, T. 9 N., R. 9 E., M.D.M. and being more particularly described as follows:


COMMENCING at a ¾" capped iron pipe, stamped "L.S. 3279", marking the Northwest corner of Parcel 'A', as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 15 of Parcel Maps at Page 53; thence along the West Line of said Parcel 'A', South 01°03'22" West, 224.10 feet; thence South 86°49'08" West, 313.01 feet; thence South 01°17'57" West, 654.84 feet to a point on the North line of said Parcel 3; thence along said North line North 88°42'03" West, 23.35 feet to the true **POINT OF BEGINNING**; thence continuing along said North line, North 88°42'03" West, 34.22 feet; thence leaving said North line, along the arc of a non-tangent curve, concave to the Southwest, having a radius of 1345.00 feet, the chord of which bears South 58°44'09" East, 216.77 feet; thence South 54°06'50" East, 499.10 feet; thence along the arc of a curve to the left, having a radius of 817.00 feet, the chord of which bears South 59°21'34" East, 149.39 feet to a point on the East line of said Parcel 3; thence along said East line, North 00°53'06" East, 16.52 feet; thence leaving said East line, along the arc of a non-tangent curve, concave to Northeast, having a radius of 802.00 feet, the chord of which bears North 59°06'53" West, 139.82 feet; thence North 54°06'50" West, 499.10 feet; thence along the arc of a curve to left, having a radius of 1360.00 feet, the chord of which bears North 58°05'03" West, 188.34 feet to the **POINT OF BEGINNING**, containing an area of 0.292 acres, more or less.

See Exhibit 'B' attached hereto and made part of this description.

End of Description

The Basis of Bearings for this description is the California State Plane Coordinate System, Zone 2, NAD 83.

This description has been prepared by me or under my direct supervision.



Kevin A. Heeney, P.L.S. 5914



10/02/2017
Date

CTA Engineering & Surveying
3233 Monier Circle
Rancho Cordova, CA 95742
916-638-0919

Exhibit 'B'



LINE DATA TABLE		
LINE	BEARING	DISTANCE
L1	N88°42'03"W	23.35'
L2	N88°42'03"W	34.22'
L3	N00°53'06"E	16.52'



DATE: 10/02/2017

OWNER: M.H. MOHANNA	DATE: 04/20/2017	DRAWN BY: KAH	SHEET 1 OF 1
	SCALE: 1"=100'	JOB NO. 16-017-018	
A.P.N. 119-080-12	TEMPORARY CONSTRUCTION EASEMENT		

cta Engineering & Surveying
Civil Engineering • Land Surveying • Land Planning
3233 Monier Circle, Rancho Cordova, CA 95742
T (916) 433-0919 • F (916) 636-2473 • www.ctaen.net

COUNTRY CLUB DRIVE
A PORTION OF THE S.E. QUARTER
OF SECTION 6, T.9N., R.9E., M.D.M.
COUNTY OF EL DORADO STATE OF CALIFORNIA

Exhibit 'A'

APN 119-080-23
Fee Road Right of Way

All that real property situated in the County of El Dorado, State of California, being a portion of Parcel 1, as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 48 of Parcel Maps at page 80, lying within the Southeast One-Quarter of Section 6, T. 9 N., R. 9 E., M.D.M. and being more particularly described as follows:

Fee

Commencing at a $\frac{3}{4}$ " capped iron pipe, stamped "L.S. 3279", marking the Northwest corner of Parcel 'A'; as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 15 of Parcel Maps at Page 53; thence along the West Line of said Parcel 'A', South 01°03'22" West, 224.10 feet; thence South 86°49'08" West, 313.01 feet to the Northeast corner of said Parcel 1; thence along the East line of said Parcel 1, South 01°17'57" West, 577.12 feet to the true **Point of Beginning**; thence continuing along the East line of said Parcel 1, South 01°17'57" West, 77.72 feet to the Southeast corner of said Parcel 1; thence along the South line of said Parcel 1, North 88°42'03" West, 23.35 feet; thence leaving said South line along the arc of a non-tangent curve, concave to the Southwest, having a radius of 1360.00 feet, the chord of which bears North 65°55'52" West, 183.88 feet; thence North 69°48'26" West, 353.69 feet; thence along the arc of a curve to the left, having a radius of 722.00 feet, the chord of which bears South 86°17'45" West, 584.90 feet; thence South 62°24'14" West, 144.69 feet to a point on the East line of Bass Lake Road as described in Document 2008-60082, Official Records of El Dorado County; thence along said East line North 17°35'46" West, 55.16 feet; thence South 72°24'14" West, 73.00 feet; thence along the arc of a curve to the right, having a radius of 20.00 feet, the chord of which bears North 61°18'12" West, 28.92 feet to a point of compound curvature; thence along the arc of a curve to the right, having a radius of 1350.00 feet, the chord of which bears North 14°43'00" West, 13.85 feet; thence leaving said East line along the arc of a non-tangent curve, concave to the Northeast, having a radius of 20.00 feet, the chord of which bears South 66°00'34" East, 31.34 feet; thence North 62°24'14" East 200.49 feet; thence along the arc of a curve to the right, having a radius of 802.00 feet, the chord of which bears North 86°17'54" East, 649.70 feet; thence South 69°48'26" East, 353.69 feet; thence along the arc of a curve to the right, having a radius of 1440.00 feet, the chord of which bears South 66°12'33" East, 180.74 feet to the **Point of Beginning**, containing an area of 2.465 acres, more or less.


See Exhibit 'B' attached hereto and made part of this description.

End of Description

Exhibit 'A'

The Basis of Bearings for this description is the California State Plane Coordinate System, Zone 2, NAD 83.

This description has been prepared by me or under my direct supervision.


Kevin A. Heeney, P.L.S. 5914



10/09/2018
Date


CTA Engineering & Surveying
3233 Monier Circle
Rancho Cordova, CA 95742
916-638-0919

Exhibit 'B'


POINT OF COMMENCEMENT
 FND 3/4" C.I.P. L.S. 3279
 S01°03'22"W 224.10'
 S86°49'08"W 313.01'

GHABI
 119-080-19

LINE DATA TABLE		
LINE	BEARING	DISTANCE
L1	S01° 17' 57"W	77.72'
L2	N88° 42' 03"W	23.35'
L3	N17° 35' 46"W	55.16'
L4	S72° 24' 14"W	73.00'



CURVE DATA TABLE				
CURVE	RADIUS	DELTA	CH. BEARING	CH. DISTANCE
C1	1360.00'	$\Delta=7^{\circ}45'09''$	N65°55'52"W	183.88'
C2	20.00'	$\Delta=92^{\circ}35'08''$	N61°18'12"W	28.92'
C3	1350.00'	$\Delta=0^{\circ}35'16''$	N14°43'00"W	13.85'
C4	20.00'	$\Delta=103^{\circ}10'24''$	S66°00'34"E	31.34'
C5	1440.00'	$\Delta=7^{\circ}11'46''$	S66°12'33"E	180.74'



SEE SHEET 2 OF 2

OWNER: M.H. MOHANNA

A.P.N. 119-080-23

cta Engineering & Surveying
 Civil Engineering • Land Surveying • Land Planning
 3233 Monier Circle, Rancho Cordova, CA 95742
 T (916) 838-0219 • F (916) 838-2470 • www.ctaeng.com

DATE: 10/08/2018

SCALE: 1"=100'

DRAWN BY: KAH

JOB NO. 16-017-018

SHEET 1 OF 2


FEE ROAD RIGHT OF WAY

A PORTION OF THE S.E. QUARTER OF SECTION 6, T.9N., R.9E., M.D.M. COUNTY OF EL DORADO STATE OF CALIFORNIA


Exhibit 'B'

LINE DATA TABLE		
LINE	BEARING	DISTANCE
L1	S01° 17' 57"W	77.72'
L2	N88° 42' 03"W	23.35'
L3	N17° 35' 46"W	55.16'
L4	S72° 24' 14"W	73.00'

CURVE DATA TABLE				
CURVE	RADIUS	DELTA	CH. BEARING	CH. DISTANCE
C1	1360.00'	$\Delta=7^{\circ}45'09''$	N65°55'52"W	183.88'
C2	20.00'	$\Delta=92^{\circ}35'08''$	N61°18'12"W	28.92'
C3	1350.00'	$\Delta=0^{\circ}35'16''$	N14°43'00"W	13.85'
C4	20.00'	$\Delta=103^{\circ}10'24''$	S66°00'34"E	31.34'
C5	1440.00'	$\Delta=7^{\circ}11'46''$	S66°12'33"E	180.74'



SEE SHEET 1 OF 2



OWNER: M.H. MOHANNA

A.P.N. 119-080-23

DATE: 10/08/2018

SCALE: 1"=100'

DRAWN BY: KAH

JOB NO. 16-017-018

SHEET 2 OF 2

cta Engineering & Surveying

Civil Engineering • Land Surveying • Land Planning

3233 Monier Circle, Rancho Cordova, CA 95742

T (916) 836-0218 • F (916) 836-2479 • www.ctaeng.com

FEE ROAD RIGHT OF WAY

A PORTION OF THE S.E. QUARTER OF SECTION 6, T.9N., R.9E., M.D.M. COUNTY OF EL DORADO STATE OF CALIFORNIA

DATE: 10/09/2018

Exhibit 'A'

**APN 119-080-23
Public Service Easement**

All that real property situated in the County of El Dorado, State of California, being a portion of Parcel 1, as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 48 of Parcel Maps at page 80, lying within the Southeast One-Quarter of Section 6, T. 9 N., R. 9 E., M.D.M. and being more particularly described as follows:

Public Service Easement-1

COMMENCING at a $\frac{3}{4}$ " capped iron pipe, stamped "L.S. 3279", marking the Northwest corner of Parcel 'A'; as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 15 of Parcel Maps at Page 53; thence along the West Line of said Parcel 'A', South 01°03'22" West, 224.10 feet; thence South 86°49'08" West, 313.01 feet to the Northeast corner of said Parcel 1; thence along the East line of said Parcel 1, South 01°17'57" West, 577.12 feet to a point hereinafter referred to as Point 'A'; thence continuing along the East line of said Parcel 1, South 01°17'57" West, 77.72 feet to the Southeast corner of said Parcel 1; thence along the South line of said Parcel 1, North 88°42'03" West, 23.35 feet; thence leaving said South line along the arc of a non-tangent curve, concave to the Southwest, having a radius of 1360.00 feet, the chord of which bears North 65°55'52" West, 183.88 feet; thence North 69°48'26" West, 353.69 feet; thence along the arc of a curve to the left, having a radius of 722.00 feet, the chord of which bears North 74°49'29" West, 126.29 feet to the true POINT OF BEGINNING; thence continuing along the arc of a curve to the left, having a radius of 722.00 feet, the chord of which bears South 81°16'51" West, 467.19 feet; thence South 62°24'14" West, 78.79 feet; thence North 71°23'20" East, 124.93 feet; thence North 74°49'06" East, 110.29 feet; thence North 77°48'27" East, 135.52 feet; thence North 80°59'42" East, 44.16 feet; thence North 86°40'55" East, 60.98 feet; thence South 89°35'27" East, 69.82 feet to the POINT OF BEGINNING, containing 0.210 acres, more or less.

Public Service Easement-2

COMMENCING at the aforementioned Point 'A'; thence leaving the East line of said Parcel 1, along the arc of a non-tangent curve, concave to the Southwest, having a radius of 1440.00 feet, the chord of which bears North 66°12'33" West, 180.74 feet; thence North 69°48'26" West, 341.48 feet to the true POINT OF BEGINNING; thence continuing North 69°48'26" West, 12.21 feet; thence along the arc of a curve to the left, having a radius of 802.00 feet, the chord of which bears North 74°05'30" West, 119.83 feet to a point hereinafter referred to as Point 'B'; thence South 84°17'44" East, 38.11 feet; thence South 76°08'30" East, 73.30 feet; thence North 08°47'36" West, 52.24 feet; thence North 81°12'24" East, 15.00 feet; thence South 08°47'36" East, 70.46 feet to the POINT OF BEGINNING, containing 1,554 square feet, more or less.

Exhibit 'A'

Public Service Easement-3


COMMENCING at the aforementioned Point 'B'; thence along the arc of a curve, concave to the Southwest, having a radius of 802.00 feet, the chord of which bears North 85°07'49" West, 188.64 feet to the true POINT OF BEGINNING; thence North 89°08'38" West, 91.66 feet; thence South 84°43'12" West, 67.35 feet; thence South 67°21'58" West, 55.63 feet ; thence South 73°05'47" West, 131.04 feet; thence South 60°23'16" West, 59.26 feet; thence South 64°57'14" West, 155.23 feet to a point on the East line of an existing Public Service Easement as described in Document 2008-60082, Official Records of El Dorado County; thence along said East line, South 14°30'45" East, 14.73 feet; thence South 41°42'52" East, 6.37 feet; thence South 75°49'53" East, 4.89 feet; thence leaving said East line, North 62°24'14" East, 191.57 feet; thence along the arc of a curve to the right, having a radius of 802.00 feet, the chord of which bears North 75°15'35" East, 356.89 feet to the Point of Beginning, containing an area of 0.176 acres, more or less.

See Exhibit 'B' attached hereto and made part of this description.

End of Description

The Basis of Bearings for this description is the California State Plane Coordinate System, Zone 2, NAD 83.

This description has been prepared by me or under my direct supervision.


Kevin A. Heeney, P.L.S. 5914



10/09/2018
Date

CTA Engineering & Surveying
3233 Monier Circle
Rancho Cordova, CA 95742
916-638-0919

LINE DATA TABLE		
LINE	BEARING	DISTANCE
L1	S01° 17' 57"W	77.72'
L2	N88° 42' 03"W	23.35'
L3	S62° 24' 14"W	78.79'
L4	N80° 59' 42"E	44.16'
L5	N86° 40' 55"E	60.98'
L6	S89° 35' 27"E	69.82'
L7	N69° 48' 26"W	12.21'
L8	S84° 17' 44"E	38.11'
L9	S76° 08' 30"E	73.30'
L10	N08° 47' 36"W	52.24'
L11	N81° 12' 24"E	15.00'
L12	S08° 47' 36"E	70.46'
L13	N89° 08' 38"W	91.66'
L14	S84° 43' 12"W	67.35'
L15	S67° 21' 58"W	55.63'




Exhibit 'B'

POINT OF COMMENCEMENT

GHABI
119-080-19

S01°03'22"W 224.10'
S86°49'08"W 313.01'

CURVE DATA TABLE				
CURVE	RADIUS	DELTA	CH. BEARING	CH. DISTANCE
C1	1360.00'	Δ=7°45'09"	N65°55'52"W	183.88'
C2	722.00'	Δ=10°02'06"	N74°49'29"W	126.29'
C3	1440.00'	Δ=7°11'46"	N66°12'33"W	180.74'
C4	802.00'	Δ=8°34'07"	N74°05'30"W	119.83'
C5	802.00'	Δ=25°42'43"	N75°15'35"E	356.89'



DATE: 10/09/2018

OWNER:
M.H. MOHANNA

DATE: 10/08/2018
SCALE: 1"=100'

DRAWN BY: JCC
JOB NO. 16-017-018

SHEET 1 OF 2





A.P.N. 119-080-23

PUBLIC SERVICE EASEMENT

cta Engineering & Surveying
Civil Engineering • Land Surveying • Land Planning
3233 Mosier Circle, Rancho Cordova, CA 95742
T (916) 633-0919 • F (916) 633-2479 • www.cta.com

A PORTION OF THE S.E. QUARTER
OF SECTION 6, T.9N., R.9E., M.D.M.
COUNTY OF EL DORADO STATE OF CALIFORNIA

Exhibit 'B'



SEE SHEET 1 OF 2

NOTE: SEE SHEET 1 OF 2 FOR LINE/CURVE TABLES



OWNER:
M.H. MOHANNA

A.P.N. 119-080-23

DATE:
10/08/2018

SCALE:
1"=100'

DRAWN BY:
JCC

JOB NO.
16-017-018

SHEET
2 OF
2

cta Engineering & Surveying

Civil Engineering • Land Surveying • Land Planning
3233 Manier Circle, Rancho Cordova, CA 95742
T (916) 838-2919 • F (916) 838-2479 • www.cta.net

PUBLIC SERVICE EASEMENT

A PORTION OF THE S.E. QUARTER
OF SECTION 6, T.9N., R.9E., M.D.M.
COUNTY OF EL DORADO STATE OF CALIFORNIA

Exhibit 'A'

APN 119-080-23
Legal Description

All that real property situated in the County of El Dorado, State of California, being a portion of Parcel 1, as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 48 of Parcel Maps at page 80, lying within the Southeast One-Quarter of Section 6, T. 9 N., R. 9 E., M.D.M. and being more particularly described as follows:

Temporary Construction Easement – 1

COMMENCING at a $\frac{3}{4}$ " capped iron pipe, stamped "L.S. 3279", marking the Northwest corner of Parcel 'A'; as shown on that certain Parcel Map filed in the office of the County Recorder of said County in Book 15 of Parcel Maps at Page 53; thence along the West Line of said Parcel 'A', South 01°03'22" West, 224.10 feet; thence South 86°49'08" West, 313.01 feet to the Northeast corner of said Parcel 1; thence along the East line of said Parcel 1, South 01°17'57" West, 577.12 feet to a point hereinafter referred to as Point 'A' and the true **POINT OF BEGINNING**; thence leaving said East line, along the arc of a curve, concave to the Southwest, having a radius of 1440.00 feet, the chord of which bears North 66°12'33" West, 180.74 feet; thence North 69°48'26" West, 341.48 feet; thence North 08°47'36" West, 70.46 feet; thence South 81°12'24" West, 15.00 feet; thence South 08°47'36" East, 52.24 feet; thence North 76°08'30" West, 73.30 feet; thence North 84°17'44" West, 38.11 feet; thence along the arc of a non-tangent curve, concave to the South, having a radius of 802.00 feet, the chord of which bears North 85°07'49" West, 188.64 feet; thence North 89°08'38" West, 91.66 feet; thence South 84°43'12" West, 67.35 feet; thence South 67°21'58" West, 55.63 feet; thence South 73°05'47" West, 131.04 feet; thence South 60°23'16" West, 59.26 feet; thence South 64°57'14" West, 155.23 feet to a point on the Easterly line of the Landscape and Public Service Easement as described in Document No. 2008-060082, Official Records of El Dorado County; thence along said Easterly line, North 13°51'47" West, 15.29 feet; thence leaving said Easterly line, North 64°57'14" East, 151.67 feet; thence North 60°23'16" East, 60.33 feet; thence North 73°05'47" East, 131.96 feet; thence North 67°21'58" East, 57.17 feet; thence North 84°43'12" East, 70.44 feet; thence South 89°08'38" East, 92.11 feet; thence along the arc of a non-tangent curve, concave to the South, having a radius of 817.00 feet, the chord of which bears South 85°08'41" East, 191.04 feet; thence South 84°17'44" East, 38.41 feet; thence South 76°08'30" East, 51.85 feet; thence North 08°47'36" West, 44.73 feet; thence North 81°12'24" East, 45.00 feet; thence South 08°47'36" East, 76.62 feet; thence South 69°48'26" East, 332.64 feet; thence along the arc of a curve to the right, having a radius of 1455.00 feet, the chord of which bears South 66°21'13" East, 175.30 feet to a point on the East line of said Parcel 1; thence along said East line, South 01°17'57" West, 16.68 feet to the **POINT OF BEGINNING**, containing 0.524 acres, more or less.

Temporary Construction Easement - 2

COMMENCING at the aforementioned "Point A"; thence along the East line of said Parcel 1, South 01°17'57" West, 77.72 feet to the Southeast corner of said Parcel 1; thence along the South line of said Parcel 1, North 88°42'03" West, 23.35 feet to the true **POINT OF**

Exhibit 'A'


BEGINNING; thence leaving said South line along the arc of a non-tangent curve, concave to the Southwest, having a radius of 1360.00 feet, the chord of which bears North 65°55'52" West, 183.88 feet; thence North 69°48'26" West, 353.69 feet; thence along the arc of a curve to the left, having a radius of 722.00 feet, the chord of which bears North 74°49'29" West, 126.29 feet; thence North 89°35'27" West, 69.82 feet; thence South 86°40'55" West, 60.98 feet; thence South 80°59'42" West, 44.16 feet; thence South 77°48'27" West, 135.52 feet; thence South 74°49'06" West, 110.29 feet; thence South 71°23'20" West, 124.93 feet; thence South 62°24'14" West, 65.91 feet to a point on the East line of Bass Lake Road, as described in Document No. 2008-060082, Official Records of El Dorado County; thence along said East line, South 17°35'46" East, 15.23 feet; thence leaving said East line, North 62°24'14" East, 67.37 feet; thence North 71°23'20" East, 123.31 feet; thence North 74°49'06" East, 109.45 feet; thence North 77°48'27" East, 134.71 feet; thence North 80°59'42" East, 43.00 feet; thence North 86°40'55" East, 59.75 feet; thence South 89°35'27" East, 68.04 feet; thence along the arc of a non-tangent curve, concave to the South, having a radius of 707.00 feet, the chord of which bears South 74°46'24" East, 122.40 feet; thence South 69°48'26" East, 353.69 feet; thence along the arc of a curve to the right, having a radius of 1345.00 feet, the chord of which bears South 66°34'57" East, 151.32 feet to a point on the South line of said Parcel 1; thence along said South line, South 88°42'03" East, 34.22 feet to the **POINT OF BEGINNING**, containing 0.432 acres, more or less.

See Exhibit 'B' attached hereto and made part of this description.

End of Description

The Basis of Bearings for this description is the California State Plane Coordinate System, Zone 2, NAD 83.

This description has been prepared by me or under my direct supervision.


Kevin A. Heeney, P.L.S. 5914



10/02/2017
Date

CTA Engineering & Surveying
3233 Monier Circle
Rancho Cordova, CA 95742
916-638-0919

Exhibit 'B'

GHABI
119-080-19


POINT OF COMMENCEMENT
FND 3/4" C.I.P. L.S. 3279
S01°03'22"W 224.10'
S86°49'08"W 313.01'



CURVE DATA TABLE				
CURVE	RADIUS	DELTA	CH. BEARING	CH. DIST.
C1	R=1440.00'	$\Delta=07^{\circ}11'46''$	N66°12'33"W	180.74'
C2	R=802.00'	$\Delta=13^{\circ}30'29''$	N85°07'49"W	188.64'
C3	R=1455.00'	$\Delta=06^{\circ}54'26''$	S66°21'13"E	175.30'
C4	R=1360.00'	$\Delta=07^{\circ}45'09''$	N65°55'52"W	183.88'
C5	R=722.00'	$\Delta=10^{\circ}02'06''$	N74°49'29"W	126.29'
C6	R=707.00'	$\Delta=09^{\circ}55'54''$	S74°46'24"E	122.40'
C7	R=1345.00'	$\Delta=06^{\circ}26'58''$	S66°34'57"E	151.32'

SEE SHEET 2 FOR LINE DATA

MOHANNA M H
119-080-23



SEE SHEET 2 OF 2

PARCEL A PM 15-53
MOORHOUSE TR. 119-080-08
POINT OF BEGINNING
S1°17'57"W 577.12'



DATE: 10/02/2017

OWNER:
M.H. MOHANNA

A.P.N. 119-080-23

cta Engineering & Surveying
Civil Engineering • Land Surveying • Land Planning
3233 Monitor Circle, Rancho Cordova, CA 95742
T (916) 838-0219 • F (916) 838-2419 • www.cta.com

DATE: 04/20/2017
SCALE: 1"=100'
DRAWN BY: KAH
JOB NO. 16-017-018
SHEET 1 OF 2


TEMPORARY CONSTRUCTION EASEMENT

COUNTRY CLUB DRIVE
A PORTION OF THE S.E. QUARTER
OF SECTION 6, T.9N., R.9E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA

Exhibit 'B'

LINE DATA TABLE		
LINE	BEARING	DIST.
L1	N08°47'36"W	70.46'
L2	S81°12'24"W	15.00'
L3	S08°47'36"E	52.24'
L4	S67°21'58"W	55.63'
L5	S84°17'44"E	38.41'
L6	N08°47'36"W	44.73'
L7	S01°17'57"W	16.68'
L8	N89°35'27"W	69.82'
L9	S80°59'42"W	44.16'
L10	S62°24'14"W	65.91'
L11	N80°59'42"E	43.00'
L12	S89°35'27"E	68.04'



SEE SHEET 1 OF 2



DATE: 10/02/2017

OWNER: M.H. MOHANNA	DATE: 04/20/2017	DRAWN BY: KAH	SHEET 2 OF 2
	SCALE: 1"=100'	JOB NO. 16-017-007	
A.P.N. 119-080-23	TEMPORARY CONSTRUCTION EASEMENT		
 Civil Engineering • Land Surveying • Land Planning <small>3233 Manier Circle, Rancho Cordova, CA 95742 T (916) 638-0219 • F (916) 638-2479 • www.ctaes.net</small>		COUNTRY CLUB DRIVE A PORTION OF THE S.E. QUARTER OF SECTION 6, T.9N., R.9E., M.D.M.	
COUNTY OF EL DORADO STATE OF CALIFORNIA 19-0278 C 20 of 20			