

Carson Creek Unit 2A, Phase 1 Final Map TM06-1428-F






Exhibit A

**POR. SECS. 23 & 26, T.9N., R.8E., M.D.M.
CARSON CREEK
J-130**

117:57



1" equals 600'



15-0761 2D 2 of 54

Exhibit B

THIS MAP IS NOT A SURVEY. It is prepared by the El Dorado Co. Assessor's office for assessment purposes only. Area calculations and characteristics are not guaranteed. Users should verify items such as dimensions and acreage.

Acreages Are Estimates

Adjacent Map Pages Shown in Grey Text
Assessor's Block Numbers Shown in Ellipses
Assessor's Parcel Numbers Shown in Circles

Rev. APR 30, 2015

Assessor's Map Bk.117, Pg. 57
County of El Dorado, CA

REVISED TENTATIVE MAP


CARSON CREEK, UNIT 2

PHASE TWO PORTION OF "CARSON CREEK SPECIFIC PLAN" OVERALL LAYOUT AND ZONING

COUNTY OF EL DORADO
MAY, 2015

SHEET 1 OF 2

STATE OF CALIFORNIA
SCALE: 1"=200'



OWNERS / APPLICANT

LENNAR HOMES OF CALIFORNIA
1420 ROCKY RIDGE DR #320
ROSEVILLE, CA 95661

ENGINEER

cta Engineering & Surveying
Civil Engineering • Land Surveying • Land Planning
10000 Rockwood Lane, Suite 200
Roseville, CA 95661

MAP SCALE

1" = 200'

CONTOUR INTERVAL

CONTOUR INTERVAL: 5'

SOURCE OF TOPOGRAPHY

AERIAL PHOTOGRAPHY

SECTION, TOWNSHIP and RANGE

SECTIONS 15, 23 & 26, T. 9 N., R. 8 E. M.D.M.

ASSESSOR'S PARCEL NUMBERS

*117-570-10 *117-570-11 *117-570-14 *117-570-15
THE THREE APN'S COMPRISE A TOTAL OF 546.0 ACRES, THE PROPOSED PROJECT WHICH COMPRISES A PORTION OF THE 3 APN'S NOTED ABOVE CONSISTS OF 446.7 ACRES.

EXISTING/PROPOSED ZONING

SP-2 / MULTI FAMILY (MF), SINGLE FAMILY HIGH DENSITY (SFHD)

MINIMUM SINGLE FAMILY LOT AREA

4,577 SQUARE FEET

WATER, RECYCLED WATER SUPPLY & SEWAGE DISPOSAL

EL DORADO IRRIGATION DISTRICT

PROPOSED STRUCTURAL FIRE PROTECTION

EL DORADO HILLS COUNTY WATER DISTRICT (FIRE DEPT.)

DATE OF PREPARATION

MAY, 2015

ENGINEER'S CERTIFICATE

I HEREBY CERTIFY THAT TO THE BEST OF MY KNOWLEDGE THE LAND DEVELOPMENT KNOWN AS CARSON CREEK, UNIT 2 OF THE "CARSON CREEK SPECIFIC PLAN" HAS BEEN DESIGNED IN ACCORDANCE WITH THE SPECIFICATIONS AND GUIDELINES ESTABLISHED BY THE COUNTY OF EL DORADO.

DAVID R. PROSPERIO R.C.E. 34520 DATE 5-15-15

TOTAL AREA

299.96 ACRES


TOTAL NO. of LOTS/AREA per VILLAGE

VILLAGE 10	TOTAL.....634 RESIDENTIAL LOTS	91.29 AC.
LOTS A THRU D, F, H THRU Q, S, & V (LANDSCAPE)		9.11 AC.
LOT E (SOCIAL CLUB HOUSE)		2.75 AC.
LOT G (PUBLIC PARK)		4.65 AC.
LOT T (PRIVATE PARK)		1.00 AC.
LOT U (EID LIFT STATION)		0.23 AC.
*LOT R (INTRACT PRIVATE ROADS)		32.84 AC.
LOT R1 (INVESTMENT BLVD EXTENSION)		0.56 AC.
LOT LL-1, LL-2 (OPEN SPACE)		148.19 AC.
LOT LL-3, LL-4 (RESEARCH & DEVELOPMENT)		9.34 AC.
TOTAL, UNIT 2		299.96 AC.


*THE CONFIGURATION OF LOT R IS DEPENDENT ON THE UNIT PHASING AND ITS ASSOCIATED FINAL MAP.

NOTE

SUBDIVIDER RESERVES THE RIGHT TO ADJUST THE RESIDENTIAL LOT SIZES WITHIN THE TENTATIVE MAP IN CONFORMANCE WITH THE "CARSON CREEK SPECIFIC PLAN" DEVELOPMENT STANDARDS.




WEST VALLEY VALLEY VIEW SPECIFIC PLAN
TM #99-1359R




PHASING PLAN NOTICE

THE FILING OF MULTIPLE FINAL MAPS WILL BE COMPLETED FOR THIS PROJECT. BY PROVIDING THIS NOTICE, THE SUBDIVIDER SHALL NOT BE REQUIRED TO DEFINE THE NUMBER OR CONFIGURATION OF THE PROPOSED MULTIPLE FINAL MAPS. (PER THE SUBDIVISION MAP ACT, 2002 EDITION, SECTION 66456.1)



PHASING MAP
NOT TO SCALE




PATTERN	TYP. LOT SIZE	VILLAGE 10
(Diagonal lines)	65' x 105'	103
(Horizontal lines)	55' x 105'	165
(Vertical lines)	45' x 105'	366
UNIT 2 TOTAL		634

RESIDENTIAL LOT BREAKDOWN
SCALE: 1"=100'

PLANNING COMMISSION: _____
APPROVAL/DENIAL DATE: _____
BOARD OF SUPERVISORS: _____
APPROVAL/DENIAL DATE: _____

APPROVED
EL DORADO COUNTY
PLANNING COMMISSION
DATE: 5/15/15
BY: [Signature]
EXECUTIVE SECRETARY



REVISED TENTATIVE MAP
CARSON CREEK, UNIT 2
 PHASE TWO PORTION OF "CARSON CREEK SPECIFIC PLAN"
 OVERALL LAYOUT AND ZONING



COUNTY OF EL DORADO
 MAY, 2015

SHEET 2 OF 2

STATE OF CALIFORNIA
 SCALE: 1"=200'



APPROVED
 EL DORADO COUNTY
 PLANNING COMMISSION
 DATE: 5/11/15
 BY: [Signature]
 EXECUTIVE SECRETARY

cta Engineering & Surveying
 Civil Engineering • Land Surveying • Land Planning
 3233 Motor Club, Placentia, California, CA 92672
 P: 951.940.8800 • F: 951.940.8801 • www.cta.com

CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1"=300'

cta Engineering & Surveying



LINE	BEARING	DIST.
L1	S73° 39' 49"E	105.27'
L2	S16° 58' 15"W	17.18'
L3	S72° 31' 37"E	40.00'
L4	N89° 26' 35"E	84.83'
L5	N64° 14' 10"E	17.75'
L6	N89° 26' 35"E	264.94'
L7	S0° 33' 25"E	85.00'
L8	S0° 33' 25"E	40.00'
L9	S0° 33' 25"E	85.00'
L10	N89° 26' 35"E	364.88'
L11	N0° 33' 25"W	50.00'
L12	N89° 26' 35"E	250.00'
L13	N0° 33' 25"W	35.62'
L14	N89° 26' 35"E	105.00'
L15	N0° 33' 25"W	186.00'
L16	N89° 26' 35"E	7.42'
L17	N0° 33' 25"W	46.50'
L18	S43° 16' 12"E	20.99'
L19	N85° 45' 18"E	117.95'
L20	N81° 29' 57"E	134.48'
L21	N42° 09' 36"E	80.00'

REFERENCES

1. S.D. J-130
2. S.D. J-135
3. P.M. 36-115
4. P.M. 37-23

CURVE	RADIUS	DELTA	CH. BEARING	CH. DIST.
C1	20.00'	83°50'58"	S05°54'55"E	26.73'
C2	20.00'	83°50'58"	S89°45'52"E	26.73'
C3	540.00'	41°07'56"	N68°52'37"E	379.39'
C4	20.00'	90°01'11"	S44°26'00"W	28.29'
C5	20.00'	89°58'49"	S45°34'00"E	28.28'
C6	875.00'	12°39'26"	S16°48'28"W	192.90'
C7	20.00'	52°49'40"	S06°32'58"E	17.80'
C8	55.00'	101°51'11"	S31°03'41"E	85.40'
C9	20.00'	90°00'00"	N44°26'33"E	28.28'
C10	20.00'	90°00'00"	S45°33'25"E	28.28'
C11	100.00'	95°47'52"	N88°49'52"E	148.39'
C12	270.00'	42°47'01"	S66°21'57"E	196.96'
C13	50.00'	36°52'08"	S17°52'39"W	31.62'
C14	75.00'	80°48'48"	S04°05'41"E	97.23'
C15	50.00'	43°56'41"	S22°31'45"E	37.42'
C16	200.00'	04°19'04"	S02°42'57"E	15.07'
C17	70.00'	54°25'43"	N69°18'20"E	64.02'
C18	100.00'	48°57'09"	N64°51'33"E	82.86'

NOTES:

1. THIS SUBDIVISION CONTAINS 298.434 ACRES GROSS, CONSISTING OF 170 RESIDENTIAL LOTS, 10 LETTERED LOTS, 6 LARGE LOTS AND INVESTMENT BOULEVARD AND IS CONSISTENT WITH THE TENTATIVE MAP 06-1428 APPROVED BY THE PLANNING COMMISSION ON DECEMBER 12, 2012.
2. LOT 'R' SHOWN HEREON IS DESIGNATED AS A "PRIVATE STREET" FOR THE BENEFIT AND GENERAL USE OF THE RESIDENTIAL LOTS SHOWN HEREON AND SHALL BE GRANTED IN FEE TO THE HOMEOWNERS ASSOCIATION CREATED FOR THIS SUBDIVISION.
3. LOTS A, B, C, D, F, H, I AND J SHALL BE GRANTED IN FEE TO THE HOMEOWNER'S ASSOCIATION CREATED FOR THIS SUBDIVISION FOR USE AS LANDSCAPE CORRIDORS AND OPEN SPACE. LOT E SHALL BE GRANTED IN FEE TO THE HOMEOWNERS ASSOCIATION CREATED FOR THIS SUBDIVISION FOR USE AS A COMMUNITY FACILITIES SITE. LOT U SHALL BE GRANTED IN FEE TO THE EL DORADO IRRIGATION DISTRICT FOR USE AS A SEWER LIFT STATION SITE. LOTS LL-1 AND LL-2 SHALL BE GRANTED IN FEE TO THE HOMEOWNERS ASSOCIATION CREATED FOR THIS SUBDIVISION, TO BE USED AND MAINTAINED AS AN OPEN SPACE PRESERVE.
4. ALL FRONT LOT CORNERS FOR THE SIDE LOT LINES ARE MARKED BY A SLASH IN THE TOP OF CONCRETE CURB OR SIDEWALK ON THE LOT LINE PROJECTED. ALL REAR LOT CORNERS ARE MARKED BY A 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914 OR AS NOTED HEREON.
5. ALL DISTANCES ALONG CURVED LINES ARE CHORD DISTANCES. THE SUM OF INDIVIDUAL UNITS MAY NOT EQUAL THE OVERALL DUE TO ROUNDING.
6. THIS MAP AND THE LOTS SHOWN HEREON ARE SUBJECT TO THE WILDLAND FIRE SAFETY PLAN AND AMENDMENTS, PREPARED BY WILLIAM F. DRAPER, DATED OCTOBER 27, 2014, CONTAINING WILDFIRE MITIGATION MEASURES WHICH SHALL BE IMPLEMENTED.
7. THE STREETS INDICATED ACROSS LARGE LOTS SHOWN HEREON ARE NON-EXCLUSIVE ROAD AND PUBLIC UTILITY EASEMENTS AND ARE RESERVED FOR FUTURE DEDICATION AND WILL BE CONSTRUCTED WITH EACH SUBSEQUENT PHASE AND FINAL MAP.

NOTICE OF RESTRICTIONS

A NOTICE OF RESTRICTION RECORDED IN DOC. NO. _____ AFFECTS LL-3, LL-4, LL-5, LL-6, LL-7 & LL-8 BY LIMITING DEVELOPMENT TO PHASING PURPOSES ONLY.

A NOTICE OF RESTRICTION RECORDED IN DOC. NO. _____ AFFECTS LOTS 1,7,8,9,137 THROUGH 147 & 158 THROUGH 162 RELATED TO ENVIRONMENTAL NOISE ASSESSMENT.

ABANDONMENT OF EASEMENTS

THE FOLLOWING PUBLIC EASEMENTS ARE HEREBY ABANDONED PURSUANT TO SECTION 66434(G) OF THE GOVERNMENT CODE:


1. THOSE PORTIONS OF THE 50' NON-EXCLUSIVE ROAD AND PUBLIC UTILITY EASEMENTS SHOWN ON S.D. J-130 LYING WITHIN VIGO DRIVE (LOT R) AND INVESTMENT BLVD.

BASIS OF BEARINGS

THE BASIS OF BEARINGS FOR THIS SURVEY IS IDENTICAL WITH THE LARGE LOT FINAL MAP OF CARSON CREEK, RECORDED IN THE OFFICE OF THE COUNTY RECORDER OF EL DORADO COUNTY IN BOOK J OF MAPS, PAGE 130, BASED ON MONUMENTS SHOWN AS FOUND HEREON.

LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- FOUND 3/4" C.I.P. STAMPED LS 5914
- FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- SET 3/4" C.I.P. STAMPED LS 5914
- SET 1 1/2" C.I.P. STAMPED LS 5914
- SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- E.V.A. EMERGENCY VEHICLE ACCESS
- (OA) OVERALL



CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1"=300'



SHEET 3 OF 12



SEE SHEET 2 FOR BASIS OF BEARINGS,
NOTICE OF RESTRICTIONS AND NOTES.

LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- FOUND 3/4" C.I.P. STAMPED LS 5914
- FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- SET 3/4" C.I.P. STAMPED LS 5914
- SET 1 1/2" C.I.P. STAMPED LS 5914
- SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- //// VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- E.V.A. EMERGENCY VEHICLE ACCESS
- (OA) OVERALL

LINE	BEARING	DIST.
L1	S70° 45' 25"W	135.63'
L2	S56° 33' 39"W	82.11'
L3	S43° 12' 30"W	26.49'
L4	S44° 23' 39"E	48.42'
L5	S14° 31' 52"W	139.89'
L6	S47° 57' 09"W	100.45'
L7	S44° 02' 25"W	205.74'
L8	S42° 05' 22"E	436.03'
L9	S65° 28' 29"E	183.81'
L10	S49° 17' 50"E	143.75'
L11	S40° 36' 29"E	344.30'
L12	N28° 40' 03"E	142.97'
L13	N44° 40' 24"E	67.33'
L14	S84° 27' 55"E	64.02'
L15	N24° 59' 59"E	0.14'
L16	S40° 33' 26"E	213.13'
L17	S29° 30' 38"W	259.22'
L18	S60° 28' 10"E	192.32'
L19	S54° 29' 49"E	167.92'
L20	S46° 00' 36"E	263.47'
L21	S40° 33' 26"E	40.16'
L22	S24° 59' 59"W	92.84'
L23	S46° 51' 40"W	172.91'
L24	S12° 33' 17"W	101.38'
L25	N38° 51' 56"E	64.70'
L26	N78° 47' 32"E	99.81'
L27	N19° 17' 03"E	59.88'
L28	N43° 52' 16"E	74.28'
L29	N88° 53' 01"W	104.11'
L30	N83° 41' 16"W	91.49'
L31	N56° 35' 05"W	277.84'
L32	N55° 53' 02"W	138.13'
L33	S45° 22' 49"W	164.48'
L34	S40° 22' 58"W	18.85'
L35	S83° 46' 41"W	11.61'
L36	N87° 45' 27"W	96.65'
L37	N87° 45' 27"W	4.95'
L38	S00° 39' 52"E	200.45'
L39	S11° 40' 56"E	134.66'
L40	S11° 27' 12"W	72.84'
L41	S39° 04' 15"W	111.75'
L42	S47° 23' 20"W	87.56'
L43	S52° 42' 00"W	122.65'
L44	S57° 43' 51"W	226.03'
L45	S68° 04' 02"W	100.92'
L46	S53° 16' 31"W	114.34'
L47	S55° 48' 29"W	162.34'

CURVE	RADIUS	DELTA	CH. BEARING	CH. DIST.
C1	R=200.00'	Δ=43°23'43"	N62°04'50"E	147.88'
C2	R=100.00'	Δ=72°33'16"	N55°57'55"E	118.34'
C3	R=270.00'	Δ=42°47'01"	S66°21'57"E	196.96'



CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1" = 40'




SHEET 4 OF 12


SEE SHEET 2 FOR BASIS OF BEARINGS,
NOTICE OF RESTRICTIONS AND NOTES.

LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- ⊗ FOUND 3/4" C.I.P. STAMPED LS 5914
- FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- SET 3/4" C.I.P. STAMPED LS 5914
- SET 1 1/2" C.I.P. STAMPED LS 5914
- SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- ⊗ VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- E.V.A. EMERGENCY VEHICLE ACCESS
- (OA) OVERALL



CURVE TABLE				
CURVE #	RADIUS	CH BEARING	DELTA	CH LENGTH
C1	561.00'	S62° 43' 16"W	2°17'13"	22.39'
C2	561.00'	S60° 24' 34"W	2°20'11"	22.88'



PARCEL 60
PM 36-115

PARCEL 61
PM 36-115

1673.00' (OA)

SEE SHEET 5

CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1" = 40'



SHEET 5 OF 12


SEE SHEET 2 FOR BASIS OF BEARINGS,
NOTICE OF RESTRICTIONS AND NOTES.

LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- FOUND 3/4" C.I.P. STAMPED LS 5914
- FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- SET 3/4" C.I.P. STAMPED LS 5914
- SET 1 1/2" C.I.P. STAMPED LS 5914
- SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- /// VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- E.V.A. EMERGENCY VEHICLE ACCESS
- (OA) OVERALL

CURVE TABLE				
CURVE #	RADIUS	DELTA	CH. BEARING	CH. LENGTH
C1	60.00'	38°23'08"	N70°48'26"W	39.45'
C2	60.00'	32°57'59"	S73°31'01"W	34.05'
C3	60.00'	44°05'44"	S02°01'11"W	45.05'
C4	60.00'	32°57'59"	S40°33'02"W	34.05'
C5	60.00'	19°28'16"	S29°45'49"E	20.29'
C6	35.00'	36°52'15"	S18°59'32"E	22.14'
C8	90.00'	31°01'33"	S21°22'15"E	48.14'
C9	90.00'	36°32'51"	S12°24'56"W	56.44'

CURVE TABLE				
CURVE #	RADIUS	DELTA	CH. BEARING	CH. LENGTH
C10	50.00'	36°52'08"	N17°52'39"E	31.62'
C13	90.00'	0°32'38"	N37°09'21"W	0.85'
C14	50.00'	43°56'41"	S22°31'45"E	37.42'
C15	50.00'	43°56'47"	N21°24'59"E	37.42'
C16	50.00'	36°52'15"	N18°59'32"W	31.62'
C17	20.00'	56°35'53"	S27°44'32"W	18.96'
C18	20.00'	90°00'00"	N44°26'35"E	28.28'



PARCEL G2
PM 36-115

PARCEL G3
PM 36-115

LOT A
2.90 Ac
(P.U.E.)

CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1" = 40'




SHEET 6 OF 12

SEE SHEET 2 FOR BASIS OF BEARINGS,
NOTICE OF RESTRICTIONS AND NOTES.

SEE SHEET 5

LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- FOUND 3/4" C.I.P. STAMPED LS 5914
- FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- SET 3/4" C.I.P. STAMPED LS 5914
- SET 1 1/2" C.I.P. STAMPED LS 5914
- SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- //// VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- E.V.A. EMERGENCY VEHICLE ACCESS
- (OA) OVERALL



CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1" = 40'




SHEET 7 OF 12

SEE SHEET 2 FOR BASIS OF BEARINGS,
NOTICE OF RESTRICTIONS AND NOTES.

LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- FOUND 3/4" C.I.P. STAMPED LS 5914
- FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- SET 3/4" C.I.P. STAMPED LS 5914
- SET 1 1/2" C.I.P. STAMPED LS 5914
- ⊙ SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- //// VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- E.V.A. EMERGENCY VEHICLE ACCESS
- (OA) OVERALL



LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- ✱ FOUND 3/4" C.I.P. STAMPED LS 5914
- FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- SET 3/4" C.I.P. STAMPED LS 5914
- SET 1 1/2" C.I.P. STAMPED LS 5914
- SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- //// VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- E.V.A. EMERGENCY VEHICLE ACCESS
- (OA) OVERALL


CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1" = 40'



SHEET 8 OF 12




SEE SHEET 2 FOR BASIS OF BEARINGS,
NOTICE OF RESTRICTIONS AND NOTES.

SEE SHEET 7

SEE SHEET 2

SEE SHEET 9



LL 5
31.995 Ac

LL 6
66.378 Ac

SEE SHEET 2

CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1" = 40'




SHEET 9 OF 12

LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- ⊗ FOUND 3/4" C.I.P. STAMPED LS 5914
- FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- ⊗ SET 3/4" C.I.P. STAMPED LS 5914
- ⊗ SET 1 1/2" C.I.P. STAMPED LS 5914
- ⊗ SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- //// VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- (OA) OVERALL



SEE SHEET 2 FOR BASIS OF BEARINGS,
NOTICE OF RESTRICTIONS AND NOTES.



CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1" = 40'

cta Engineering & Surveying


SHEET 11 OF 12

SEE SHEET 2 FOR BASIS OF BEARINGS,
NOTICE OF RESTRICTIONS AND NOTES.

LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- ⊗ FOUND 3/4" C.I.P. STAMPED LS 5914
- ⊙ FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- ⊘ SET 3/4" C.I.P. STAMPED LS 5914
- ⊙ SET 1 1/2" C.I.P. STAMPED LS 5914
- ⊙ SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- ▬ VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- E.V.A. EMERGENCY VEHICLE ACCESS
- (OA) OVERALL

Curve Table				
CURVE #	RADIUS	DELTA	CH.BEARING	CH.DIST.
C1	42.00'	20°35'14"	S43°37'12"E	15.01'
C2	42.00'	9°14'08"	S37°56'39"E	6.76'
C3	42.00'	11°21'06"	S48°14'16"E	8.31'



CARSON CREEK UNIT 2A, PHASE 1

BEING LOTS 12, 14, 15, 16 AND A PORTION OF LOT 11 OF S.D. J-130
BEING A PORTION OF SECTIONS 23 & 26, T. 9 N., R. 8 E., M.D.M.

COUNTY OF EL DORADO STATE OF CALIFORNIA
OCTOBER, 2017 SCALE: 1" = 60'






SHEET 12 OF 12

SEE SHEET 2 FOR BASIS OF BEARINGS,
NOTICE OF RESTRICTIONS AND NOTES.

LEGEND

- DIMENSION POINT, NOTHING FOUND OR SET
- ⊗ FOUND 3/4" C.I.P. STAMPED LS 5914
- FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED LS 5914
- FOUND MONUMENT AS NOTED
- ⊗ SET 3/4" C.I.P. STAMPED LS 5914
- ⊗ SET 1 1/2" C.I.P. STAMPED LS 5914
- ⊗ SET SURVEY SPIKE AND WASHER STAMPED LS 5914
- /// VEHICULAR ACCESS RESTRICTION
- P.U.E. PUBLIC UTILITY EASEMENT
- S.D.E. STORM DRAIN EASEMENT
- E.V.A. EMERGENCY VEHICLE ACCESS
- (OA) OVERALL



SEE SHEET 2

Verification Conformance to Conditions of Approval

The following details the conditions of approval for the Carson Creek Unit 2 Tentative Subdivision Map as approved on December 2012 (original map) and July 2015 (revised map). As applicable, each condition is substantiated with a response verifying conformance.

1. The Tentative Subdivision Map, Minor Modifications to the CCSP, and Design Waivers are based upon and limited to compliance with the project description, the Planning Commission hearing exhibits marked Exhibits M and N, and conditions of approval set forth below. Any deviations from the project description, exhibits or conditions must be reviewed and approved by the County for conformity with this approval. Deviations may require approved changes to the permit and/or further environmental review. Deviations without the above described approval will constitute a violation of permit approval. The project description is as follows:
 - A. Tentative Subdivision Map creating a residential subdivision creating 634 residential lots ranging from 4,000 square feet to 16,390 square feet, two large lettered lots for future multifamily residential development, five private recreational lots, 13 landscape lots, one open space lot, two landscape/access lots, one park lot, two private road lots, one utility lot (pump station), a Remainder parcel, and a phasing plan;
 - B. Administrative modifications to the Carson Creek Specific Plan including:
 1. Amendment to the Circulation Plan as follows:
 - A. Construction of a secondary point of road access connection to Investment Blvd;
 - B. Construction of 6-foot wide sidewalk on one side of the internal residential collector (promenade); and
 - C. Removal of sidewalks within residential courts; and
 2. Amendment to the Land Use Plan deleting the identified Sheriffs and Fire Station sites; and
 - C. Design Waivers of the following El Dorado County Design and Improvement Standard Manual (DISM) road standards:
 1. Construction of Carson Crossing Drive encroachment onto Golden Foothill Parkway based on Standard Plan 103E without the 100-foot tapers;
 2. Construction of all proposed encroachments onto Carson Crossing Drive based on Standard Plan 103D without the 100-foot tapers;
 3. Construction of dead-end cul-de-sac in excess of 500 feet located at the southern of the project;
 4. Reduction of cul-de-sacs and knuckle rights-of-ways from 60 feet to 50 feet and curb face radius from 50 feet to 44.5 feet;
 5. Reduction of minimum gutter slope to 0.45%;
 6. Reduction of sidewalk widths from 6-foot to 4-foot for residential streets; and
 7. Reduction of residential street right-of-way from 50 feet to 40 feet.

(Revised Project Description under TM06-1428-R)

Revision to approved Carson Creek Unit 2 Tentative Subdivision Map consisting of the following modifications:

Exhibit E

- 1) Modify approved Phasing Plan;
- 2) Re-design alley-load residential lots with standard front load street frontage;
- 3) Realignment of on-site trail at Lot G Park;
- 4) Relocate sewer lift station;
- 5) Addition of landscape lots along Promenade area;
- 6) Eliminate the roadway loop at the southern portion of the project area and replace it with the roadway stubs fire department turn-around(s) and;
- 7) Eliminate Condition of Approval No.31 involving a 30-acre regional park.

The grading, development, use, and maintenance of the property, the size, shape, arrangement, and location of structures, parking areas and landscape areas, and the protection and preservation of resources shall conform to the project description above and the hearing exhibits and conditions of approval below. The property and any portions thereof shall be sold, leased or financed in compliance with this project description and the approved hearing exhibits and conditions of approval hereto. All plans must be submitted for review and approval and shall be implemented as approved by the County.

Response: Acknowledged. No response necessary.

2. As a condition of approval of all tentative maps, a minimum 6-foot-tall wood or other solid fence shall be required to be constructed for all parcels adjacent to the boundaries of the Specific Plan. Materials shall be those specified in the revised acoustical analysis for the project.

Response: Condition satisfied. In accordance with the Carson Creek Specific Plan, fencing will be constructed along the boundaries of the subdivision.

3. An updated open space management plan shall be prepared by the developer, subject to review and approval by the El Dorado Hills CSD. The plan shall include wild fire management plans for the open space.

Response: Condition satisfied. The Long-Term Open Space Management Plan (dated May 25, 2017) has been reviewed and approved by the El Dorado Hills Community Services District.

4. If parkland is dedicated to the EDHSCD, prior to County approval of any final map, the developer shall show evidence of a recorded agreement with the El Dorado Hills Community Services District (EDHSCD) for the location, size, park improvements (including water meters and sewer hook ups), maintenance, and timing of dedication and acceptance of parks throughout the Specific Plan area.

The developer will be required to provide a Phase I environmental assessment of land to be dedicated to a public agency.

Response: Condition satisfied. Applicable parks required of the project have been satisfied with the executed Parkland Agreement dated April 2015. As part of park site assessment, a Phase 1 environmental assessment shall be reviewed by the EDHCSD

5. A financing mechanism or mechanisms, such as a Landscaping and Lighting District (LLAD) for development and maintenance of parks, and for maintenance of open space, landscaping, lighting, fencing, trails, walkways, corridors, signage, sound walls, entry monuments, and other common or public areas shall be determined prior to approval of the final map: Improvement plans for the above referenced items will be submitted to the El Dorado Hills Community Services District (EDHCSD) for approval, and the financing mechanisms shall be in place prior to issuance of building permits (section 5.2 of the Carson Creek Specific Plan). Upon annexation of this project into the EDHCSD; the Carson Creek Specific Plan area shall be subject to the adopted park impact fee imposed for new development within the EDHCSD boundary and will be paid by the developer at the time a building permit is issued.

Response: This condition has been waived with the execution of the Pre-Annexation Agreement between El Dorado Hills CSD and Developer (Euer Ranch, AKT Mosher Partners, et al). The waiver was in response to Mitigation Measure 5-3 of the Carson Creek Specific Plan EIR and condition of approval No.67 of the Euer Ranch Tentative Map.

6. As a condition of approval of all tentative maps, a wood or other solid fence, at least six feet in height, will be constructed by the developer for all residential lots adjacent to the boundaries of the Specific Plan:

Agricultural fencing per County Resolution No. 98A-90 shall be required along the Sacramento/El Dorado County line in any location not adjacent to a residential lot/parcel.

The CC&Rs will specify the fence design approval process. Fence design will be as approved by the El Dorado Hills Community Services District and the appropriate design review committee.

The developer will provide a funding mechanism, such as a homeowners association or a Landscaping and Lighting District, for the maintenance of fencing adjacent to open space.

Response: Condition satisfied. Satisfaction of Conditions of Approval Nos. 2 and 5 warrants satisfaction of this condition.

7. The developer will be required to provide water meters for all residential lots, parks, landscaped corridors, and open space parcels. (Costs of water meters for parks may or may not be a credit to developer pending negotiations with EDHCSD Board of Directors.

Response: Condition satisfied. The applicant has provided an EID meter letter detailing the required amount of meters to provide water and sewer service.

8. The filing of tentative map and recording of the final map shall establish the appropriate zoning.

Response: Condition satisfied. In accordance with the Carson Creek Specific Plan, zoning designation for the subdivision has been approved and will be applied with Final Map recordation.

The following are Mitigation Measures from the CCSP EIR:

9. Golden Foothills Parkway at Carson Creek
- a) Use native plant species as the majority of those planted in the proposed 30-foot greenbelt to maximize a compatible visual relationship with the surrounding natural terrain and vegetation.
 - b) Require use of natural colored roof materials in project developments to maximize consistency with the surrounding natural environment and to minimize stark visual contrasts.
 - c) Use natural components in fencing materials (e.g., wood, stone, and brick) in developments along Carson Creek to enhance visual compatibility with the natural surroundings of the site.
 - d) Use natural components in pedestrian trail features (e.g., fences, trail materials) to enhance visual compatibility with the natural surroundings of the site.
 - e) Retain unobstructed views of Carson Creek from locations along Golden Foothills Parkway.

Response: Condition satisfied. Design materials in accordance with the Carson Creek Specific Plan shall be implemented through the CCR's by the private Homeowner's Association and Architectural Review Committee. Where applicable, subdivision design incorporates views of Carson Creek.

10. Phase 1 (Grading Phase) Construction Emissions
- a) The project applicant shall comply with El Dorado County APCD Rule 223 as required by the Air Pollution Control Officer. The project applicant shall prepare a fugitive dust control plan to be submitted to, and approved by, the APCD prior to the commencement of construction. Control measures to be outlined in the plan may include, but are not limited to, the following:
 - Application of water or suitable chemicals Or other specified covering on materials stockpiles, wrecking activity, excavation, grading, sweeping, clearing of land, solid waste disposal operations, or construction or

demolition of buildings or structures (all exposed soil shall be kept visibly moist during grading);

- Installation and use of hoods, fans and filters to enclose, collect, and clean the emissions of dusty materials;
- Covering or wetting at all times when in motion of open-bodied trucks, trailer or other vehicles transporting materials which create a nuisance by generating particulate matter in areas where the general public has access;
- Application of asphalt, oil, water or suitable chemicals on dirt roads;
- Paving of public or commercial parking surfaces;
- Removal from paved streets and parking surfaces of earth or other material which has a tendency to become airborne;
- Limiting traffic speeds on all unpaved road surfaces to 15 mph;
- Suspending all grading operations when wind speeds exceed 20 miles per hour(including instantaneous gusts);
- Alternate means of control as approved by the Air Pollution Control Officer.

b) Construction equipment engines shall be maintained in proper operating condition.

Response: Condition satisfied. The approved Improvement Plans for the subdivision incorporates all applicable air quality measures including Fugitive Dust Control Plan.

11. Phase II (Facilities Phase) Construction Emissions

- a) Low emission mobile construction equipment shall be used (e.g., tractor, scraper, dozer, etc.)
- b) Construction equipment engines shall be maintained in proper operating condition.
- c) Low-emission stationary construction equipment shall be used,
- d) A trip reduction plan shall be developed and implemented to achieve 1.5 average vehicle occupancy (AVO) for construction employees.
- e) Construction activity management techniques, such as extending construction period, reducing number of pieces used simultaneously, increasing distance between emission sources reducing or changing hours of construction, and scheduling activity during off-peak hours shall be developed and implemented.
- f) The project applicant shall comply with El Dorado County APCD Rule 224.
- g) The project applicant shall comply with El Dorado County APCD Rule 215.

Response: Condition satisfied. The approved Improvement Plans for the subdivision incorporates all applicable air quality measures including Fugitive Dust Control Plan.

12. Stationary Source Emissions

- a) The applicant shall incorporate energy-saving design features into future levels of project implementation as feasible and appropriate. The feasibility and appropriateness of each measure can best be determined at future, more-detailed levels of planning. These design features may include, but are not limited to, the following:
- 1) Shade trees;
 - 2) Energy-efficient and automated air conditioners;
 - 3) Double-pane glass in all windows;
 - 4) Energy-efficient parking lot lights;
 - 5) Adequate ventilation systems for enclosed parking facilities;
 - 6) Solar or low-emission water heaters;
 - 7) Energy-efficient lighting and lighting controls;
 - 8) Central water heating systems;
- b) The applicant, future successors in interest or future homebuilders shall install only EPA-certified woodstoves and fire places.

Response: Condition satisfied. Residential units within the subdivision will be equipped with energy efficient features including solar panels, low E2 window, Title 24 compliant gas water heaters, energy efficient lighting in accordance with California Building Code.

13. Regional Mobile Source Emissions - The County shall coordinate with the Folsom, El Dorado, Cordova TMA to consider including the project site within the TMA's jurisdiction.

Response: The County is part of the on-going efforts to ensure high air quality standards at regional level.

14. Short-Term Construction Noise - Construction activities not associated with road infrastructure improvements shall be conducted in accordance with the County noise regulation or limited to the following hours and days: Between the hours of 7:00 a.m. and 5:00 p.m. on any weekday; Between the hours of 8:00 a.m. and 5:00 p.m. on Saturdays; Prohibited on Sundays and holidays

At the time of the letting of the construction contract, it shall be demonstrated that engine noise from excavation equipment would be mitigated by keeping engine doors closed during equipment operation. For equipment that cannot be enclosed behind doors, lead curtains shall be used to attenuate noise.

Response: **Condition satisfied.** The approved construction and Improvement Plans for the subdivision include measures to lessen the effects construction noise in accordance with specific plan and/or County standards.

15. Increased Traffic Noise

Where the development of a project could result in the exposure of noise-sensitive land uses to existing or projected future traffic noise levels in excess of the applicable County noise standards, the County shall require an acoustical analysis to be performed prior to the approval of such projects. Where acoustical analysis determines that the project would contribute to traffic noise levels in excess of applicable County noise standards at proposed on-site or planned future off-site noise sensitive uses, the County shall require the implementation of noise attenuation measures, such as setback, sound barrier walls, or noise berms, as necessary to reduce traffic noise levels at proposed noise sensitive uses to conform with the applicable County standards.

In accordance with the recommendations of the Environmental Noise Assessment prepared by Bollard Acoustical Consultants (dated January 21, 2009), the following provisions shall be implemented:

- a) An 8-foot tall solid noise barrier shall be constructed at the locations shown in Figure 1 of the noise assessment to reduce noise levels in future backyard areas of the affected residential lots to 60 dB Ldn or less. Conformance with this condition shall be verified by Planning Services Division.
- b) To ensure compliance with the County's 45 dB Ldn interior noise level standard, all second-floor bedroom windows of the residences constructed adjacent to Carson Crossing Drive from which that roadway would be visible have a minimum STC rating of 30. A Notice of Restriction shall be recorded with the Final Map for the affected lots requiring that the above requirement shall be implemented with the residential building permits for the affected lots. The language of the notice shall be reviewed and approved by Planning Services Division prior to recordation.

Response: Condition satisfied. Subdivision improvements include construction of an 8-foot tall sound wall along the residential lots (Lots 1, 7, 8 and 9) adjacent Carson Crossing Drive on the northeastern part of the subdivision, installation for STC 30 rated windows on 2-story residential units, and recordation of a Notice of Restriction regarding application of these measures to lessen vehicular noise along Carson Crossing Drive.

16. Stationary Source Noise

Where the development of a project could result in the exposure of on-site noise-sensitive land uses to projected on-site or off-site stationary source noise levels in excess of the applicable County noise standards the County shall require an acoustical analysis to be performed prior to the approval of such projects. Where acoustical analysis determines that stationary source noise levels would exceed applicable County noise standards at proposed on-site noise sensitive uses, the County shall require the implementation of noise attenuation measures, such as setbacks, sound barrier walls, or noise berms, as necessary to reduce stationary source noise levels at proposed noise sensitive uses to conform to the applicable County standards.

In accordance with the recommendations of the Environmental Noise Assessment prepared by Bollard Acoustical Consultants (dated January 21, 2009) for Unit 2 Tentative Map, the following provisions shall be implemented:

- a) A copy of the disclosure statement detailing the potential operational impacts from adjacent uses shall be provided to the future residents of the residential subdivision. Prior to recordation of the first residential final map, the applicant shall provide a copy of the disclosure statement for review and approval by the Development Services-Planning Division.
- b) Air conditioning shall be included in all residences to allow occupants to close doors and windows as desired to achieve additional acoustic isolation from the commercial noise source in the project vicinity and maintain a 45 dB interior noise level. A Notice of Restriction shall be recorded with the Final Map for the affected lots requiring that the above requirement shall be implemented with the residential building permits. The language of the notice shall be reviewed and approved by Planning Services Division prior to recordation.
- c) The applicant shall coordinate with El Dorado Irrigation District (EID) to ensure that acoustic retrofits and upgrades to the emergency generator building are constructed or an 8-foot tall solid barrier shall be constructed along the southern and western property lines of the generator site. Upgrades to the generator building would require the use of acoustically absorptive materials at the interior of the generator building, silencers at both cooling air inlet and exhaust ports, and upgraded doors. If the lift station is abandoned, then a 6-foot tall barrier shall be required at the nearest residences to provide shielding from the boat storage facility. Conformance with this condition shall be verified by Planning Services Division.
- d) Prior to recordation of first residential lot final map that includes lots subject to DST noise impacts greater 45 dB, the applicant shall: 1) coordinate with DST to develop industrial noise control measures which could be implemented at the source of the noise (i.e. acoustical silencers, partial enclosures of the noise generating equipment, procurement of quieter equipment, etc.) to reduce the size of the 45 dB Leq contour to the area where no residences are proposed. The applicant shall coordinate in writing with Planning Services Division on the status of the applicant's coordination with DST; 2) provide for review by Planning Services Division an updated acoustical study detailing the necessary standards to minimize the noise impact. Until noise control measures described in b) above or any other mitigation measures can be implemented and verified as being effective, only residential final map in areas beyond the 45 dB Leq contour (as shown in Figure 4 of the assessment) shall be recorded and allowed to be developed.

Response: Condition satisfied. a) A disclosure statement detailing the existence of potential non-residential noise sources in the area has been reviewed and approved by the department; b) All residences shall be equipped with air conditioning units in order maintain 45 db interior noise level (with closed windows and doors). Affected lots shall be subject to

Notice of Restriction implementing these requirements; c) The previously identified site for an off-site sewer lift station has been relocated approximately 1,000 feet west of the nearest residential lots along Carson Crossing Drive; therefore, the previously identified noise from the lift station and required noise reducing measure are no longer applicable; d) The applicant submitted an updated Acoustical Noise study (dated July 10, 2017) analyzing the noise impacts from the current DST operations adjacent to the east. The study concluded that the noise levels at the proposed residential lots are not anticipated to exceed the 45 db nighttime exterior performance standard. Nevertheless, and as recommended in the study, the applicant shall implement additional measures including installation of windows with an upgraded noise rating of Sound Transmission Class (STC) Rating 32 in all residences within 1,400 feet of the common property line with DST. Installation of these windows shall be verified during review of residential building permits.

A Notice of Restriction (NOR) shall be recorded with the Final Map on lots (Lots 137 through 147 and 158 through 162) within the 45 db noise radius detailing the necessary installation of air conditioning units in order to be consistent with the required noise levels.

The applicant has coordinated with the operators of DST facilities on the requirements of this condition, conclusions of the updated acoustical study, and the identified measures that would be implemented to ensure compliance with the noise standards. No additional measures have been determined to be necessary between the applicant and DST, as long as the conclusion and identified measures of the acoustical study are fully implemented.

17. Loss of Wetlands

- a) Prior to issuance of a grading permit, a Stream Bed Alteration Agreement shall be obtained from CDFG, pursuant to §1600 of the California Fish and Game Code, for each stream crossing and any other activities affecting the bed, bank, or associated riparian vegetation of the stream. If required, the project applicant shall coordinate with CDFG in developing appropriate mitigation, and shall abide by the conditions of any executed permits.
- b) Grading activities shall incorporate appropriate erosion control measures as provided in the El Dorado County Grading Ordinance. Appropriate runoff controls such as berms, storm gates, detention basins, overflow collection areas, filtration systems, and sediment traps shall be implemented to control situation, and the potential discharge of pollutants into drainages.

Response: Condition satisfied. All required regulatory permits for wetland impacts have been acquired and grading activities implemented necessary control measures.

18. Liquefaction

- a) The El Dorado County Department of Transportation (DOT) shall consult with the El Dorado County Planning Department during the grading permit approval process

to ensure that earth resources impacts related to development in the Carson Creek Specific Plan area are sufficiently addressed.

- b) Prior to the approval of a grading permit for development in the Carson Creek drainage, the applicant shall submit to, and receive approval from, the El Dorado County Department of Transportation (DOT) a soils and geologic hazards report meeting the requirements for such reports provided in the El Dorado County Grading Ordinance. If proposed improvements to the Carson Creek drainage would be located in areas identified as susceptible to soils or geologic hazards, proposed improvements to the Carson Creek drainage shall be designed to prevent failure or damage due to such hazards.

Response: Condition satisfied. All soils and geological reports evaluating the potential hazards associated with the development have been reviewed and approved by County Engineer as part of grading permit review.

19. Ground Staking

Prior to the issuance of building permits all structures shall be designed in accordance with the Uniform Building Code (UBC), Chapter 23. Although wood frame buildings of not more, than two stories in height in unincorporated areas are exempt under the California Earthquake Protection Law, structures shall adhere to the design factors presented for UBC Zone 3, as a minimum; Final design standards shall be in accordance with 'the findings of detailed geologic and geotechnical analyses for proposed building sites.

Prior to the approval of subdivision maps in the vicinity of the Mormon Island Fault Zone, a ground acceleration analysis shall be conducted for the Mormon Island Fault Zone. All structures shall be designed in accordance with the ground acceleration analysis for the Mormon Island Fault Zone and the on-site ground accelerations anticipated from the Bear Mountains Fault Zone.

Response: Conformance with this condition shall be verified during review of residential building permits.

20. Topographic Alteration (Ground Stability & Erosion) Prior to the issuance of grading permits, grading design plans shall incorporate the findings of detailed geologic and geotechnical investigations. These findings all include methods to control soil erosion and ground instability. Some potential methods include:

- a) Uncemented silty soils are prone to erosion. Cut slopes and drainage ways within native material shall be protected from direct exposure to water run off immediately following grading activities. Any cut or fill slopes and their appurtenant drainage facilities shall be designed in accordance with the El Dorado County Grading Ordinance and the Uniform Building Code guidelines. In general, soil slopes shall be no steeper than 2:1 (horizontal to vertical) unless authorized by the Geotechnical Engineer. Slope angles shall be designed to conform to the competence of the

material into which they are excavated. Soil erosion and instability may be accelerated due to shearing associated with the Foothills Fault System, and/or Mormon Island Fault Zone.

- b) Drainage facilities shall be lined as necessary to prevent erosion of the site soils immediately following grading activities.
- c) During construction, trenches greater than 5 feet in depth shall be shored, sloped back at a 1:1 (horizontal to vertical) slope angle or reviewed for stability by the Geotechnical Engineer in accordance with the Occupational Safety and Health Administration regulations if personnel are to enter the excavations.
- d) Surface soils may be subject to erosion when excavated and exposed to weathering. Erosion control measures shall be implemented during and after construction ~to conform With National Pollution Discharge Elimination System, Storm Drain Standards and El Dorado County Standards.
- e) Rainfall shall be collected and channeled into an appropriate collection system designed to receive the runoff, minimize erosion and convey the runoff off-site. Conduits intended to convey drainage water off-site shall be protected with energy dissipating devices as appropriate, and in some areas potentially lined with an impermeable, impact proof material.
- f) Parking facilities, roadway surfaces, and buildings all have impervious surfaces which concentrate runoff and artificially change existing drainage conditions. Collection systems shall be designed where possible to divert natural drainage away from these structures, to collect water concentrated by these surfaces and to convey water away from the Site in accordance with the National Pollution Discharge Elimination System, Storm Drain Standards and El Dorado County Standards.

Response: Condition satisfied. As applicable, the above measures have been incorporated in the design of subdivision improvements and verified in the approved grading and Improvement Plans.

21. Increased Surface Runoff

- a) Prior to the approval of the first tentative subdivision or parcel map, a condition of approval shall be placed on the tentative map that states prior to the issuance of a grading plan, the project applicant shall submit and obtain approval of final drainage plans by the El Dorado County Department of Transportation. These final drainage plans shall demonstrate that future post-development storm water discharge levels from the project will remain at existing storm water discharge levels and detention basins will be permanently maintained. The drainage plan shall be prepared by a certified Civil Engineer and shall be in conformance with the El Dorado County Drainage Manual adopted by the Board of Supervisors in March 1995. The project applicant shall forma drainage zone of benefit (ZOB) or other appropriate entity to

ensure that all storm water drainage facility maintenance requirements are met. The drainage plans shall include, at a minimum, written text addressing existing conditions, the effects of project improvements all appropriate calculations, a watershed map, potential increases in downstream flows, proposed on-site improvements, and drainage easements, if necessary., to accommodate flows from the site and implementation and maintenance responsibilities. The plan shall address storm drainage during construction and proposed BMPs to reduce erosion and water quality degradation. All on-site drainage facilities shall be constructed to El Dorado County Department of Transportation satisfaction. BMPs shall be implemented throughout the construction process. The following BMPs, or others deemed effective, by the Department of Transportation, will be implemented as necessary and appropriate:

- *Soil Stabilization Practices*

- Straw Mulching
- Hydromulching
- Jute Netting
- Revegetation
- Preservation of Existing Vegetation

- *Sediment Barriers*

- Straw Bale Sediment Barriers
- Filter Fences
- Straw Bale Drop Inlet Sediment Barriers

- *Site Construction Practices*

- Winterization
- Traffic Control
- Dust Control

- *Runoff Control in Slopes/Streets*

- Diversion Dikes
- Diversion Swales
- Sediment Traps

- b) Specific measures shall be identified in the final drainage plans to reduce storm water discharge at the Southern Pacific Railroad bridge (Malby Crossing) at the site's southern end. These measures shall include detention basins of adequate size to reduce post-development discharge to pre-development levels. Maintenance of the detention basin and drainage facilities shall include periodic inspections (e.g., annual) to ensure facility integrity and debris removal as necessary.

Response: Condition satisfied. County approved Grading and Improvement Plans include drainage control measures as well as implementation of Storm Water Pollution Program (WDID#5S09C379973) for the subdivision has been conducted.

22. 100-Year Flood Event

Prior to the approval of the final map, the applicant shall submit a final drainage plan that clearly identifies the 100-year flood zone following project development to the El Dorado County Department of Transportation for approval. Project development shall not occur in areas within the 100-year flood zone shown in the final drainage plan. The final drainage plan shall be prepared by a registered civil engineer and contain a hydrologic study that outlines the 100-year flood zones associated with the project and proposed flood control measures such as detention basins. Alternatively, 100-year flood protection improvements, approved by the El Dorado County Department of Transportation, can be implemented to allow development in these areas. All storm drainage facilities and embankments shall be designed in compliance with the County Drainage Manual.

Response: County approval of the Rough Grading Plans and Improvement Plans, which include a final drainage plan, warrants compliance with this condition.

23. Short-Term Construction-Related Water Quality Impacts

- a) Prior to issuance of a grading permit, the developer shall obtain from the SWRCB a General Construction Activity Storm water Permit under the National Pollutant Discharge Elimination System (NPDES) and comply with all requirements of the permit to minimize pollution of storm water discharges during construction activities.
- b) Prior to issuance of a grading permit, the project applicant shall submit to the El Dorado County Department of Transportation and the Resource Conservation District for review and approval an erosion control program which indicates that proper control of siltation, sedimentation and other pollutants will be implemented per NPDES permit requirements. The erosion control plan shall include BMPs as discussed in mitigation measure 4.10-1, and as follows: sediment basins sediment traps, silt fences, hay bale dikes, gravel construction entrances .maintenance programs, and hydroseeding.

Response: Condition satisfied. County approved Grading and Improvement Plans include drainage control measures as well as implementation of Storm Water Pollution Program (WDID#5S09C379973) for the subdivision have been conducted.

24. Long-Term Water Quality Impacts

- a) On-site detention basins shall be constructed and maintained through the construction period to receive storm water runoff from graded areas to allow capture and settling of sediment prior to discharge to receiving waters. Periodic maintenance

of detention basins, Such as debris removal, shall occur on a monthly basis or more frequently as needed to ensure continued effectiveness.

- b) Prior to issuance of a grading permit, the project applicant shall develop a surface water pollution control plan (i.e., parking lot sweeping program and periodic storm drain cleaning) to reduce long-term surface Water quality impacts. Parking lot sweeping shall occur on a weekly basis and storm drain clearing shall occur semi-annually. The plan shall also include the installation of oil. gas and grease trap separators in the project parking lot. These grease trap separators will be cleaned annually. The project applicant shall develop a financial mechanism, to be approved by the El Dorado County Department of Transportation that ensures the long-term implementation of the program.

Response: Condition satisfied. County approved Grading and Improvement Plans include drainage control measures as well as implementation of Storm Water Pollution Program (WDID#5S09C379973) for the subdivision have been conducted.

25. Archaeological Sites CC-1, CC-2, CC-3, CC-4, CC-5, CC-6 and Archaeological Linear Features CC-LF-1, CC-LF-2, and CC-LF-3

- a) Prior to grading and construction activities, significant cultural resources found on the project site shall be recorded or described in a professional report and. submitted to the North Central Information Canter at California State University at Sacramento.
- b) During grading and construction activities, the name and telephone number of an El Dorado County-approved, licensed archaeologist shall be available at the project site. In the event a heritage resource is encountered during grading or construction activities, the project applicant shall ensure that all activities will cease in the vicinity of the recovered heritage resource until an archaeologist can examine the find in place and determine its significance. If a find is authenticated, the archaeologist shall determine proper methods of handling the resource(s) for transport and placement in an appropriate repository. Grading and construction activities may resume, after the resource is either, retrieved or found to be not of consequence.

Response: Condition satisfied. County approved Grading and Improvement Plans include measures for monitoring to sensitive cultural resources. No resources were identified.

26. School Fees

- a) The project applicant shall pay the commercial school fee of \$0.31 per square foot for the age-restricted residential development.

- b) The project applicant shall reimburse the Latrobe School District for out-of-pocket expenses incurred in planning for school sites within the Carson Creek Specific Plan area before it was age restricted.
- c) The project applicant also shall meet with the Latrobe School District and the El Dorado Union High School. District to renegotiate school fees in the unlikely event that the age restrictions for the Carson Creek Specific Plan area are lifted.

Response: This condition is not applicable to the specific plan.

27. Law Enforcement

The project applicant shall ensure adequate law enforcement personnel and equipment to serve the Specific Plan area, as demonstrated by one of the following mechanisms:

- a) Prior to the issuance of each building permit, the project applicant will be required to obtain a service letter from the El Dorado County Sheriff's Department identifying that law enforcement staff and equipment are available to serve the proposed land use upon occupancy,
- b) Prior to the issuance of the building permit, the project applicant shall create an assessment district or other mechanism to provide funding to the El Dorado County Sheriff's Department for adequate law enforcement staff and equipment upon occupancy and in the future.

Response: Conformance with this condition shall be verified during review of residential building permits.

28. Water Consumption

Project impacts cannot be reduced to a less than significant level until the EID procures new water supplies that are sufficient to meet water needs of the proposed Specific Plan at build out in conjunction with existing planned growth, or an alternative public water source is secured. Implementation of the following mitigation, measures would reduce potential project impacts on water supply. The project applicant would be required to implement these measures before approval of building permits.

- a) In accordance with EID Policy Statement No. 22, the project applicant shall prepare a Facility Plan Report (FPR) for the proposed project, The FPR Shall address the expansion of the water and sewer facilities and the specific fire flow requirements for the phases of the project.

Response: Condition satisfied. EID approval of FPR warrants compliance with this condition.

- b) Low-volume and low-flow fixtures shall be installed to reduce water consumption.

Response: Compliance with this condition shall be verified during building permit review.

- c) Efficient irrigation systems shall be installed to minimize runoff and evaporation and maximize the water that will reach plant roots. One or any combination of the following methods of increasing irrigation efficiency shall be employed: drip irrigation, soil moisture sensors, and automatic irrigation systems. Mulch shall be used extensively in all landscaped areas. Drought resistant and native vegetation shall be used in landscaped areas.

Response: Condition satisfied. County and EID approval of Improvement Plans which includes Landscaping and Irrigation Plans, warrants compliance with this condition.

29. Historic Mining

Prior to the issuance of a grading permit, shallow groundwater and on-site drainage area shall be sampled to determine the potential presence of on-site contamination (mercury, etc.). If contamination is found, the appropriate regulatory agency shall be contacted. If deemed necessary by the appropriate regulatory agency, remediation shall be undertaken in accordance with all existing local, state, and federal regulations/requirements and guidelines established for the treatment of hazardous substances.

Response: Condition satisfied. Transportation Division and Youngdahl Consulting Group's approval of the rough grading and improvement plans demonstrates compliance with this condition.

30. Underground Storage Tank (UST)

Prior to the issuance of a grading permit, the extent (soil and/or groundwater) of potential on-site contamination resulting from the operation of off-site USTs shall be assessed. Once the extent of contamination has been determined, the appropriate regulatory agency shall be consulted in identifying the responsible party and initiating the development of a remediation program in accordance with all applicable local, state, and federal regulations/requirements and guidelines established for the treatment of hazardous substances.

Response: Condition satisfied. Transportation Division and Youngdahl Consulting Group's approval of the rough grading and improvement plans demonstrates compliance with this condition.

- 31. The applicant will pay light rail fees in the following circumstances: (1) a region-wide or county-wide, light-rail fee requirement is imposed; (2) before grading permits are issued; and (3) fees shall only apply to units in which no building permit has been issued at the time the light rail fee is imposed. The applicant will receive credit against any fees for any light rail related improvements or land donated to serve light rail.

Response: This condition is not applicable as there is no light rail fee established.

32. Open channel drainage: The applicant shall minimize the use of culverts and concrete V-ditches and maximize the use of open: unlined and vegetated channels to facilitate removal of pollutants and sediment and to preserve a more natural rural feel to the development. The applicant shall employ best management practices to protect water quality and to minimize erosion in the drainage system. Such practices shall include utilizing grassy swales, open ditches, energy dissipaters, water quality ponds, and grease/oil traps.
- a) Open Space Areas: All drainage in open space corridors shall remain natural, unlined and open. Except as expressly indicated elsewhere in the specific plan, the applicant will not use culverts in these channels and road crossings shall be bridged.
 - b) Within areas designated for residential and industrial use, vegetated open-channel drainage shall be the primary means of accommodating stormwater runoff and existing surface water bodies, in residential areas, where the homes front the streets, site design shall emphasize drainage to open, vegetated channels away from streets and towards the back and side lots. In instances where such drainage is not engineering practicable, drainage towards streets shall utilize gutters, A.C. dikes, rolled curbs, and/or vertical curbs will be utilized. These drainage facilities shall be kept to a minimum and will convey drainage to open channel ditches (1) along collectors and other streets where homes do not front the streets and (2) between lots. Piped drainage facilities shall be kept to a minimum. Open channel ditches shall convey the drainage to natural drainage channels in the open space areas but not before ensuring that water quality standards are maintained through the implementation of best management practices.

Response: Condition satisfied. Transportation Division approval of the rough grading and improvement plans demonstrates compliance with this condition.

33. Roadways in the Carson Creek Specific Plan Area shall be curvilinear and separated from pedestrian pathways that run around, over, under, and between structures. Where feasible, cul-de-sacs will be incorporated into circulation system designs. The majority of roads (asphalt portion only) shall be 26 feet or less in width.

Furthermore, the Carson Creek Specific Plan Phase 2 street development standards (asphalt portion only), shall be modified to incorporate the following maximum widths:

- a) One-way streets shall be no more than 18 feet wide;
- b) Two-way streets shall be no more than 24 feet wide;
- c) Minor collectors with less than 350 average daily trips ("ADT") shall be no more than 24 feet wide;

- d) Minor collectors with more than 350 average daily trips ("ADT") shall be no more than 26 feet wide;
- e) Major collectors with homes fronting the street, shall be no more than 30 feet wide;
- f) Major collectors, without homes fronting the street and with less than 350 ADT, shall be no more than 24 feet wide;
- g) Major collectors, without homes fronting the street and with more than 350 ADT, shall be no more than 26 feet wide. The majority of roads (asphalt portion only) shall be 26 feet or less in width.

Parking bays may be required for emergency parking along collectors and in residential areas where these standards prohibit parking along the streets. The parking bays shall be kept to a minimum and located where topography permits. Street standards are subject to the review of the El Dorado Hills Fire Departments; for public safety reasons, the fire department may require wider roads in some places or turn-arounds, hammerheads, or other measures to facilitate the movement of emergency vehicles.

For the Carson Creek Specific Plan, Phase 1, these road standards will be adopted only if the County finds that the final maps, containing these standards, are consistent with the tentative maps, as required by law.

Response: Condition satisfied. Transportation Division approval of the rough grading and improvement plans demonstrates compliance with this condition.

Planning Services

- 34. In the event of any legal action instituted by a third party challenging the validity of any provision of this approval, the developer and landowner agree to be responsible for the costs of defending such suit and shall hold County harmless from any legal fees or costs County may incur as a result of such action, as provided in Section 66474.9(b) of the California Government Code.

The applicant shall defend, indemnify, and hold harmless El Dorado County and its agents, officers, and employees from any claim, action, or proceeding against El Dorado County or its agents, officers, or employees to attack, set aside, void, or annul an approval of El Dorado County concerning a subdivision, which action is brought within the time period provided for in Section 66499.37.

Response: No legal challenges to the approval of the tentative subdivision map.

- 35. Prior to submittal of first final map, the applicant shall remit payment of any outstanding fees as detailed and required in the *Agreement for Payment of Processing Fees* authorized for this project.

Response: Condition satisfied. All application fees have been paid.

36. Prior to recordation of the residential Final Map, the applicant shall provide written statement justifying the project's consistency with the mitigation measures in the adopted Mitigation Monitoring Reporting Program for Carson Creek Specific Plan. The documentation shall be provided to and reviewed by the Development Services-Planning Division.

Response: Condition satisfied. Submitted narrative containing justification for compliance with the mitigation measures in the MMRP has been reviewed and verified.

37. Prior to recordation of the residential Final Map, the applicant shall submit an executed EID meter award letter.

Response: Condition satisfied. The applicant has provided an EID meter letter detailing the required amount of meters to provide water and sewer service.

DEPARTMENT OF TRANSPORTATION

PROJECT SPECIFIC CONDITIONS

38. Specific Plan and Mitigation Measures: The applicant shall be subject to all applicable conditions as specified for the Carson Creek Specific Plan as well as any required Mitigation Measures described in the Mitigation Monitoring Checklist for the Carson Creek Specific Plan.

Response: Condition satisfied. Submitted narrative containing justification for compliance with the mitigation measures in the MMRP has been reviewed and verified.

39. Carson Crossing Drive: The applicant shall construct Carson Crossing Drive with an 80-foot right of way from the northwest corner of Lot A as shown on the Tentative Map, to the intersection with Golden Foothill Parkway. The applicant shall provide the appropriate lane spacing and site distance along Carson Crossing Drive for any future signal at the Carson Crossing Drive and A drive intersection.

The applicant shall place conduits across Carson Creek Drive and A Drive to be utilized for a future signal at the Carson Crossing Drive and A drive intersection.

The applicant shall construct an opening in the median at the B Drive intersection. The applicant shall install a mountable curb system across the opening to deter regular vehicular use of the opening, but will still allow emergency vehicles to cross the median and enter the emergency gate at B Drive.

The above improvements shall be substantially completed to the approval of the Department of Transportation or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Response: Condition satisfied. Design and construction of Carson Crossing Drive has been approved with Carson Creek Unit 1 subdivision.

40. Investment Blvd: The applicant shall construct a full width extension of Investment Blvd to the west to the intersection with ZZ Drive. The extension shall have a 67 foot right of way with slope and utility easements as needed to extend to the southwestern curb return of ZZ Drive. The improvements shall include curb, gutter and 6 foot sidewalk on both sides of Investment Blvd. All wet and dry utilities shall be extended to the western end of the Investment Blvd extension. The applicant shall also provide a temporary turnaround at the western end of the extension. The turnaround shall be constructed to the provisions of County Standard Plan 114 or approved equivalent by the local fire district. The improvements shall be substantially completed to the approval of the Department of Transportation or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Response: Condition satisfied. County approved Improvement Plans confirms design of road as conditioned.

41. Encroachment: The applicant shall obtain an encroachment permit from DOT and shall construct Carson Crossing Drive encroachment onto Golden Foothill Parkway per DISM Standard Plan 103E without the 100-foot tapers. The improvements shall be substantially completed to the approval of the Department of Transportation or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Response: Condition satisfied. Design and construction of Carson Crossing Drive encroachment onto Golden Foothills Parkway has been approved with Carson Creek Unit 1 subdivision.

42. Encroachment: The applicant shall construct the encroachments of A Drive and B Drive onto Carson Crossing Drive per DISM Standard Plan 103E and 103D respectively without the 100-foot tapers. B drive shall be gated with emergency access and right out only egress. The improvements shall be substantially completed to the approval of the Department of Transportation or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Response: Condition satisfied. County approved Improvement Plans confirms design of road and encroachment improvements as conditioned.

43. Encroachment: The applicant shall construct the encroachment of ZZ Drive onto Investment Blvd per DISM Standard Plan 103D without the 100-foot tapers. The improvements shall be substantially completed to the approval of the Department of Transportation or the applicant

shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Response: Condition satisfied. County approved Improvement Plans confirms design of road and encroachment improvements as conditioned.

44. Turn Pocket: The applicant shall provide a left turn pocket on west bound Carson Crossing Drive onto A Drive. The improvements shall be substantially completed to the approval of the Department of Transportation or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Response: Condition satisfied. Design and construction of Carson Crossing Drive has been approved with Carson Creek Unit 1 subdivision.

45. Turn Pocket: The applicant shall provide a striped left turn pocket on west bound Golden Foothill Parkway onto Carson Crossing Drive. The improvements shall be substantially completed to the approval of the Department of Transportation or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Response: Condition satisfied. Design and construction of Carson Crossing Drive has been approved with Carson Creek Unit 1 subdivision.

46. Road Design Standards: All roads shall be constructed in conformance with the Carson Creek Specific Plan and the Design and Improvements Standard Manual Standard Plan 101B and as noted in table 1 below. The improvements shall be substantially completed to the approval of the Department of Transportation or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Table 1. Carson Creek Unit 2 Revised Tentative Map Roadways

ROAD NAME	DESIGN STANDARD PLAN	ROAD WIDTH* / SHOULDER WIDTH	RIGHT OF WAY**	DESIGN SPEED	EXCEPTIONS/ NOTES
A Drive (From C Drive to D Drive	Per typical section detail shown on the plans I-I	26 feet travel way (2 – 13 feet lanes) swale drainage.	64 foot	25 MPH	Type 2 vertical curb & gutter on both sides, four foot sidewalk on both sides, open swales drainage on both sides between back of curb and sidewalk.
Carson Crossing Drive	Per typical section shown on the plans E-E	36 feet travel way (2-12 feet lanes w/6 feet bike lane, 18 feet total), landscape median (width varies)	80 foot plus utility/ slope easement	35 MPH	Two foot benches on outer side of travel way next to roadside drainage ditch on both sides, six foot sidewalk outside of ROW on south and east side. (Lots A, L, O and Y).
Investment Blvd extension	Per typical section shown on the plans H-H	48 feet travel way.	67 foot plus utility slope easement	40 MPH	Type 2 vertical curb and gutter with six foot sidewalk and one foot bench behind sidewalk on both sides.
ZZ Drive	Per typical section shown on the plans G-G.	26 feet (2-13' lanes) travel way	40 foot travel way	25 MPH	Type 2 vertical curb and gutter and four foot sidewalk w/0.5' (1/2 foot) bench behind sidewalk on both sides. Except where homes front the street, then type 1 rolled curb and gutter.

E Drive, F Drive, G Drive, J Drive, K Drive, L Drive, M Drive, N Drive, O Drive, Q Drive, S Drive, T Drive, V Drive, X Drive, Y Drive, Z Drive, BB Drive, V Court	Per typical section shown on the plans A-A	24- foot travel way	40 foot travel way	25 MPH	Type 1 rolled curb & gutter on both sides. Four foot sidewalk on one side.
E Court	Per typical section shown on the plans B-B	24- foot travel way	40 foot travel way	25 MPH	Type 1 rolled curb & gutter on both sides, no sidewalk.
B Drive, C Drive, D Drive	Per typical section shown on the plans C-C	26 foot travel way	64 foot travel way	25 MPH	Curb adjacent to the fronts of lots shall be type 1 rolled curb & gutter. All curb adjacent to the sides of lots shall be Type 2 vertical curb & gutter on both sides, six foot separated sidewalk on one side.
A Drive (From Carson Crossing Drive to C Drive)	Per typical section shown on the plans D-D	36 foot travel way (2-18 foot lanes), landscape median (width varies 6 feet to 26 feet)	80 foot to 150 foot	25 MPH	Type 2 vertical curb & gutter on both sides, six foot sidewalk on both sides, open swale drainage on both sides between back of curb and sidewalk.

* Road widths are measured from curb face to curb face or edge of pavement to edge of pavement if no curb (traveled way). Curb face for rolled curb and gutter is 6" from the back of the curb.

** Non-exclusive road and public utility easements included

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads as conditioned.

47. Easements: The applicant shall irrevocably offer to dedicate a non-exclusive road and public utility easement (R&PUE) for onsite roadways as listed in the Table 1 and 50 feet wide radius R&PUE for any cul-de-sac on the final map. Slope easements shall be included as necessary. This offer will be accepted by the County.

Response: Condition satisfied. Easements are shown on the Final Map; thus warranting compliance with this condition.

48. Irrevocable Offer of Dedication: The applicant shall irrevocably offer to dedicate the right of way for all roads as described in Table 1, with the exception of Carson Creek Drive and Investment Boulevard with the filing of the final map. This offer will be acknowledged and rejected by the County.

Response: Condition satisfied. IOD is shown on the Final Map; thus warranting compliance with this condition.

49. Irrevocable Offer of Dedication: The applicant shall irrevocably offer to dedicate, in fee, the right-of-way for Carson Crossing Drive and Investment Boulevard as described in Table 1 with the filing of the final map. This offer will be accepted by the County.

Response: Condition satisfied. IOD is shown on the Final Map; thus warranting compliance with this condition.

50. Public Service Easement: The applicant shall provide an additional Public Service Easement (PSE) where the sidewalks are outside of the proposed right-of-way with the filing of the final map.

Response: Condition satisfied. Easements are shown on the Final Map; thus warranting compliance with this condition.

51. Gates, Location: Pursuant to Article 2, Section 1273.11 of the SRA Fire Safe Regulations, all gates providing access from a road to a driveway shall be located at least 30 feet from the roadway and shall open to allow a vehicle to stop without obstructing traffic on that road. Additionally, gate entrances shall be at least two feet wider than the width of the traffic lane(s) serving that gate.

Response: Condition satisfied. County and El Dorado Hills Fire Department approved Improvement Plans confirms design of subdivision gates as conditioned.

52. Gates, Turnarounds: All gates shall be designed and constructed with turnarounds acceptable to the Department of Transportation and the Fire Department. The improvements shall be completed to the satisfaction of the Department of Transportation and Building Services or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Response: Condition satisfied. County and El Dorado Hills Fire Department approved Improvement Plans confirms design of subdivision gates as conditioned.

53. Turnaround: The applicant shall provide a turnaround at the end of the dead end roadways to the provisions of County Standard Plan 114 or approved equivalent by local fire district. The improvements shall be completed to the satisfaction of the Department of Transportation or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the final map.

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads as conditioned.

54. Vehicular Access Restriction: The applicant shall record a vehicular access restriction along the entire frontage of the lots adjacent to the following roads:
- Carson Crossing Drive except Lot M & Lot N
 - A Drive from Carson Crossing Drive to C Drive, except Lot A
 - B Drive

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads, which includes access restrictions, as conditioned. The Final Map also reflects these restrictions.

55. Easements: All applicable existing and proposed easements shall be shown on the project plans.

Response: Condition satisfied. County approved Improvement Plans includes all applicable easements, as conditioned. The Final Map also reflects these restrictions.

56. Signage: The applicant shall install all necessary signage such as stop signs, street name signs, and/or "not a county maintained road" sign as required by the Department of Transportation prior to the filing of the map. The signing and striping shall be designed and constructed per the latest version of the California Manual Uniform Traffic Control Devices (MUTCD).

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads as conditioned.

57. Sidewalks: Sidewalks may be located outside the right-of-way and meander as a means to provide interest and variety in alignment. The alignment and design of the sidewalks shall be reviewed and approved by the Department of Transportation prior to issuance of building permits. Pedestrian easements shall be provided where necessary. Final lane configurations, including the need for additional rights-of-way, shall be subject to review and approval of the Department of Transportation prior to improvement plan approval.

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads and sidewalks as conditioned.

58. Curb Returns: All curb returns, at pedestrian crossing, will need to include a pedestrian ramp with truncated domes per Caltrans Standard A88A and 4 feet of sidewalk/landing at the back of the ramp.

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads as conditioned.

59. Maintenance Entity: The proposed project must form an entity for the maintenance of any shared or common: private roads, parking facilities, landscaping, signs and drainage facilities. If there is an existing entity, the property owner shall modify the document if the current document does not sufficiently address maintenance of the roads, parking facilities, landscaping, signs, and drainage facilities of the current project. DOT shall review the document forming the entity to ensure the provisions are adequate prior to filing of the map.

Response: Condition satisfied. The Carson Creek Master Association (HOA) will maintain any shared or common areas. See Section 1.1.14 entitled Master Association Maintenance Areas in the CC&Rs.

60. Common Fence/Wall Maintenance: The responsibility for, and access rights for maintenance of any fences and walls constructed on property lines shall be included in the Covenants Codes and Restrictions (CC&Rs).

Response: Condition satisfied. The Carson Creek Master Association (HOA) will maintain any shared or common areas and fences. See Section 1.1.14 entitled Master Association Maintenance Areas in the CC&Rs.

61. Water Quality Stamp: All new or reconstructed drainage inlets shall have a storm water quality message stamped into the concrete, conforming to the Storm Water Quality Design Manual for the Sacramento and South Placer Regions, Chapter 4, Fact Sheet SD-1. All stamps shall be approved by the El Dorado County inspector prior to being used.

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads as conditioned.

62. Construction Hours: Construction activities shall be conducted in accordance with the County Health, Safety, and Noise Element and limited to the daylight hours between 7:00 a.m. and 7:00 p.m. on any weekday, and 8:00 a.m. and 5:00 p.m. on weekends and federal holidays.

Response: County approved Improvement Plans includes the required construction hours as conditioned.

63. DISM Consistency: The developer shall obtain approval of project improvement plans and cost estimates consistent with the Subdivision Design and Improvement Standards Manual from the County Department of Transportation, and pay all applicable fees prior to filing of the map.

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads as conditioned.

64. Road Improvement Agreement & Security: The developer shall enter into a Road Improvement Agreement (RIA) with the Department of Transportation for all roadway, frontage, and intersection improvements. The developer shall complete the improvements to the satisfaction of DOT or provide security to guarantee performance of the RIA as set forth within the County of El Dorado Subdivision Division Ordinance, prior to filing of the map.

Response: No RIA is warranted for this subdivision.

65. Subdivision Improvement Agreement & Security: The developer shall enter into a Subdivision Improvement Agreement (SIA) with the Department of Transportation for all onsite roadway, drainage infrastructure, grading, etc. The developer shall complete the improvements to the satisfaction of DOT or provide security to guarantee performance of the SIA as set forth within the County of El Dorado Subdivision Division Ordinance, prior to filing of the map.

Response: Condition satisfied. County Transportation Department has approved the Subdivision Improvement Agreement for the subdivision.

66. Import/Export Grading Permit: Any import, or export to be deposited or borrowed within El Dorado County, shall require an additional grading permit for that offsite grading.

Response: Condition satisfied. County approved Improvement Plans included import and export of dirt for the subdivision, as conditioned.

67. Grading Permit / Plan: The applicant shall submit a site improvement/grading plan prepared by a professional civil engineer to the DOT for review and approval. The plan shall be in conformance with the County of El Dorado "Design and Improvement Standards Manual", the "Grading, Erosion and Sediment Control Ordinance", the "Drainage Manual", the "Off-Street Parking and Loading Ordinance", and the State of California Handicapped Accessibility Standards. All applicable plan check and inspection fees shall be paid at the time of submittal of improvement plans. The improvements and grading shall be completed to the satisfaction of DOT or the applicant shall obtain an approved improvement agreement with security, prior to the filing of the map.

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads as conditioned.

68. Grading Plan Review: Grading and improvement plans shall be prepared and submitted to the El Dorado County Resource Conservation District (RCD) and the Department of Transportation. The RCD shall review and make appropriate recommendations to the County. Upon receipt of the review report by the RCD, the Department of Transportation shall consider imposition of appropriate conditions for reducing or mitigating erosion and

sedimentation from the project. Grading plans shall incorporate appropriate erosion control measures as provided in the El Dorado County Grading Ordinance and El Dorado County Storm Water Management Plan. Appropriate runoff controls such as berms, storm gates, detention basins, overflow collection areas, filtration systems, and sediment traps shall be implemented to control siltation, and the potential discharge of pollutants into drainages.

Response: Condition satisfied. County approved Improvement Plans confirms design of subdivision roads as conditioned.

69. RCD Coordination: The timing of construction and method of revegetation shall be coordinated with the El Dorado County Resource Conservation District (RCD). If grading activities are not completed by September, the developer shall implement a temporary grading and erosion control plan. Such temporary plans shall be submitted to the RCD for review and recommendation to the Department of Transportation. The Department of Transportation shall approve or conditionally approve such plans and cause the developer to implement said plan on or before October 15.

Response: Condition satisfied. Approved Improvement Plans confirms design of subdivision improvement includes grading and erosion control plan, as conditioned.

70. At the time of the submittal of the grading or improvement plans, the applicant shall submit a soils and geologic hazards report (meeting the requirements for such reports provided in the El Dorado County Grading Ordinance) to, and receive approval from the El Dorado County Department of Transportation. Grading design plans shall incorporate the findings of detailed geologic and geotechnical investigations and address, at a minimum, grading practices, compaction, slope stability of existing and proposed cuts and fills, erosion potential, ground water, pavement section based on TI and R values, and recommended design criteria for any retaining walls.

Response: Condition satisfied. County approved Improvement Plans included approval of soils and geologic hazards report, as conditioned.

71. Drainage Study / SWMP Compliance: The applicant shall provide a drainage report at time of improvement plans or grading permit application, consistent with the Drainage Manual and the Storm Water Management Plan, which addresses storm water runoff increase, impacts to downstream facilities and properties, and identification of appropriate storm water quality management practices to the satisfaction of the Department of Transportation. The Drainage Study must demonstrate the subject property has adequate existing and proposed storm drainage facilities. At a minimum, the drainage study, plans, and calculations shall include the following:

- The site can be adequately drained;
- The development of the site will not cause problems to nearby properties, particularly downstream sites;
- The on-site drainage will be controlled in such a manner as to not increase the downstream peak flow more than the pre-development 10-year storm event or

cause a hazard or public nuisance. Detention shall be required if said condition is not met or demonstrate that there are no downstream impacts.

- The ultimate drainage outfall of the project.

Pursuant to Section 1.8.3 of the Drainage Manual, the report shall be prepared by a Civil Engineer who is registered in the State of California. A Scoping Meeting for the required drainage study between County staff and the engineer shall occur prior to the first submittal of improvement plans. The engineer shall bring a watershed map and any other existing drainage system information to the Scoping Meeting. The improvements shall be completed to the approval of the Department of Transportation, prior to the filing of the final map or the applicant shall obtain an approved improvement agreement with security.

Response: Condition satisfied. County approved Improvement Plans included review and approval of a drainage report for the subdivision, as conditioned. An SIA has been secured for the subdivision.

72. Drainage (Cross-Lot): Cross lot drainage shall be avoided. When concentrated cross lot drainage does occur or when the natural sheet flow drainage is increased by the project, it shall be contained within dedicated drainage easements, and included in the County Service Area Zone of Benefit (ZOB), Home Owners Association, or other entity acceptable to the County. Any variations shall be approved by the County Engineer. This drainage shall be conveyed via closed conduit or v-ditch, to either a natural drainage course of adequate size or an appropriately sized storm drain system within the public roadway. The site plans shall show drainage easements for all on-site drainage facilities. Drainage easements shall be provided where deemed necessary prior to the filing of the final map.

Response: Condition satisfied. Approved Improvement Plans confirms design of subdivision improvement includes drainage network, as conditioned.

73. Drainage Easements: Pursuant to Section 4.D of the DISM, the site plans shall show drainage easements for all on-site drainage courses and facilities and shall be included on all improvement plans and /or on the final map.

Response: Condition satisfied. Approved Improvement Plans confirms design of subdivision improvement includes drainage network, as conditioned.

74. At the time that an application is submitted for improvement plans or a grading permit, and if the proposed project disturbs more than one acre of land area (43,560 square feet), the applicant shall file a "Notice of Intent" (NOI) to comply with the Statewide General NPDES Permit for storm water discharges associated with construction activity with the State Water Resources Control Board (SWRCB). This condition is mandated by the Federal Clean Water Act and the California Water Code. A filing form, a filing fee, a location map, and a Storm Water Pollution Prevention Plan (SWPPP) are required for this filing. A copy of the Application shall be submitted to the County, prior to building permit issuance, and by state law must be done prior to commencing construction.

Response: Condition satisfied. County approved Grading and Improvement Plans include drainage control measures as well as implementation of Storm Water Pollution Program (WDID#5S09C379973) for the subdivision has been conducted.

75. Storm Water Drainage BMPs: Storm drainage from on-and off-site impervious surfaces (including roads) shall be collected and routed through specially designed water quality treatment facilities (BMPs) for removal of pollutants of concern (e.g. sediment, oil/grease, etc.), as approved by DOT. This project is located within the area covered by El Dorado County's municipal storm water quality permit, pursuant to the National Pollutant Discharge Eliminated System (NPDES) Phase II program. Project related storm water discharges are subject to all applicable requirements of said permit. BMPs shall be designed to mitigate (minimize, infiltrate, filter, or treat) storm water runoff in accordance with "Attachment 4" of El Dorado County's NPDES Municipal Storm water Permit (State Water Resources Control Board NPDES General Permit No. CAS000004). With the Improvement Plans, the applicant shall verify that the proposed BMPs are appropriate to treat the pollutants of concern from this project. A maintenance entity of these facilities shall be provided by the project applicant. DOT shall review the document forming the entity to ensure the provisions are adequate prior to filing of the final map.

Response: Condition satisfied. County approved Grading and Improvement Plans include drainage control measures as well as implementation of Storm Water Pollution Program (WDID#5S09C379973) for the subdivision has been conducted.

76. Off-site Improvements (Security): Prior to the filing of a final map, the applicant shall enter into an agreement pursuant to Government Code Section 66462.5 to complete the required offsite improvements, including the full costs of acquiring any real property interests necessary to complete the required improvements. In addition to the agreement, the applicant shall provide a cash deposit, letter of credit, or other acceptable surety in the amount sufficient to pay such costs, including legal costs, subject to the approval of County Counsel.

Response: No off-site improvements required for this subdivision.

77. Off-site Improvements (Acquisition): As specified in the Conditions of Approval, the applicant is required to perform off-site improvements. If it is determined that the applicant does not have or cannot secure sufficient title or interest of such lands where said off-site improvements are required, the County may, at the applicant's expense and within 120 days of filing the Final Map, acquire by negotiation or commence proceedings to acquire an interest in the land which will permit the improvements to be made, including proceedings for immediate possession of the property. In such cases, prior to filing of any final map, the applicant shall submit the following to the Department of Transportation Right of Way Unit, and enter into an agreement pursuant to Government Code Section 66462.5 and provide acceptable security to complete the offsite improvements, including costs of acquiring real property interest to complete the required improvements, construction surveying, construction management, and a 20% contingency:

- a. A legal description and plat, of the land necessary to be acquired to complete the offsite improvements, prepared by a civil engineer or land surveyor.
- b. Approved improvement plans and specifications of the required off-site improvements, prepared by a civil engineer.
- c. An appraisal prepared by a certified appraiser of the cost of land necessary to complete the off-site improvements. In addition to the agreement the applicant shall provide a cash deposit, letter of credit, or other acceptable surety in an amount sufficient to pay such costs including legal costs subject to the approval of County Counsel.

Response: No off-site improvements required for this subdivision.

78. Electronic Documentation: Upon completion of the improvements required, and prior to acceptance of the improvements by the County, the developer will provide a CD to DOT with the drainage report, structural wall calculations, and geotechnical reports in PDF format and the record drawings in TIF format.

Response: Condition satisfied. Electronic documentation of Improvement Plan has been received by County Transportation Department.

79. TIM Fees: The applicant shall pay the traffic impact mitigation fees in effect at the time a building permit is deemed complete.

Response: TIM fees shall be paid prior to issuance of residential building permit.

EL DORADO HILLS FIRE DEPARTMENT

80. This development shall annex to the El Dorado Hills County Water District and pay all fees associated with that annexation. Conformance with this condition shall be verified prior to recordation of first residential final map.

Response: Condition satisfied. The subdivision has been annexed into the district.

81. All homes shall be fire sprinklered in accordance with NFPA 13D and Fire Department requirements.

Response: This condition shall be verified during review of residential building permits.

82. The potable water system with the purpose of fire protection for this residential development shall provide a minimum fire flow of 1,000 gallons per minute with a minimum residual pressure of 20 psi for a two-hour duration. This requirement is based on a single family dwelling 6,200 square feet or less in size. All homes shall be fire sprinklered in accordance with NFPA 13D and Fire Department requirements. This fire flow rate shall be in excess of the maximum daily consumption rate for this development. A set of engineering calculations reflecting the fire flow capabilities of this system shall

be supplied to the Fire Department for review and approval. Conformance with this condition shall be verified prior to prior to recordation of the final map.

Response: This condition shall be verified during review of residential building permits.

83. Mueller Dry Barrel fire hydrants shall be installed conforming to El Dorado Irrigation District specifications. The spacing between hydrants in this development shall not exceed 500 feet. The exact location of each hydrant shall be determined by the Fire Department. Hydrant locations shall be shown the Improvement Plan.

Response: This condition shall be verified during review of residential building permits.

84. In order to enhance nighttime visibility, each hydrant shall be painted with safety white enamel and marked in the roadway with a blue reflective marker as specified by the Fire Department and State Fire Safe Regulations. This condition shall be incorporated and verified as a note on the Improvement Plans.

Response: Condition satisfied. El Dorado Hills Fire Department approved Improvement Plans confirms subdivision safety improvements, as conditioned.

85. In order to provide this development with adequate fire and emergency medical response during construction, all access roadways and fire hydrant systems shall be installed and in service prior to combustibles being brought onto the site as specified by the Fire Department, Standard B-003. This condition shall be incorporated as a note and verified prior to approval of Improvement Plan.

Response: Condition satisfied. El Dorado Hills Fire Department approved Improvement Plans confirms subdivision safety improvements, as conditioned.

86. A Wildland Fire Safe Plan shall be prepared in accordance with the State Fire Safe Regulations. The plan shall include provisions for implementation and maintenance. A copy of the final Wildland Fire Safe Plan approved by the department shall be provided prior to recordation of the first residential final map.

Response: Condition satisfied. A Wild Fire Safe Plan was approve in August 2014.

87. This development shall be prohibited from installing any type of traffic calming device that utilizes a raised bump/dip section of roadway. This condition shall be incorporated as a note on the Improvement Plan and verified prior to approval of Improvement Plan.

Response: Condition satisfied. El Dorado Hills Fire Department approved Improvement Plans confirms subdivision safety improvements, as conditioned.

88. Any gate shall meet the El Dorado Hills Fire Department Gate Standard B-002. Gate details shall be noted on the Improvement Plan.

Response: Condition satisfied. El Dorado Hills Fire Department approved Improvement Plans include subdivision gates, as conditioned.

89. There shall be no less than 4 access points for emergency equipment to make access on to the walking path surrounding the proposed subdivision. These access points are indicated on the tentative map as OSA. Gates or removable bollards shall be installed and locked with a low priority KNOX lock. The design and locations shall be approved by the El Dorado Hills Fire Department prior to installation. Access shall be wide enough for emergency equipment to access the trail (minimum of 12 feet). Access details shall be noted on the Improvement Plan.

Response: Condition satisfied. El Dorado Hills Fire Department approved Improvement Plans confirms subdivision safety improvements, as conditioned.

90. All parking restrictions as stated in the El Dorado Hills County Water District Ordinance 36 shall be in effect. On streets where parking is restricted, the roadway shall be signed or marked as described on the El Dorado Hills Fire Department No Parking Fire Lane Standard B-004 available at www.edhfire.com
- a. For Typical Section A-A, the parking restrictions are:
 - i. Parking allowed on the side of the street opposite the sidewalk only.
 - b. For Typical Section B-B, the parking restrictions are:
 - i. Parking on one side of the street only (no sidewalk on this street).
 - c. For Typical Section C-C, the parking restrictions are:
 - i. Parking on one side of the street only (no sidewalks on these streets).
 - d. For Typical Section D-D, Residential Collector Entry, the parking restrictions are:
 - i. No parking
 - e. For Typical Section G-G, the parking restrictions are:
 - i. Parking on one side of the street only (sidewalks on both sides, so pick a side to allow parking).
 - f. For Typical Section H-H, the parking restrictions are:
 - i. Parking allowed on both sides of the street.
 - g. For Typical Section I-I, the parking restrictions are:
 - i. Parking on one side of the street only (no sidewalks on these streets).

The above restrictions shall be shown as notes on the Improvement Plan.

Response: Condition satisfied. El Dorado Hills Fire Department approved Improvement Plans confirms subdivision safety improvements, as conditioned.

91. A secondary means of egress shall be provided prior to any construction or the project can be phased. Dead end roads may not exceed 800' or 24 parcels; whichever comes first.

The above restrictions shall be shown as notes on the Improvement Plan.

Response: Condition satisfied. El Dorado Hills Fire Department approved Improvement Plans include subdivision safety and emergency improvements, as conditioned.

92. Lots G and H shall be reserved for future potential residential access and circulation to future development to the southeast. A notice of restriction shall be recorded with the final map for the phase in which these lots are located providing constructive notice of this development limitation. The language of the restriction shall be prepared by the applicant and reviewed by Planning Services prior to recording of the notice. The restriction may be rescinded if, after review of future development to the southeast, it is determined by the County and the El Dorado Hills Fire Department that one or both lots are not needed for circulation purposes.

Response: This condition does not apply to this phase of the subdivision. Conformance with this condition shall be verified with Phase 2B.

93. Lots that back up to wildland open space shall be required to use non-combustible type fencing. This condition shall be incorporated as a note on the Improvement Plan and verified prior to approval of Improvement Plan.

Response: Condition satisfied. El Dorado Hills Fire Department approved Improvement Plans confirms subdivision safety improvements, as conditioned.

COUNTY SURVEYOR

94. All survey monuments must be set prior to the representation of the final map to the Board of Supervisors for approval, or the developer shall a surety of work to be done by bond or cash deposit. Verification of set survey monuments, or amount of bond or deposit to coordinated with the County Surveyor's Office.

Response: Condition satisfied. Monuments have been set.

95. The roads serving the development shall be named by filing a completed Road Name Petition with the County Surveyor's Office prior to filing the Final Map.

Response: Condition satisfied. Road Name Petition has been approved.

EL DORADO HILLS COMMUNITY SERVICES DISTRICT (EDH CSD)

96. Prior to recordation of the first small-lot final map, a total of 10.1 acres of parkland shall be dedicated to the district via grant deed. The 3.3 acres of public park will be given 100% park credit and 50% credit will be given for the 6.6 acres of private park provided that the park site meets the CSD development standards. The remaining 3.5 acres of park shall be met either through payment of in-lieu fees or by applying credit towards the future Regional Park indicated in the CCSP and Unit 1 large lot map.

An agreement between the applicant and CSD shall be executed describing the method in which the remaining parkland dedication requirements will be satisfied prior to filing of the first small-lot final map

Response: Condition satisfied. An agreement between CSD and the applicant has been approved.

97. Prior to recordation of first small-lot final map, the applicant shall coordinate with the CSD in forming a Landscape and Lighting District (LLAD), which shall function as the funding mechanism for the maintenance and operation of the 3.3 acre public park site. The formation costs shall be borne by the applicant.

Response: Condition satisfied. The Carson Creek Master Association (HOA) will maintain the multi-use trail. See Section 1.1.14 entitled Master Association Maintenance Areas in the CC&Rs.

98. Prior to recordation of first small-lot final map, the applicant shall coordinate with the CSD in forming a shell Landscape and Lighting District (LLAD). The shell LLAD shall function as a back-up funding mechanism to the Carson Creek Homeowner's Association for the maintenance and operation of landscaping, streetscape, lighting, fencing, trails, walkways, signage, soundwalls and other common or public areas. The formation costs shall be borne by the applicant.

Response: Condition satisfied. A CFD is being prepared as a backup funding mechanism. The timing of the formation of the CFD is after recordation of the first final maps. However, the Park Development Agreement obligates Lennar to complete the formation of the CFD prior to closing of any homes at Carson Creek.

99. The multi-purpose trails shall be maintained by the future Homeowners Association (HOA) or through the LLAD in coordination with CSD. Evidence of dedicated funding mechanism for trail maintenance is required prior to recordation of first small-lot final map. CSD shall review and approve trail layout and design.

Response: Condition satisfied. The Carson Creek Master Association (HOA) will maintain the multi-use trail. See Section 1.1.14 entitled Master Association Maintenance Areas in the CC&Rs.

100. The project shall grant an Irrevocable Offer of Dedication through the open space area for trails to the El Dorado Hills Community Services District upon recording of the final map.

Response: Condition satisfied. IOD will be recorded with Final Map. However, the CSD is not interested in maintaining the trails and open space within the development. The responsibility for maintenance will be of the HOA.



El Dorado Irrigation District
METER AWARD LETTER

This serves as an award for:

Date: September 6, 2017

SUBDIVISION

PARCEL SPLIT

OTHER

APPLICANT/S NAME AND ADDRESS

PROJECT NAME, LOCATION & APN

Lennar Homes of California, Inc.

Carson Creek Unit 2A, Phase 1

1420 Rocky Ridge Dr., Ste. 320

El Dorado Hills, CA

Roseville, CA 95661

APN:117-570-14 and -20

This METER AWARD LETTER is issued to the - OWNER / AGENT (Circle one)

Note: If the agent is making the application, a duly notarized authorization must be attached.

SUBDIVISION - Applicant has met the following requirements:

1. District has approved the final Facility Plan Report.
2. Applicant submits verification of a valid Tentative Parcel Map from the County/City.
3. Applicant has satisfied all applicable engineering, environmental, right-of-way, and bonding requirements.
4. Applicant has paid all applicable water and wastewater fees, connection charges, and Bond Segregation Fees if applicable.
5. Applicant has satisfied all other District requirements.

PARCEL SPLIT - Applicant has met the following requirements for a Parcel Split:

1. Applicant submits Facility Improvement Letter.
2. Applicant completes Water Service Application form.
3. Applicant submits verification of a valid Tentative Parcel Map from the County/City.
4. Applicable water/wastewater connection fees paid.
5. Applicant pays Bond Segregation Fees; if applicable.
6. Bond Requirements (e.g. Performance/Guarantee) have been met if applicable.

The District hereby grants this award for:

WATER: 170 EDUs (Equivalent Dwelling Unit). **NOTE: 1-inch meters to be installed for fire sprinkler operation.**

RECYCLED WATER 0 EDUs (Equivalent Dwelling Unit).

WASTEWATER: 170 EDUs (Equivalent Dwelling Unit).

Project No. / Work Order No: 2570DEV / 766923

Service Purchase Project No.: 2725SP

Please Note: Building Permits will not be signed off until released by EID Inspection. Water meters will not be installed until the final map has been approved, new parcel numbers and addresses have been assigned and a release has been obtained from EID Inspection. It is the property owner's responsibility to notify the District upon final map.

Applicant has read the above information and acknowledges receipt of a copy of this Meter Award Letter.



Owner/Applicant Signature



Development Services

Original Copy - Project File

1 Copy - Applicant

1 Copy - County/City

Exhibit F