

**COUNTY OF EL DORADO
CONSTRUCTION CHANGE ORDER**

CHANGE ORDER DATE: 10/29/07
PROJECT: El Dorado Trail
PROJECT NO: 04-06A
CONTRACTOR: YubaCon, Inc.
520 Truck Street
Placerville, CA 95667
(530) 295-5890

C.O. NUMBER 02

PAGE 1 OF 1
Contract # 122-C0899

YOU ARE DIRECTED TO MAKE THE FOLLOWING CHANGES IN THIS CONTRACT PER THE FOLLOWING/ATTACHED:

ITEM NO.	DESCRIPTION	AMOUNT
04	Cost for repair of subgrade and installation of blanket drain in wetlands area due to constantly flowing water runoff. Excavation 200' x 20' x 18", placement of drain rock, fabric, and aggregate base.	\$16,151.75
05	Total costs for removing existing culvert discovered during grading at Sta. 129+00 and replacing with 18" HDPE at lower elevation, backfill and compacting.	.\$943.60
06	Cost for installation of OMP at subdrain located at Sta. 86+89. This includes excavation of temp. dewatering trench, removal of existing collection box, backfill around OMP, and placement of riprap.	\$6,138.10
07	Cost for installation of OMP and re-excavation of trench at System 9. This includes removal of existing metal flared end section, excavation of new trench away from trail, construction of berm to divert water away from trail, backfill around OMP, and placement of riprap.	\$8,242.27
08	Cost for excess fill placement on southern slope between Sta. 67+00 and 70+00. This includes trucking material to slope, placement and compaction of material.	\$14,365.58

*** ALL OTHER TERMS AND CONDITIONS OF THE CONTRACT DOCUMENTS SHALL REMAIN IN EFFECT.**

ORIGINAL CONTRACT AMOUNT WAS:	\$671,267.40
NET CHANGE BY PREVIOUSLY APPROVED CHANGE ORDERS:	\$ 25,835.00
APPROVED CONTRACT AMOUNT PRIOR TO THIS CHANGE ORDER WAS:	\$697,102.40
THIS CHANGE ORDER WILL <u>INCREASE</u> CONTRACT AMOUNT BY:	\$ 45,841.30
NEW CONTRACT AMOUNT INCLUDING THIS CHANGE ORDER IS:	\$742,943.70

THE CONTRACT TIME WILL CHANGE BY: (11) DAYS

THE REVISED CONTRACT COMPLETION DATE IS: November 15, 2007

NOT VALID UNTIL SIGNED BY OWNER, ARCHITECT/ENGINEER, AND CONTRACTOR

--

CONTRACTOR – YubaCon, Inc.	DATE
	11/8/07

PROJECT MANAGER – Jordan Postlewait	DATE
	11/8/07

DEPUTY DIRECTOR – George W. Sanders	DATE

(OWNER) COUNTY OF EL DORADO – Laura S. Gill	DATE

C:\WP51\WORK\FORMS\CHG-ORDR.FRM
– Project #04-06A
Change Order #01