





PD19-0003/Diamond Village Apartments Location Map Exhibit A











PD19-0003/Diamond Village Apartments Aerial Map Exhibit E

0 0.025 0.05 0.1 0.15 199.12425 D 5 of 73 Miles

### PARKING REQUIRED No. UNITS TYPE RESIDENT GUEST REQUIRED 40 2-BDRM 3-BDRM MANAGER 81

BUILDING LEGEND

COMMUNITY & 3-BEDROOM NUMBER of BUILDINGS | 1 NUMBER of WASHERS 9 NUMBER of DRYERS 9 UNITS PER BUILDING

F00TPRINT 3, 841

1-BEDROOM

UNITS PER o BUILDING ( NUMBER of BUILDINGS F00TPRINT 3, 697 TOTAL UNITS 16

2-BEDROOM UNITS PER BUILDING NUMBER of BUILDINGS F00TPRINT 4, 733 TOTAL UNITS 40

3-BEDROOM UNITS PER BUILDING NUMBER of BUILDINGS F00TPRINT 6, 056 | TOTAL UNITS | 16 |

1&3-BEDROOM I BEDROOM UNITS PER BUILDING BEDROOM UNITS PER BUILDING NUMBER of BUILDINGS F00TPRINT 5, 032 TOTAL UNITS | 8 |

PROJECT INFORMATION

GENERAL PLAN

DESIGNATION:

ELECTRICAL &

TELEPHONE:

GAS UTILITIES:

PACIFIC GAS & ELECTRIC

SEWAGE DISPOSAL:

SCHOOL DISTRICT:

EL DORADO UNION

EL DORADO IRRIGATION DISTRICT

WATER:

MFR - MULTI-FAMILY RESIDENTIAL

EL DORADO COUNTY FIRE DISTRICT

EL DORADO IRRIGATION DISTRICT

FIRE PROTECTION:

OWNER / APPLICANT:

8863 GREENBACK LN, STE 324

471 SUTTON WAY, SUITE 210 GRASS VALLEY, CA 95945

JERALD A. BECK, ARCHITECT

ASSESSOR'S PARCEL:

MICHELLE LAYSHOT, PE.

CONTACT PERSON: SERGEI OLESHKO

PLANNING & ENGINEERING:

MILLENNIUM PLANNING & ENGINEERING

ORANGEVALE, CA 95662

SNO FOUNDATION

(916) 949-8882

530-446-6765 CONTACT PERSON:

ARCHITECT:

CA LIC C11902

916-223-5152

051-461-59

LAND AREA:

10. 72 ACRES

ZONING:

REQUIRED 35	PARK ING PROVIDED				
	STANDARD	98			
90	COVERED	62			
45	COMPACT	12			
4	HAND I CAP	7			
174	TOTAL PROVIDED	179			

#### MIN. PARKING SIZE STANDARD: 9' WIDE, 19' DEEP COMPACT: 9' WIDE, 16' DEEP

AREA			
CALCULATIONS			KEYNOTES
AREA	SQFT	1	12" DEEP, 96" WIDE, 60" HIGH SIGN
CONDITIONED	78, 401	2	(E) 6' REDWOOD FENCE TO REMAIN
PORCH/PATIO	5, 859	3	PROPOSED 6' REDWOOD FENCE
STORAGE	3, 624	4	METAL STORAGE CONTAINER
LAUNDRY	170	5	PLAYGROUND CHILDREN AGES 2-12 (700SF)
COMMON AREA	12, 294	6	FIRE LANE, NO PARKING ALLOWED
SITE STORAGE	375	7	PLAYGROUND CHILDREN AGES 13-17 (700SE)

## DIAMOND VILLAGE APARUMENUS


### CONCEPUAL SUE PLAN

A PORTION OF THE SOUTH 1/2 OF SECTION 19 AND THE NORTH 1/2 OF SECTION 30, T.10 N., R.11 E., M.D.M. DIAMOND SPRINGS, EL DORADO COUNTY, CALIFORNIA OCTOBER, 2017 SCALE: |" = 50"




### **Exhibit F**

	SHEET INDEX
SHEET	TITLE
A0. 1	• CONCEPTUAL SITE PLAN
A0. 2	• NEIGHBORHOOD PARCEL MAP
A0. 3	• VICINITY MAP
A1. 1	• 1-BED FLOOR/ROOF PLAN
A1. 2	• 1-BED ELEVATIONS
A2. 1	• 2-BED FLOOR/ROOF PLAN
A2. 2	• 2-BED ELEVATIONS
A3. 1	• 3-BED FLOOR/ROOF PLAN
A3. 2	• 3-BED ELEVATIONS
A4. 1	• HYBRID FLOOR/ROOF PLAN
A4. 2	HYBRID ELEVATIONS
A5. 1	• COMMUNITY FL/ROOF PLAN
A5. 2	COMMUNITY ELEVATIONS



**VICINITY MAP** NO SCALE




## DIAMOND VILLAGE APARUMENUS

### VICINIUY MAP

A PORTION OF THE SOUTH 1/2 OF SECTION 19 AND THE NORTH 1/2 OF SECTION 30, T.10 N., R.II E., M.D.M.
DIAMOND SPRINGS, EL DORADO COUNTY, CALIFORNIA

OCTOBER, 2017 SCALE: |'' = 100'






SQUARE FOOTAGE


LIVING AREA - 648 SF


DECK/PATIO - 66 SF



ROOF PLAN

1/8"=1"-0"







FIRST FLOOR PLAN

1/8''=1'-0''

19-1425 D 8 of 73



I-BDRM ELEVATION 4 LEFT 1/6''=1'-0''



-BDRM ELEVATION 3 RIGHT 1/6''=1'-0''



TYPICAL EXTERIOR FINISHES

1. COMP ROOFING

I-BDRM ELEVATION FRONT/ REAR 1/6"=1"-0"




-BDRM ELEVATION I FRONT/REAR 1/6''=1'-0''

<ol> <li>COMP ROOFING</li> <li>STUCCO WALL FINISH</li> <li>STONE VENEER ACCENTS</li> <li>VINYL FRAME WINDOWS AND SLIDING DOORS</li> <li>COMPOSITE ENTRY DOORS</li> <li>FIBER CEMENT TRIMS AND FASCIAS</li> <li>METAL GUTTERS AND DOWNSPOUTS</li> <li>METAL HANDRAILS AND GUARDRAILS</li> <li>STEEL FRAME STAIRS / CONCRETE TREADS</li> </ol>	DESIGNED: MDW	DRAWN: MDW	PROJ. NO:201214	DWG:SEE DAY STAMP	DATE: SEE DAY STAMP	
	DATE					
	REVISIONS					
	NO.					
					IFORNIA	

### SQUARE FOOTAGE


LIVING AREA - 922 SF


DECK/PATIO - 60 SF



ROOF PLAN

1/8"="-0"





DIAMOND SPRINGS VILLAGE AF FLOOR PLAN/ROOF PL

SHEET
A2.1

19-1425 D 10 of 73



LEFT |/6''=|'-0''



TYPICAL EXTERIOR FINISHES

1. COMP ROOFING

2. STUCCO WALL FINISH


2. STUCCO WALL FINISH
3. STONE VENEER ACCENTS
4. VINYL FRAME WINDOWS AND SLIDING DOORS
5. COMPOSITE ENTRY DOORS
6. FIBER CEMENT TRIMS AND FASCIAS
7. METAL GUTTERS AND DOWNSPOUTS

8. METAL HANDRAILS AND GUARDRAILS
9. STEEL FRAME STAIRS / CONCRETE TREADS

2-BDRM ELEVATION

FRONT/REAR

1/6''=1'-0''



2-BDRM ELEVATION 3

RIGHT
1/6"=1'-0"





2-BDRM ELEVATION 2

FRONT/REAR
1/6''=1'-0''

DIAMOND SPRINGS VIL ARCHITECTURAL

SHEET
A2.2





LEFT 1/6''=1'-0''



TYPICAL EXTERIOR FINISHES

1. COMP ROOFING


2. STUCCO WALL FINISH
3. STONE VENEER ACCENTS

5. COMPOSITE ENTRY DOORS

4. VINYL FRAME WINDOWS AND SLIDING DOORS

6. FIBER CEMENT TRIMS AND FASCIAS
7. METAL GUTTERS AND DOWNSPOUTS
8. METAL HANDRAILS AND GUARDRAILS
9. STEEL FRAME STAIRS / CONCRETE TREADS

FRONT/REAR 1/6"=1"-0"



3-BDRM ELEVATION 3 



3-BDRM ELEVATION 2 FRONT/REAR 1/6"=1"-0"

19-1425 D 13 of 73

# ELEVATION I BEDROOM BEDROOM LIVING ROOM BEDROOM ELEVATION 3 DINING ROOM ELEVATION 4 DINING ROOM BEDROOM LIVING ROOM BEDROOM . SECOND FLOOR PLAN 1/8"="-0" ELEVATION 2 ELEVATION I BEDROOM LIVING ROOM BEDROOM BEDROOM FIRST FLOOR PLAN 1/8"=1"-0" ELEVATION 2 19-1425 D 14 of 73


## SQUARE FOOTAGE

LIVING AREA (3 BED) - 1234 SF

LIVING AREA (1 BED) - 704 SF

DECK/PATIO (3 BED) 60 SF

DECK/PATIO (1BED) 66 SF



ROOF PLAN
1/8"=1"-0"






I-BDRM/3-BDRM ELEVATION

FRONT/REAR

1/6"=1'-0"



I-BDRM/3-BDRM ELEVATION 3

RIGHT
1/6''=1'-0''




I-BDRM/3-BDRM ELEVATION 2

FRONT/REAR
1/6"=1'-0"

DIAMOND SPRINGS VILLAGE APARTME
ARCHITECTURAL ELEVATIONS

EL DORADO COUNTY 1BEDROOM/3BEDROOM-ELEVATIONS

A4.2



19-1425 D 16 of 73







DIAMOND VILLAGE APARTMENTS
6035 SERVICE DRIVE
PRELIMINARY GRADING AND DRAINAGE PLAN

-0401 DESCRIPTION DATE
-0401 DESCRIPTION DATE
-0401 DESCRIPTION DE

ROPESSION CTOP918

COVIL OF CALIFORNIA

SHEET NUMBER

## Preliminary Drainage Report

## Diamond Village Apartments Diamond Springs, CA

Prepared for:

#### **CoreCare Foundation**

Sergei Oleshko, Trustee 8863 Greenback Lane, Suite 324 Orangevale, CA 95662



Prepared by:

#### Millennium Planning & Engineering

471 Sutton Way, Ste 210 Grass Valley, CA 95945 T (530) 446-6765

**May 2019** 

### DRAINAGE REPORT

### Diamond Springs Village

#### **TABLE OF CONTENTS**

**SECTION 1: SUMMARY** 

A.	PURPOSE		1
B.	INTRODUCTION		1
C.	METHODOLOGY		2
D.	RESULTS AND CONCLU	SIONS	2
E.	REFERENCES		2

SECTION 2: HYDROLOGIC SOIL GROUP

**SECTION 3: RETENTION CALCULATIONS** 

SECTION 4: HYDRAULIC CALCULATIONS (TO BE COMPLETED IN

FINAL DESIGN)

#### **EXHIBITS**

EXHIBIT 1: DRAINAGE MAP

#### **SECTION 1: SUMMARY**

#### A. <u>PURPOSE</u>

The purpose of this report is to:

- Provide storm water quality treatment measures;
- Provide hydraulic analysis to meet El Dorado drainage standards; and
- Describe the proposed storm drainage and water quality treatment system.

#### B. <u>INTRODUCTION</u>

The proposed project consists of construction of affordable apartment units and one supervisory unit located south of Black Rice Lane, north of Pearl Place, east of Courtside drive, and west of Deuce Drive/Service Drive. The site is surrounded primarily by multi-family residential and rural single-family residential.

#### **Existing Site Conditions:**

The property is mostly grassy with trees. There are apartments and single-family homes on the west and south side of the property. The site generally slopes to the south west into existing storm drain systems on Service Drive and Deuce drive. A large portion of the drainage ultimately ends up in a culvert that outfalls into wetlands on the north side of Deuce Drive.

#### Proposed Site Drainage System:

On-site drainage will be collected in a series of storm water drainage systems and treated through infiltration treatment devices for filtering and infiltration. Overflow drainage will either connect to the existing storm drain system or will discharge into its natural pre-existing drainage pattern.

#### Water Quality Treatment Methods:

Storm drainage from impervious areas (roads, walks, roofs) is collected and routed through Stormtech chambers under pavement. Catch basins will contain a 12-inch deep sump for initial pre-treatment to capture sand and sediments through weep holes for infiltration.

During construction, additional BMPs including temporary erosion control facilities will be implemented to control pollutants that have a potential to affect the quality of storm water discharges from the construction site. Implementation of BMPs for Construction Activities will be in accordance with California State Water Resources Control Board (SWRCB) requirements.

#### C. <u>METHODOLOGY</u>

#### **Hydrology**

Hydrology calculations for the project site are provided in Section 3 of this report. The required retention volume for each drainage area is based on the unit storage basin to achieve 85th percentile, 24-hr storm volume of treatment based on the "design storm," per El Dorado County post construction runoff procedures. A web-based tool (http://www.owp.csus.edu/LIDTool/Start.aspx) for sizing LID devices was used to calculate the volume requirements based on the design storm and soil hydraulic conductivity. Based on the website, the 85th percent capture is 1.13 inches for the site and the hydraulic conductivity is 1 in/hr. Retention calculations are provided in Section 3 — Retention Calculations.

#### **Hydraulics**

Hydraulic Calculations will be completed during the construction document phase of the project.

#### **Detention**

The post-development rate and volume will be reduced below the predevelopment flow rate with the infiltration facilities and BMP's identified herein. Onsite retention facilities will reduce the post-development flow by attenuating the peak flow.

#### D. RESULTS AND CONCLUSIONS

As described above, the planned design incorporates current requirements of El Dorado County for post-construction treatment requirements for the 85th percentile, 24-hr storm. Proposed drainage improvements meet water quality objectives, provide groundwater recharge, minimize erosion and provide conveyance to natural drainage courses as required. Drainage details and hydraulic calculations will be provided in final design.

#### E. REFERENCES

- Western El Dorado County Storm Water Management Plan, dated August, 2004
- El Dorado Apartments Preliminary Grading, Drainage and Utilities Plan, by Millennium Planning & Engineering, Inc, dated May 2019.
- Sacramento State Office of Water Programs, California Phase II LID Sizing Tool, http://www.owp.csus.edu/LIDTool/Start.aspx, May 2019.

As always please feel free to contact our office at (530) 446-6765 with any questions.

Millennium Planning & ENGINEERING, INC.

Michelle Layshot, P.E., QSD/QSP

Principal Engineer

Michelle hayshot

## SECTION 2: HYDROLOGIC SOIL GROUP



Sac State Home | College of Engineering & Computer Science | Department of Civil Engineering | Office of Water Programs

#### California Phase II LID Sizing Tool

Welcome to the California Phase II Low Impact Development (LID) Sizing Tool. This is a web-based tool that assists stormwater practitioners in selecting and sizing LID Best Management Practices (BMPs) that meet the sizing requirements set forth in California's National Pollutant Discharge Elimination System (NPDES) permit for stormwater discharges from small municipal separate storm sewer systems (MS4s). The tool allows users to input their location, soil type, and impervious areas, and then queries a database containing pre-solved sizing factors and design curves for a variety of LID BMP types, performs permit-based sizing calculations, and tabulates allowable sizes for each LID BMP type. Sizing results are provided based on three different sizing methods allowed by the Phase II permit: a Design Storm Method, a Percent Capture Method, and a Baseline Bioretention or Equivalent Performance Method, Sizing results are also provided for the Central Coast RWQCB (Region 3) simple sizing method adopted via resolution R3-2013-0032. Users are also provided references for considering LID BMP feasibility factors beyond sizing, such as site topography and geometry and LID BMP maintenance requirements and costs. The tool includes training videos to visually instruct users on various aspects of the tool's interface, input, and output. Further information about the tool and its development is provided in the Documentation Manual.

Development of this tool was funded by the California State Water Resources Control Board's (SWRCB) Proposition 84 Stormwater Grant Program (SWGP).

The tool consists of a website that is linked to a database through a server. The database stores precipitation and evaporation data for multiple geographic locations throughout California, pre-defined parameters for multiple LID BMP types and project soil types, and pre-solved design curves based on SWMM 5 modeling. Over 13,000 SWMM simulations were run to develop these curves. After the user enters project information into the tool's website, the server queries the database, performs calculations, and tabulates the areas required for various LID BMP types.

Use these Layers to help you find the inputs for steps 1 to 3 below the map

#### Step 1

Climate Stations

#### Step 2

Soil Types

#### Step 3

Find your impervious area

Measure

Clear

Distance (feet): 0


Area (acres): 0

To ensure the most accurate values zoom in close to vour

site.

#### Other Layers

Counties



## SECTION 3: RETENTION REQUIREMENTS

## DRAINAGE AREA "A" RETENTION REQUIREMENTS

#### California Phase II LID Sizing Tool - v1.1

#### **Step 5 - Site Design Measures**

Project name Diamond Springs Apartments Area A

Climate station PLACERVILLE

Saturated hydraulic conductivity 1 in/hr

Impervious area 14180 square feet

Design storm 1.13 in

Site Design Measures (SDMs) must first be implemented to the extent technically feasible before implementing Storm Water Treatment Measures (SWTMs). SDMs must be sized using the 85th percentile, 24-hour storm, or another design storm as adopted by local regulators.

#### Site Design Measures Using a Design Storm of 1.13 Inches

LID BMP Types		(square feet)	Accomplished	
Porous Pavement	685	0.00	0.00	
Strip, Amended 6"	21333	0.00	0.00	
Strip, Amended 12"	5787	0.00	0.00	
Strip, Amended 18"	3347	0.00	0.00	
Swale, Amended 6"2	21333	0.00	0.00	
Swale, Amended 12"2	5787	0.00	0.00	
Swale, Amended 18"2	3347	0.00	0.00	
Capture and Use Storage <sup>3</sup>	1230 cf	0.00 c	f 0.00	
	Totals	0.000	0.00	



Instructions for Site Design Measures +

Footnotes +

Background +

CA Phase II LID Sizing Tool Methods +

Special Notes Regarding the Tables +

<sup>©</sup> Office of Water Programs | 2017 All Rights Reserved. Funding for this project has been provided in full or in part through an agreement with the State Water Resources Control Board and the California Department of Parks and Recreation. The contents of this



#### **User Inputs**

#### <u>Results</u>

Chamber Model: MC-3500

Outlet Control Structure: Yes

**Project Name:** Diamond Springs

Apartments

Engineer: N/A

Project Location: California

Measurement Type: Imperial

**Required Storage Volume:** 1230 cubic ft.

Stone Porosity: 40%

**Stone Foundation Depth:** 9 in.

Stone Above Chambers: 12 in.

**Average Cover Over Chambers:** 24 in.

**Design Constraint Dimensions:**  $(14 \text{ ft.} \times 50 \text{ ft.})$ 

System Volume and Bed Size

**Installed Storage Volume:** 1316.21 cubic ft.

**Storage Volume Per Chamber:** 109.90 cubic ft.

Number Of Chambers Required: 6
Number Of End Caps Required: 2

Chamber Rows: 1

Maximum Length: 48.75 ft.

Maximum Width: 8.42 ft.


**Approx. Bed Size Required:** 410.31 square ft.

**System Components** 

**Amount Of Stone Required:** 58.06 cubic yards

Volume Of Excavation (Not Including 83.58 cubic yards

Fill):



\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 30" (750 mm).

## DRAINAGE AREA "B" RETENTION REQUIREMENTS

#### California Phase II LID Sizing Tool - v1.1

#### **Step 5 - Site Design Measures**

Project name Diamond Springs Apartments Area B

Climate station PLACERVILLE

Saturated hydraulic conductivity 1 in/hr

Impervious area 16060 square feet

Design storm 1.13 in

Site Design Measures (SDMs) must first be implemented to the extent technically feasible before implementing Storm Water Treatment Measures (SWTMs). SDMs must be sized using the 85th percentile, 24-hour storm, or another design storm as adopted by local regulators.

#### Site Design Measures Using a Design Storm of 1.13 Inches

LID BMP Types		Area Avaliable (square feet)	Percent Accomplished
Porous Pavement	776	0.00	0.00
Strip, Amended 6"	24161	0.00	0.00
Strip, Amended 12"	6554	0.00	0.00
Strip, Amended 18"	3791	0.00	0.00
Swale, Amended 6"2	24161	0.00	0.00
Swale, Amended 12"2	6554	0.00	0.00
Swale, Amended 18"2	3791	0.00	0.00
Capture and Use Storage <sup>3</sup>	1393 cf	0.00 c	f 0.00
	Totals	0.000	0.00



Instructions for Site Design Measures +

Footnotes +

Background +

CA Phase II LID Sizing Tool Methods +

Special Notes Regarding the Tables +

<sup>©</sup> Office of Water Programs | 2017 All Rights Reserved. Funding for this project has been provided in full or in part through an agreement with the State Water Resources Control Board and the California Department of Parks and Recreation. The contents of this



#### **User Inputs**

#### Results

Chamber Model: MC-3500

Outlet Control Structure: Yes

**Project Name:** Diamond Springs

Apartments

Engineer: N/A

**Project Location:** California

Measurement Type: Imperial

**Required Storage Volume:** 1393 cubic ft.

Stone Porosity: 40%

**Stone Foundation Depth:** 9 in.

Stone Above Chambers: 12 in.

**Average Cover Over Chambers:** 24 in.

**Design Constraint Dimensions:** (18 ft. x 60 ft.)

System Volume and Bed Size

**Installed Storage Volume:** 1514.85 cubic ft.

**Storage Volume Per Chamber:** 109.90 cubic ft.

Number Of Chambers Required: 7
Number Of End Caps Required: 2
Chamber Rows: 1

**Maximum Length:** 55.92 ft.

**Maximum Width:** 8.42 ft.


**Approx. Bed Size Required:** 470.63 square ft.

#### **System Components**

**Amount Of Stone Required:** 66.27 cubic yards

Volume Of Excavation (Not Including 95.87 cubic yards

Fill):



\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 30" (750 mm).

## DRAINAGE AREA "C" RETENTION REQUIREMENTS

#### California Phase II LID Sizing Tool - v1.1

#### **Step 5 - Site Design Measures**

Project name Diamond Springs Apartments Area C

Climate station PLACERVILLE

Saturated hydraulic conductivity 1 in/hr

Impervious area 53202 square feet

Design storm 1.13 in

Site Design Measures (SDMs) must first be implemented to the extent technically feasible before implementing Storm Water Treatment Measures (SWTMs). SDMs must be sized using the 85th percentile, 24-hour storm, or another design storm as adopted by local regulators.

#### Site Design Measures Using a Design Storm of 1.13 Inches

LID BMP Types		(square feet)	Accomplished	
Porous Pavement	2570	0.00	0.00	
Strip, Amended 6"	80038	0.00	0.00	
Strip, Amended 12"	21711	0.00	0.00	
Strip, Amended 18"	12559	0.00	0.00	
Swale, Amended 6"2	80038	0.00	0.00	
Swale, Amended 12"2	21711	0.00	0.00	
Swale, Amended 18"2	12559	0.00	0.00	
Capture and Use Storage <sup>3</sup>	4614 cf	0.00 ct	0.00	
	Totals	0.000	0.00	



Instructions for Site Design Measures +

Footnotes +

Background +

CA Phase II LID Sizing Tool Methods +

Special Notes Regarding the Tables +

<sup>©</sup> Office of Water Programs | 2017 All Rights Reserved. Funding for this project has been provided in full or in part through an agreement with the State Water Resources Control Board and the California Department of Parks and Recreation. The contents of this



#### **User Inputs**

#### **Results**

Chamber Model: MC-3500

Outlet Control Structure: Yes

**Project Name:** Diamond Springs

Apartments

Engineer: N/A

Project Location: California

Measurement Type: Imperial

**Required Storage Volume:** 4614 cubic ft.

Stone Porosity: 40%

**Stone Foundation Depth:** 12 in.

Stone Above Chambers: 12 in.

**Average Cover Over Chambers:** 24 in.

**Design Constraint Dimensions:** (30 ft. x 80 ft.)

#### System Volume and Bed Size

**Installed Storage Volume:** 4652.52 cubic ft.

**Storage Volume Per Chamber:** 109.90 cubic ft.

Number Of Chambers Required: 21
Number Of End Caps Required: 6
Chamber Rows: 3

Maximum Length:59.85 ft.Maximum Width:23.35 ft.


**Approx. Bed Size Required:** 1397.45 square ft.

#### **System Components**

Amount Of Stone Required: 208.82 cubic yards

Volume Of Excavation (Not Including 297.61 cubic yards

Fill):



\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 30" (750 mm).

# DRAINAGE AREA "D" RETENTION REQUIREMENTS

# California Phase II LID Sizing Tool - v1.1

## **Step 5 - Site Design Measures**

Project name Diamond Springs Apartments Area D

Climate station PLACERVILLE

Saturated hydraulic conductivity 1 in/hr

Impervious area 16180 square feet

Design storm 1.13 in

Site Design Measures (SDMs) must first be implemented to the extent technically feasible before implementing Storm Water Treatment Measures (SWTMs). SDMs must be sized using the 85th percentile, 24-hour storm, or another design storm as adopted by local regulators.

#### Site Design Measures Using a Design Storm of 1.13 Inches

LID BMP Types		(square feet)	Accomplished
Porous Pavement	781	0.00	0.00
Strip, Amended 6"	24341	0.00	0.00
Strip, Amended 12"	6603	0.00	0.00
Strip, Amended 18"	3819	0.00	0.00
Swale, Amended 6"2	24341	0.00	0.00
Swale, Amended 12"2	6603	0.00	0.00
Swale, Amended 18"2	3819	0.00	0.00
Capture and Use Storage <sup>3</sup>	1403 cf	0.00 c	0.00
	Totals	0.000	0.00



Instructions for Site Design Measures +

Footnotes +

Background +

CA Phase II LID Sizing Tool Methods +

Special Notes Regarding the Tables +

<sup>©</sup> Office of Water Programs | 2017 All Rights Reserved. Funding for this project has been provided in full or in part through an agreement with the State Water Resources Control Board and the California Department of Parks and Recreation. The contents of this



# **User Inputs**

# <u>Results</u>

Chamber Model: MC-3500

Outlet Control Structure: Yes

**Project Name:** Diamond Springs

Apartments Area D

Engineer: N/A

Project Location: California

Measurement Type: Imperial

**Required Storage Volume:** 1403 cubic ft.

Stone Porosity: 40%

**Stone Foundation Depth:** 12 in.

Stone Above Chambers: 12 in.

**Average Cover Over Chambers:** 24 in.

**Design Constraint Dimensions:** (30 ft. x 80 ft.)

# System Volume and Bed Size

**Installed Storage Volume:** 1357.24 cubic ft.

**Storage Volume Per Chamber:** 109.90 cubic ft.

Number Of Chambers Required: 6

Number Of End Caps Required: 2

Chamber Rows: 1

**Maximum Length:** 48.75 ft.

Maximum Width: 8.42 ft.


**Approx. Bed Size Required:** 410.31 square ft.

# **System Components**

**Amount Of Stone Required:** 61.86 cubic yards

Volume Of Excavation (Not Including 87.38 cubic yards

Fill):



\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 30" (750 mm).

# DRAINAGE AREA "E" RETENTION REQUIREMENTS

# California Phase II LID Sizing Tool - v1.1

## **Step 5 - Site Design Measures**

Project name Diamond Springs Apartments Area E

Climate station PLACERVILLE

Saturated hydraulic conductivity 1 in/hr

Impervious area 33980 square feet

Design storm 1.13 in

Site Design Measures (SDMs) must first be implemented to the extent technically feasible before implementing Storm Water Treatment Measures (SWTMs). SDMs must be sized using the 85th percentile, 24-hour storm, or another design storm as adopted by local regulators.

#### Site Design Measures Using a Design Storm of 1.13 Inches

LID BMP Types		Area Avaliable (square feet)	Accomplished
Porous Pavement	1641	0.00	0.00
Strip, Amended 6"	51120	0.00	0.00
Strip, Amended 12"	13867	0.00	0.00
Strip, Amended 18"	8021	0.00	0.00
Swale, Amended 6"2	51120	0.00	0.00
Swale, Amended 12"2	13867	0.00	0.00
Swale, Amended 18"2	8021	0.00	0.00
Capture and Use Storage <sup>3</sup>	2947 cf	0.00 cf	0.00
	Totals	0.000	0.00



Instructions for Site Design Measures +

Footnotes +

Background +

CA Phase II LID Sizing Tool Methods +

Special Notes Regarding the Tables +

<sup>©</sup> Office of Water Programs | 2017 All Rights Reserved. Funding for this project has been provided in full or in part through an agreement with the State Water Resources Control Board and the California Department of Parks and Recreation. The contents of this



# **User Inputs**

# Results

Chamber Model: MC-3500

Outlet Control Structure: Yes

**Project Name:** Diamond Springs

Apartments Area E

Engineer: N/A

Project Location: California

Measurement Type: Imperial

**Required Storage Volume:** 2947 cubic ft.

Stone Porosity: 40%

**Stone Foundation Depth:** 12 in.

Stone Above Chambers: 12 in.

**Average Cover Over Chambers:** 24 in.

**Design Constraint Dimensions:** (30 ft. x 80 ft.)

System Volume and Bed Size

**Installed Storage Volume:** 2992.60 cubic ft.

**Storage Volume Per Chamber:** 109.90 cubic ft.

Number Of Chambers Required: 13

Number Of End Caps Required: 4

Chamber Rows: 2

**Maximum Length:** 59.85 ft.

**Maximum Width:** 16.18 ft.


**Approx. Bed Size Required:** 912.88 square ft.

# **System Components**

**Amount Of Stone Required:** 139.29 cubic yards

Volume Of Excavation (Not Including 194.41 cubic yards

Fill):



\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 30° (750 mm).

# DRAINAGE AREA "F" RETENTION REQUIREMENTS

# California Phase II LID Sizing Tool - v1.1

## **Step 5 - Site Design Measures**

Project name Diamond Springs Apartments Area F

Climate station PLACERVILLE

Saturated hydraulic conductivity 1 in/hr

Impervious area 13400 square feet

Design storm 1.13 in

Site Design Measures (SDMs) must first be implemented to the extent technically feasible before implementing Storm Water Treatment Measures (SWTMs). SDMs must be sized using the 85th percentile, 24-hour storm, or another design storm as adopted by local regulators.

#### Site Design Measures Using a Design Storm of 1.13 Inches

LID BMP Types		(square feet)	Accomplished
Porous Pavement	647	0.00	0.00
Strip, Amended 6"	20159	0.00	0.00
Strip, Amended 12"	5468	0.00	0.00
Strip, Amended 18"	3163	0.00	0.00
Swale, Amended 6"2	20159	0.00	0.00
Swale, Amended 12"2	5468	0.00	0.00
Swale, Amended 18"2	3163	0.00	0.00
Capture and Use Storage <sup>3</sup>	1162 cf	0.00 c	f 0.00
	Totals	0.000	0.00



Instructions for Site Design Measures +

Footnotes +

Background +

CA Phase II LID Sizing Tool Methods +

Special Notes Regarding the Tables +

<sup>©</sup> Office of Water Programs | 2017 All Rights Reserved. Funding for this project has been provided in full or in part through an agreement with the State Water Resources Control Board and the California Department of Parks and Recreation. The contents of this



# **User Inputs**

# Results

Chamber Model: MC-3500

Outlet Control Structure: Yes

**Project Name:** Diamond Springs

Apartments Area F

Engineer: N/A

**Project Location:** California

Measurement Type: Imperial

**Required Storage Volume:** 1162 cubic ft.

Stone Porosity: 40%

**Stone Foundation Depth:** 12 in.

Stone Above Chambers: 12 in.

**Average Cover Over Chambers:** 24 in.

**Design Constraint Dimensions:** (24 ft. x 60 ft.)

System Volume and Bed Size

**Installed Storage Volume:** 1152.56 cubic ft.

**Storage Volume Per Chamber:** 109.90 cubic ft.

Number Of Chambers Required: 5
Number Of End Caps Required: 2
Chamber Rows: 1

**Maximum Length:** 41.58 ft.

Maximum Width: 8.42 ft.


**Approx. Bed Size Required:** 349.99 square ft.

**System Components** 

**Amount Of Stone Required:** 53.08 cubic yards

Volume Of Excavation (Not Including 74.54 cubic yards

Fill):



\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 30" (750 mm).

# DRAINAGE AREA "G" RETENTION REQUIREMENTS

# California Phase II LID Sizing Tool - v1.1

## **Step 5 - Site Design Measures**

Project name Diamond Springs Apartments Area G

Climate station PLACERVILLE

Saturated hydraulic conductivity 1 in/hr

Impervious area 14770 square feet

Design storm 1.13 in

Site Design Measures (SDMs) must first be implemented to the extent technically feasible before implementing Storm Water Treatment Measures (SWTMs). SDMs must be sized using the 85th percentile, 24-hour storm, or another design storm as adopted by local regulators.

#### Site Design Measures Using a Design Storm of 1.13 Inches

LID BMP Types		Area Available (square feet)	Accomplished
Porous Pavement	713	0.00	0.00
Strip, Amended 6"	22220	0.00	0.00
Strip, Amended 12"	6027	0.00	0.00
Strip, Amended 18"	3487	0.00	0.00
Swale, Amended 6"2	22220	0.00	0.00
Swale, Amended 12"2	6027	0.00	0.00
Swale, Amended 18"2	3487	0.00	0.00
Capture and Use Storage <sup>3</sup>	1281 cf	0.00 c	0.00
	Totals	0.000	0.00



Instructions for Site Design Measures +

Footnotes +

Background +

CA Phase II LID Sizing Tool Methods +

Special Notes Regarding the Tables +

<sup>©</sup> Office of Water Programs | 2017 All Rights Reserved. Funding for this project has been provided in full or in part through an agreement with the State Water Resources Control Board and the California Department of Parks and Recreation. The contents of this



# **User Inputs**

# <u>Results</u>

Chamber Model: MC-3500

Outlet Control Structure: Yes

**Project Name:** Diamond Springs

Apartments Area Gg

Engineer: N/A

Project Location: California

Measurement Type: Imperial

**Required Storage Volume:** 1281 cubic ft.

Stone Porosity: 40%

**Stone Foundation Depth:** 12 in.

Stone Above Chambers: 12 in.

**Average Cover Over Chambers:** 24 in.

**Design Constraint Dimensions:** (30 ft. x 50 ft.)

# System Volume and Bed Size

**Installed Storage Volume:** 1398.06 cubic ft.

**Storage Volume Per Chamber:** 109.90 cubic ft.

Number Of Chambers Required: 5
Number Of End Caps Required: 4

Maximum Length: 31.18 ft.

Maximum Width: 16.18 ft.

**Approx. Bed Size Required:** 448.96 square ft.

# **System Components**


2

**Amount Of Stone Required:** 73.05 cubic yards

Volume Of Excavation (Not Including 95.61 cubic yards


Fill):

**Chamber Rows:** 



\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 30" (750 mm).

# EXHIBIT 1: DRAINAGE MAP





STINENTS ADVENTIC	6035 SERVICE DRIVE	DD AINI ACE MAD	DIAMOND SPRINGS
DATE			
DESCRIPTION			
REV.			

SHEET NUMBER



Letter No.: EEO2017-0401

Exhibit H

March 21, 2017

VIA FIRST-CLASS MAIL

Sergei Oleshko Core Care Foundation 8863 Greenback Lane, Ste 324 Orangevale, CA 95662

Subject: Facility Improvement Letter (FIL), Diamond Springs Village Apartments Assessor's Parcel No. 051-461-59 (Diamond Springs)

Dear Mr. Oleshko:

This letter is in response to your request dated February 13, 2017 and is valid for a period of three years. If facility improvement plans for your project are not submitted to El Dorado Irrigation District (EID or District) within three years of the date of this letter, a new Facility Improvement Letter will be required.

Design drawings for your project must be in conformance with the District's Water, Sewer and Recycled Water Design and Construction Standards.

This proposed project is an 81-unit multifamily apartment complex on 10.7 acres. Water service, sewer service, private fire service and fire hydrants are requested. The property is within the District boundary.

This letter is not a commitment to serve, but does address the location and approximate capacity of existing facilities that may be available to serve your project.

#### Water Supply

As of January 1, 2016, there were 12,537 equivalent dwelling units (EDUs) of water supply available in the Western/Eastern Water Supply Region. Your project as proposed on this date would require approximately 60 EDUs of water supply.

#### **Water Facilities**

An 8-inch water line exists in Black Rice Road and 8-inch water lines are also located on the parcel to be developed (see enclosed System Map). The Diamond Springs/El Dorado Fire Protection District has determined that the minimum fire flow for this project is 1,500 GPM for a 2-hour duration while maintaining a 20-psi residual pressure. According to the District's hydraulic model, the existing system can deliver the required fire flow. In order to provide this fire flow and receive service, you must construct a water line extension connecting to the previously identified water facilities. The hydraulic grade line for the existing water distribution facilities is 2,080 feet above mean sea level at static conditions and 2,029 feet above mean sea level during fire flow and maximum day demands.

Letter No.: EEO2017-0401 To: Sergei Oleshko

The flow predicted above was developed using a computer model and is not an actual field flow test.

#### **Sewer Facilities**

There is a 6-inch sewer line traversing the property to be developed. This sewer line has adequate capacity at this time. In order to receive service from this line, an extension of facilities of adequate size must be constructed. Your project as proposed on this date would require approximately 56 EDUs of sewer service.

## **Easement Requirements**

Proposed and existing water lines, sewer lines and related facilities must be located within an easement accessible by conventional maintenance vehicles. When the water lines or sewer lines are within streets, they shall be located within the paved section of the roadway. No structures will be permitted within the easements of any existing or proposed facilities. The District must have unobstructed access to these easements at all times, and generally does not allow water or sewer facilities along lot lines.

Easements for any new District facilities constructed by this project must be granted to the District prior to District approval of water and/or sewer improvement plans, whether onsite or offsite. In addition, due to either nonexistent or prescriptive easements for some older facilities. any existing onsite District facilities that will remain in place after the development of this property must also have an easement granted to the District.

#### **Environmental**

The County is the lead agency for environmental review of this project per Section 15051 of the California Environmental Quality Act Guidelines (CEQA). The County's environmental document should include a review of both offsite and onsite water and sewer facilities that may be constructed by this project. You may be requested to submit a copy of the County's environmental document to the District if your project involves significant off-site facilities. If the County's environmental document does not address all water and sewer facilities and they are not exempt from environmental review, a supplemental environmental document will be required. This document would be prepared by a consultant. It could require several months to prepare and you would be responsible for its cost.

#### Summary

Service to this proposed development is contingent upon the following:

- The availability of uncommitted water supplies at the time service is requested;
- Approval of the County's environmental document by the District (if requested):
- Executed grant documents for all required easements;
- Approval of an extension of facilities application by the District;
- Approval of facility improvement plans by the District;
- Construction by the developer of all onsite and offsite proposed water and sewer facilities.
- · Acceptance of these facilities by the District; and
- Payment of all District connection costs.

Letter No.: EEO2017-0401 To: Sergei Oleshko



Services shall be provided in accordance with El Dorado Irrigation District Board Policies and Administrative Regulations, as amended from time-to-time. As they relate to conditions of and fees for extension of service, District Administrative Regulations will apply as of the date of a fully executed Extension of Facilities Agreement.

If you have any questions, please contact Marc Mackay at (530) 642-4135.

Sincerely,

Michael J. Brink, P.E. Supervising Civil Engineer


MB/MM:at

Enclosures: System Map

cc w/ System Map:

Kenneth Earle – Deputy Chief / Fire Marshal Diamond Springs / El Dorado Fire Department Via email - kearle@diamondfire.org

Roger Trout, Director El Dorado County Development Services Department Via email - roger.trout@edcgov.us



# DIAMOND SPRINGS VILLAGE APARTMENTS

DIAMOND SPRINGS, EL DORADO COUNTY, CALIFORNIA


# **Exhibit I**

# WATER BUDGET CALCULATIONS REFERENCE EVAPOTRANSPIRATION = 47.3 INCHES PER YEAR (CAMINO STATION) $MAWA = (ETo) (.62) [(.7 \times SF) + (.3 \times SLA)]$ $= (47.3") (.62) [(.45 \times 54,119) + (.3 \times 0)]$ = 714,192 GALLONS PER YEAR ETWU = (ETo) (.62) $\left(\frac{PF \times HA}{PF \times HA}\right) + SLA$ LOW PLANTS = (47.3) (.62) $\left(\frac{.3 \times 50,384}{.81}\right) + 0 = 547,244$ GALLONS PER YEAR HIGH LAWN = $(47.3) (.62) \left( \frac{.7 \times 3,735}{-5} \right) + 0 = 102,230 \text{ GALLONS PER YEAR}$ TOTAL ETWU = 714,192 GALLONS PER YEAR MAWA = 649,474 GALLONS PER YEAR ETWU < MAWA

SYM	BOTANICAL/ COMMON NAME	SIZE	QTY	WATER USE	HTxWD
0	TREES  CERCIS CANADENSIS 'OAKLAHOMA'/EASTERN REDBUD FRUIT TREES (APPLE, GRAPEFRUIT, LEMON, ORANGE)	15 GAL	41	LOW	18'x18'
	QUERCUS WISLIZENII/INTERIOR LIVE OAK	24" BOX	20	LOW	35'x35'
	ACER 'RUBRUM'/ RED MAPLE	15 GAL	20	LOW	30'x30'
	SHRUBS/ GROUNDCOVER				
+ + + + +	ARCTOSTAPHYLOS 'EMERALD CARPET'/MANZANITA	5 GAL		LOW	
+ + + + + + + +	CISTUS LADANIFER/CRIMSON SPOT ROCKROSE	5 GAL		LOW	4'x4'
*	DIETES VEGETA/FORTNIGHT LILY	1 GAL		LOW	30"x24
+ + + + + + +	MYRTUS COMMUNIS 'COMPACTA'/COMPACT MYTRLE MUHLENBERGIA RIGENS/DEER GRASS	5 GAL 5 GAL		LOW	3'x3' 4'x4'
++++++		1 GAL	<b></b>	LOW	4 x4 30"x30
+ + + + + + + + +	NANDINA 'GULF STREAM'/ COMPACT HEAVENLY BAMBOO	I GAL	<b></b>	LOVV	30 X30
+++++++	ROSMARINUS OFFICINALIS TUSCAN BLUE/ROSEMARY	1 GAL	<del></del>	LOW	5'x3'
+ + + + +	STIPA TENUISSIMA/MEXICAN FEATHER GRASS	1 GAL		LOW	30"x24


# PLANTING NOTES


- PLANTING SHALL CONFORM TO EL DORADO COUNTY REQUIREMENTS FOR LANDSCAPE SITE DEVELOPMENT.
- 2. PROVIDE MINIMUM SLOPE OF 1 ½% FOR POSITIVE DRAINAGE AWAY FROM CENTER IN ALL PLANTED AREAS.
- 3. THE PLANT QUANTITIES SHOWN ON THE DRAWINGS ARE INFORMATIONAL ONLY. THE CONTRACTOR IS RESPONSIBLE FOR FINAL QUANTITIES REQUIRED TO COMPLETE THE WORK. IN CASE OF DISCREPANCY, THE PLAN SHALL GOVERN.
- 4. ALL TREES SHALL BE PLANTED A MINIMUM OF 5' FROM UNDERGROUND UTILITIES.
- 5. ALL EXISTING TREES SHALL BE PROTECTED FROM DAMAGE OR INJURY. NO PARKING OR STACKING OF CONSTRUCTION MATERIAL IS ALLOWED WITHIN THE DRIPLINE OF AN EXISTING TREE.
- 6. IMMEDIATELY AFTER AWARD OF CONTRACT, THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT IF SPECIFIED PLANT MATERIAL IS AVAILABLE FROM COMMERCIAL NURSERIES. IN THE EVENT THAT A PLANT IS NOT AVAILABLE, THE LANDSCAPE ARCHITECT WILL PROVIDE ALTERNATE PLANT MATERIAL SELECTIONS. SUCH CHANGES WILL NOT ALTER THE CONTRACTOR'S ORIGINAL BID PRICE UNLESS A CREDIT IS DUE TO THE OWNER.
- 7. THE CONTRACTOR SHALL ENSURE THAT ALL EXCAVATED PLANT PITS HAVE POSITIVE DRAINAGE. PLANT PITS SHALL BE FULLY FILLED WITH WATER AND SHALL DRAIN WITHIN ONE (1) HOUR OF FILLING. THE CONTRACTOR SHALL EXCAVATE THROUGH ANY IMPERVIOUS LAYER IF ENCOUNTERED.
- 8. ALL PLANT MATERIAL SHALL COMPLY WITH ANSI Z601 'STANDARD FOR NURSERY STOCK'.
- 9. ROOT BARRIERS SHALL BE PROVIDED FOR ALL TREES WITHIN ANY PLANTING AREAS THAT ARE LESS THAN 10' WIDE.
- 10. ALL PLANTER AREAS SHALL RECEIVE A 3" LAYER OF BARK MULCH.
- 11. THE CONTRACTOR SHALL PROVIDE A SOILS REPORT PREPARED BY A QUALIFIED SOILS SPECIALIST AND SUBMIT TO THE OWNER FOR FINAL APPROVAL. SOILS SAMPLES SHALL BE COLLECTED AFTER ROUGH GRADING OPERATIONS AND PRIOR TO THE INSTALLATION OF PLANT MATERIAL. SOIL SAMPLES SHALL BE SUFFICIENTLY NUMEROUS TO ACCOUNT FOR ANY SOIL VARIATIONS THAT MAY BE PRESENT ON THE SITE. THE FOLLOWING MINIMUM ITEMS SHALL BE INCLUDED IN THE ANALYSIS:
  - A. INFILTRATION RATE.
  - B. SOIL TEXTURE. C. CATION EXCHANGE CAPACITY.
  - D. SOIL FERTILITY INCLUDING TESTS FOR NITROGEN, POTASSIUM, PHOSPHOROUS, PH, ORGANIC MATTER AND SPECIFIC CONDUCTANCE (E.C.).
- 12. PRIOR TO PLANTING, SOIL AMENDMENTS SHALL BE ADDED PER RECOMMENDATIONS OF THE SOILS REPORT. SOIL AMENDMENTS SHOWN ON THE PLANS ARE TO BE USED FOR BIDDING PURPOSES ONLY. THE RESULTS OF THE SOILS TESTS THE CONTRACTOR PERFORMS SHALL DETERMINE ACTUAL AMENDMENTS. FAILURE TO PERFORM SOILS ANALYSIS AND RECOMMENDED SOILS AMENDMENTS WILL RESULT IN REPLACEMENT OF PLANT MATERIAL. CONTRACTOR WILL BE REQUIRED TO REMOVE AND REPLACE ANY PLANT MATERIAL, BARK, ETC INSTALLED PRIOR TO











# Lumière

#### DESCRIPTION

The Aspen 1900-OA bollard features a sleek, contemporary aesthetic and low glare fixed optics. Lamp source selections include LED, incandescent PAR lamps or low voltage MR16 halogen lamps. Luminaires with a halogen source are available with an integral or remote 12V transformer option. Our patented LumaLevel™ leveling system provides quick installation, easy adjustment, secure mounting and protection from vibration. Aspen bollards are available in two standard heights of 24" [610mm] and 30" [762mm].

Catalog #	Туре
Project	
Comments	Date
Prepared by	

#### **SPECIFICATION FEATURES**

#### Material

Mounting base and housing are precision-machined from corrosion-resistant 6061-T6 aluminum billet and extrusion.

#### **Finish**

Fixture and mounting base are double protected by a RoHS compliant chemical film undercoating and polyester powdercoat paint finish, surpassing the rigorous demands of the outdoor environment. Fixture housing is available in a variety of standard colors. Mounting base is painted black.

#### Lens

Lens is machined from solid U.V. stabilized clear acrylic and is designed to produce maximum

3-1/2"
[89mm]

24" [610mm]
or
30" [762mm]
(specify)

light output with low brightness.

#### Adjustable Mounting Base

Machined 6061-T6 aluminum mounting base assembly is equipped with the patented LumaLevel™ leveling system that includes mounting chassis, 70 shore neoprene base pad, stainless steel hardware and 3/4" conduit entry. The LumaLevel™ leveling system provides quick installation, easy adjustment, secure mounting and protection from vibration.

#### **Anchor Bolts & Template**

Three (3) 3/8" x 12" galvanized anchor bolts and a galvanized steel anchor bolt template are standard. Anchor bolts and template are available to ship in advance of fixture for roughin purposes (specify option -LAB and order anchor bolts/template kit separately).

#### Hardware

Stainless steel hardware is standard to provide maximum corrosion-resistance.

#### Socket

PAR20: Ceramic socket with 250° CTeflon® coated lead wires and medium base. 50MR16: Ceramic socket with 250° CTeflon® coated lead wires and GU5.3 bi-pin base.

#### Electrical

20LED: 120-277VAC, 50/60Hz, rated for -40°C to + 40°C [-40°F to 104°F] operation temperature. 50MR16: 12V transformer required (not included). Remote transformer is available from Lumière as an accessory - see the Accessories & Technical Data section of this catalog for details. 50MR16: XXX/12V includes integral electronic transformer - must specify voltage.

#### ΙFΓ

LED light engine with integrated driver. Includes four (4) field-adjustable, pushbutton activated light level selections: 100%, 80%, 55%, or 18%. Available in 2700K, 3000K, 3500K and 4000K color temperatures at 80 CRI. Dimming: 120V Phase dimming at highest (100%) light level. 120-277V universal 0-10V diming available at 100%, 80% and 55% light levels.

#### Lamp

Halogen or Incandescent lamp options available. Lamps not included. Soraa lamp compatible.

#### Warranty

Lumière warrants its fixtures against defects in materials & workmanship for three (3) years for halogen and incadescent or five (5) years for LED. Auxiliary equipment such as transformers, ballasts and lamps carry the original manufacturer's warranty.



# **ASPEN**

1900-OA LED Halogen Incandescent

APPLICATIONS: OPEN APERTURE BOLLARD ACCENT MARKER



#### CERTIFICATION DATA

UL and cUL Wet Location Listed LM79 / LM80 Compliant ROHS Compliant IP66 Ingressed Protection Rated

#### TECHNICAL DATA

20W LED, L70/60,000 hours 40°C Maximum Temperature Rating 50W (max.) MR16

Halogen | Low Voltage | Line Voltage 50W (max.) PAR20 Incandescent | Line Voltage

#### ORDERING INFORMATION

Sample Number: 1900-OA-24-50MR16-120/12-BZ-LAB

Series	Height	Source	Voltage	Finish	Options
1900-OA=Aspen Bollard	<b>24</b> =24" Nominal	LED	LED	<u>Painted</u>	LAB=Less Anchor Bolts &
Open Aperture	Height	20LED2715=20W LED, 2700K, 80CRI	UNV =120-277V (50-60Hz)	BK=Black	Template (Requires Anchor
	<b>30</b> =30" Nominal	20LED3015=20W LED, 3000K, 80CRI	Halogen (12V remote transformer)	BZ=Bronze	Kit Be Ordered Separately)
	Height	20LED3515=20W LED, 3500K, 80CRI	12=12V Fixture (Remote Transformer Required -	CS=City Silver	
		20LED4015=20W LED, 4000K, 80CRI	Order Separately)	<b>VE</b> =Verde	
		<u>Halogen</u>	Halogen (integral transformer)	WT=White	
		50MR16=50W Max Halogen MR16, GU5.3	120/12=120V to 12V Integral Transformer		
		Base	277/12=277V to 12V Integral Transformer		
		Incandescent	Incandescent		
		50PAR20=50W Max Halogen PAR20,	<b>120</b> =120V		
		Medium Base			



#### **ACCESSORIES**

#### **Anchor Bolts & Templates**

7048PK= Anchor Bolt/Template Kit for 24" & 30" Aspen Bollards

#### **PHOTOMETRY**

#### **LUMENS - CRI/CCT TABLE**

CCT (K) / Color	CRI Minimum [Typical]	Light Level	Nominal Watts @ 120V [277V]	Delivered Lumens	lm/W
		100%	16.9 [19.6]	237	14.0
4000	80 [83]	80%	12.8 [14.6]	195	15.5
4000	R9	55%	8.6 [10.1]	142	16.5
		18%	3.8 [4.4]	57	15.0

All specifications subject to tolerance of +/- 10%

## **CCT MULTIPLIER TABLE**


CCT(K) / COLOR	MULTIPLIER
2700K	0.922
3000K	0.953
3500K	0.992
4000K	1.000

Note: Multiplier can be used to calculate Lumens and footcandle (FC) values.

#### **LUMEN MAINTENANCE**


Ambient Temperature	TM-21 Lumen Maintenance (72,000 Hours)	TM-21 Reported L70(10k) (Hours)
25°C	> 85%	> 60.000
40°C	> 85%	> 60,000

#### ISO-FOOTCANDLE PLOTS - 24" MOUNTING HEIGHT




FILE NAME: 1900-OA-24-20LED4015-UNV-BK.ies LAMP: LED MODULE -TLM-R20A-A124015, 4000K LUMENS: 1280 (module lumens)

WATTS: 15.7 TEST NO: P189461



FILE NAME: 1900-OA-24-50PAR20-120-BK.ies LAMP: INCANDESCENT 50W PAR20 - 10° LUMENS: 530 WATTS: 50 TEST NO: P189462



FILE NAME: 1900-OA-24-50MR16.ies LAMP: HALOGEN 50W MR16 - 10° LUMENS: 950 WATTS: 50 TEST NO: ITL52169

#### **TECHNICAL NOTES AND FORMULAS**

- Beam diameter is to 50% of maximum footcandles, rounded to the nearest half-foot.
- Footcandle values are initial. Apply appropriate light loss factors where necessary.
- The fixture body must be removed from the base to adjusting light level or relamp. Do not try to remove top cap or optical lens.

Specifications and dimensions subject to

change without notice.

Type S5

The geometric form of MESA LED luminaire allows it to adapt to either contemporary or traditional architectural settings. Available in single or twin pole mount configurations with optional wall mounting capability, the MESA LED luminaire's mounting options allow for harmonized site design whether at the entryway or in the parking lot. UL/cUL listed for use in wet locations.

Catalog #	Туре
Project	
Comments	Date
Prepared by	

#### **SPECIFICATION FEATURES**

#### Construction

HOUSING: Die-cast aluminum main housing and spider mount base maintain a minimum 0.125 wall thickness. Integral aluminum heat sink provides superior thermal heat transfer in +40°C ambient environments. DOOR ASSEMBLY: Top mounted, heavy wall, diecast aluminum door maintains a nominal 0.125 thickness. Door includes a self-retaining interior hinge. GASKET: Continuous silicone gasket provided to seal housing door assembly and optic tray. LENS: Downlight lens is LED board integrated acrylic overoptics, each individually sealed for IP66 rating. HARDWARE: Four iinset fasteners on underside of housing provide access to luminaire interior. Concealed, stainless steel four bar hinge lock allows door to lock in the open position.

#### Optics

Choice of twelve patented, highefficiency AccuLED Optic™
technology manufactured from
injection-molded acrylic. Optics
are precisely designed to shape
the light output, maximizing
efficiency and application spacing.
AccuLED Optic technology, creates
consistent distributions with the

scalability to meet customized application requirements. Offered Standard in 4000K (+/- 275K) CCT and minimum 70 CRI. Optional 3000K CCT, 5000K CCT and 5700K CCT. For the ultimate level of spill light control, an optional houseside shield accessory can be field or factory installed. The house-side shield is designed to seamlessly integrate with the SL2, SL3 or SL4 optics. LightBAR optic tray is removable and able to rotate 360° in 90° increments for specific placement of the distribution relative to fixture.

#### **Electrical**

LED drivers mount to die-cast aluminum back housing for optimal heat sinking, operation efficacy, and prolonged life. Standard drivers feature electronic universal voltage (120-277V 50/60Hz), 347V 60Hz or 480V 60Hz operation, greater than 0.9 power factor, less that 20% harmonic distortion, and is suitable for operation in -40°C to 40°C ambient environments. All fixtures are shipped standard with 10kV/10kA common and differential - mode surge protection. LightBARs feature and IP66 enclosure rating and maintain greater than 95% lumen maintenance at 60,000 hours per

IESNA TM-21. Occupancy sensor and dimming options available.

#### Mounting

Fitter assembly mounts over 3" O.D. tenon and is secured via three concealed stainless steel set screws. Design of fitter provides seamless transition to 4" round poles. Additional mounting accessories include a dual fixture post top mounting arm and wall mount arm.

#### Finish

Housing is finished in five-stage super TGIC polyester powder coat paint, 2.5 mil nominal thickness for superior protection against fade and wear. LightBAR™ cover plates are standard white and may be specified to match finish of luminaire housing. Standard colors include black, bronze, grey, white, dark platinum and graphite metallic. RAL and custom color matches available. Consult Outdoor Architectural Colors brochure for a complete selection.

#### Warranty

Five-year warranty.




# **MSA** MESA LED


1-6 LightBARs Solid State LED

**DECORATIVE LUMINAIRE** 


#### **DIMENSIONS**



#### MOUNTING ACCESSORIES



#### **DUAL MOUNT ARM** (EPA 1.36)



#### CERTIFICATION DATA

UL/cUL Listed ISO 9001 IP66 LightBARs LM79 / LM80 Compliant 2G Vibration Tested

# ENERGY DATA

>0.9 Power Factor <20% Total Harmonic D

<20% Total Harmonic Distortion 120-277V/50 & 60Hz, 347V/60Hz, 480V/60Hz -40°C Minimum Temperature 40°C Ambient Temperature Rating

#### FΡΔ

**Effective Projected Area: (**Sq. Ft.) Single Mount 1.1

# SHIPPING DATA Approximate Net Weight:

50 lbs. (22.7 kgs.)




#### POWER AND LUMENS BY BAR COUNT (21 LED LIGHTBARS)

Number of LightBARs		E01	E02	E03	E04	E05	E06	
Drive Current 350mA Drive Current								
Power (Wa	tts)	25W	52W	75W	5W 97W 127W		150W	
Current @	120V (A)	0.22	0.44	0.63	0.82 1.07		1.26	
Current @	<b>277V</b> (A)	0.10	0.20	0.28	0.36	0.48	0.56	
Power (Wa	tts)	31W	58W	82W	99W	132W	159W	
Current @	<b>347V</b> (A)	0.11	0.19	0.28	0.29	0.39	0.48	
Current @	<b>480V</b> (A)	0.09	0.15	0.20	0.21	0.30	0.36	
T2	Lumens	2,460	4,920	7,379	9,839	12,299	14,759	
12	BUG Rating	B1-U0-G1	B2-U0-G2	B2-U0-G2	B3-U0-G3	B3-U0-G3	B3-U0-G3	
Т3	Lumens	2,485	4,970	7,456	9,941	12,426	14,911	
13	BUG Rating	B1-U0-G1	B2-U0-G2	B2-U0-G2	B3-U0-G3	B3-U0-G3	B3-U0-G3	
Т4	Lumens	2,423	4,845	7,268	9,690	12,113	14,535	
T4	BUG Rating	B1-U0-G1	B1-U0-G2	B1-U0-G2	B2-U0-G2	B2-U0-G3	B2-U0-G3	
ENIO	Lumens	2,615	5,230	7,844	10,459	13,074	15,689	
5MQ	BUG Rating	B2-U0-G1	B3-U0-G1	B3-U0-G1	B3-U0-G2	B4-U0-G2	B4-U0-G2	
5WQ	Lumens	2,604	5,207	7,811	10,415	13,018	15,622	
SWG	BUG Rating	B2-U0-G1	B3-U0-G1	B3-U0-G2	B4-U0-G2	B4-U0-G2	B4-U0-G2	
5XQ	Lumens	2,603	5,206	7,809	10,412	13,015	15,618	
570	BUG Rating	B2-U0-G1	B3-U0-G2	B3-U0-G2	B4-U0-G3	B4-U0-G3	B4-U0-G3	
SL2	Lumens	2,445	4,891	7,336	9,781	12,226	14,672	
SLZ	BUG Rating	B1-U0-G1	B1-U0-G1	B2-U0-G2	B2-U0-G2	B2-U0-G2	B3-U0-G3	
SL3	Lumens	2,461	4,921	7,382	9,842	12,303	14,763	
SL3	BUG Rating	B1-U0-G1	B1-U0-G2	B2-U0-G2	B2-U0-G2	B2-U0-G2	B3-U0-G3	
SL4	Lumens	2,376	4,752	7,128	9,504	11,880	14,256	
3L4	BUG Rating	B1-U0-G1	B1-U0-G2	B1-U0-G2	B2-U0-G2	B2-U0-G3	B2-U0-G3	
RW	Lumens	2,398	4,796	7,194	9,591	11,989	14,387	
n#V	BUG Rating	B1-U0-G1	B2-U0-G2	B3-U0-G3	B3-U0-G3	B3-U0-G3	B4-U0-G4	
SLL/SLR	Lumens	2,227	4,453	6,680	8,906	11,133	13,360	
SLL/SLK	BUG Rating	B1-U1-G1	B1-U1-G2	B1-U1-G3	B1-U1-G3	B2-U2-G3	B2-U2-G4	

#### LUMEN MAINTENANCE

Ambient Temperature	25,000 Hours*	50,000 Hours*	60,000 Hours*	100,000 Hours	Theoretical L70 (Hours)
25°C	> 99%	> 97%	> 96%	> 93%	> 450,000
40°C	> 98%	> 97%	> 96%	> 92%	> 425,000
50°C	> 97%	> 96%	> 95%	> 91%	> 400,000

<sup>\*</sup> Per IESNA TM-21 data.



#### LUMEN MULTIPLIER

Ambient Temperature	Lumen Multiplier
10°C	1.02
15°C	1.01
25°C	1.00
40°C	0.99
50°C	0.96




## POWER AND LUMENS BY BAR COUNT (7 LED LIGHTBARS)

Number of	LightBARs	F01	F02	F03	F04	F05	F06	
Drive Current 1A Drive Current								
Power (Wa	tts)	26W	55W	78W	102W	133W	157W	
Current @	120V (A)	0.22	0.46	0.66	0.86	0.86 1.12		
Current @ 2	277V (A)	0.10	0.21	0.29	0.37	0.50	0.58	
Power (Wa	tts)	32W	60W	85W	105W	137W	164W	
Current @ 3	<b>347V</b> (A)	0.11	0.19	0.28	0.30	0.41	0.49	
Current @	480V (A)	0.09	0.15	0.21	0.22	0.31	0.37	
T2	Lumens	2,031	4,061	6,092	8,122	10,153	12,184	
12	BUG Rating	B1-U0-G1	B1-U0-G1	B2-U0-G2	B2-U0-G2	B3-U0-G3	B3-U0-G3	
ТЗ	Lumens	2,052	4,103	6,155	8,206	10,258	12,310	
13	BUG Rating	B1-U0-G1	B2-U0-G2	B2-U0-G2	B3-U0-G3	B3-U0-G3	B3-U0-G3	
T4	Lumens	2,000	4,000	6,000	7,999	9,999	11,999	
14	BUG Rating	B1-U0-G1	B1-U0-G1	B1-U0-G2	B1-U0-G2	B2-U0-G2	B2-U0-G3	
5MQ	Lumens	2,159	4,317	6,476	8,634	10,793	12,951	
	BUG Rating	B1-U0-G1	B2-U0-G1	B3-U0-G1	B3-U0-G2	B3-U0-G2	B4-U0-G2	
5WQ	Lumens	2,149	4,299	6,448	8,597	10,747	12,896	
2000	BUG Rating	B2-U0-G1	B3-U0-G1	B3-U0-G2	B3-U0-G2	B4-U0-G2	B4-U0-G2	
5XQ	Lumens	2,149	4,298	6,446	8,595	10,744	12,893	
27.0	BUG Rating	B2-U0-G1	B3-U0-G2	B3-U0-G2	B3-U0-G3	B4-U0-G3	B4-U0-G3	
01.0	Lumens	2,019	4,037	6,056	8,075	10,093	12,112	
SL2	BUG Rating	B1-U0-G1	B1-U0-G1	B1-U0-G2	B2-U0-G2	B2-U0-G2	B2-U0-G2	
01.0	Lumens	2,031	4,062	6,094	8,125	10,156	12,187	
SL3	BUG Rating	B1-U0-G1	B1-U0-G1	B1-U0-G2	B2-U0-G2	B2-U0-G2	B2-U0-G2	
SL4	Lumens	1,961	3,923	5,884	7,846	9,807	11,769	
JL4	BUG Rating	B1-U0-G1	B1-U0-G1	B1-U0-G2	B1-U0-G2	B2-U0-G2	B2-U0-G3	
RW	Lumens	1,980	3,959	5,939	7,918	9,898	11,877	
n∜V	BUG Rating	B1-U0-G1	B2-U0-G2	B3-U0-G3	B3-U0-G3	B3-U0-G3	B3-U0-G3	
SLL/SLR	Lumens	1,838	3,676	5,514	7,352	9,191	11,029	
OLL/OLK	BUG Rating	B0-U1-G1	B1-U1-G2	B1-U1-G2	B1-U1-G3	B1-U1-G3	B2-U2-G3	

#### LUMEN MAINTENANCE

Ambient Temperature	25,000 Hours*	50,000 Hours*	60,000 Hours*	100,000 Hours	Theoretical L70 (Hours)
25°C	> 99%	> 97%	> 96%	> 93%	> 450,000
40°C	> 98%	> 97%	> 96%	> 92%	> 425,000
50°C	> 97%	> 96%	> 95%	> 91%	> 400,000

<sup>\*</sup> Per IESNA TM-21 data.



#### LUMEN MULTIPLIER

Ambient Temperature	Lumen Multiplier
10°C	1.02
15°C	1.01
25°C	1.00
40°C	0.99
50°C	0.96



Specifications and dimensions subject to change without notice.

#### ORDERING INFORMATION


Sample Number: MSA-E06-LED-E1-T3-GM

Product Family	Number of LightBARs <sup>1,2</sup>	Lamp Type	Voltage	Distribution	Color <sup>5</sup>			
MSA=Mesa	E01=(1) 21 LED LightBAR <sup>3</sup> E02=(2) 21 LED LightBARs E03=(3) 21 LED LightBARs E04=(4) 21 LED LightBARs E05=(5) 21 LED LightBARs E06=(6) 21 LED LightBARs F01=(1) 7 LED LightBARs F02=(2) 7 LED LightBARs F03=(3) 7 LED LightBARs F04=(4) 7 LED LightBARs F05=(5) 7 LED LightBARs F05=(5) 7 LED LightBARs F06=(6) 7 LED LightBARs	LED=Solid State Light Emitting Diodes	E1=Electronic (120-277V) 347=347V 480=480V 4	T2=Type II T3=Type III T4=Type IV S12=Type II w/Spill Control SL3=Type II w/Spill Control SL4=Type IV w/Spill Control RW=Rectangular Wide 5MQ=Type V Square Medium 5WQ=Type V Square Wide 5XQ=Type V Square Wide SLL=90° Spill Light Eliminator Left SLR=90° Spill Light Eliminator Right	AP=Grey BZ=Bronze BK=Black DP=Dark Platinum GM=Graphite Metallic WH=White			
Options (Add as S	uffix)			Accessories (Order Separately) 11				
R=NEMA Twistloc 2L=Two Circuits of LCF=LightBAR Coo 7030=70 CRI / 3000 7050=70 CRI / 5000 7060=70 CRI / 5700 8030=80 CRI / 3000 ICB=Integral Cold of DIMRF-LW=LumaN	OK CCT <sup>7</sup>	20 or 277V) * s for 8' - 16' Mounting He	VA6028-XX=Dual Mount Arm (EPA 1.38) VA6029-XX=Wall Mount Arm OA/RA1016-NEMA Photocontrol - Multi-Tap OA/RA1027-NEMA Photocontrol - 480V OA/RA1201=NEMA Photocontrol - 347V MA1253=10kV Circuit Module Replacement LB/HSS-21=Field Installed House Side Shield LB/HSS-07=Field Installed House Side Shield	l for "E" LightBARs <sup>10, 12</sup>				

- Standard 4000K CCT and nominal 70 CRI.

- 1. Standard 4000K CCT and nominal 70 CRI.
  2. 21 LED LightBAR powered at 350mA, 7 LED LightBAR powered at 1A.
  3. Streetside orientation 90° to LightBAR.
  4. Only for use with 480V Wye systems. Per NEC, not for use with ungrounded systems, impedance grounded systems or corner grounded systems (commonly known as Three Phase Three Wire Delta, Three Phase High Leg Delta and Three Phase Corner Grounded Delta systems).
  5. Cutsom and RAL color matching available upon request. Consult your lighting representative at Eaton for more information.
  6. Low-level output varies by bar count. Consult factory. Not available with 3470 or 480V. Requires quantity two or more LightBARs.
  7. Consult factory for lead times and lumen multiplier.
  8. Available with E01-E04 or F01-F04 configurations only. Specify 120V or 277V. LED cold weather integral battery pack is rated for minimum operating temperature -40°F (-20°C). Operates one LightBAR for 90-minutes. Not available in all configuration, consult factory, Rated for use in 25°C ambient.
  9. LumaWatt wireless sensors are factory installed and require network components RF-EM-1, RF-GW-1 and RF-ROUT-1 in appropriate quantities. See www.eaton.com/lighting for LumaWatt application information.
  10. Only for use with SL2, SL3 and SL4 distributions.
  11. Replace XX with color designation.
  12. One required for each LightBAR.





#### **LAMPING**

- o (1x) 10.1w LED Array
- o 3000k, 350mA
- o Initial Lumens: 1460 lm
- o Delivered Lumens: 684 Im
- o CRI >80
- o Color Consistency: 3 Step MacAdams Ellipse

#### **DRIVER** (Dimmable)

o (1x) 0-10v & Reverse Phase Dimming Constant Current, 12w, 350mA

#### **METAL FINISHES**

(All finishes polyester powdercoat)

- o 22 Oiled Bronze
- o 24 Satin Nickel

#### **DIFFUSER**

o 2 - Matte White Acrylic

#### **INPUT VOLTAGE**

o 120v OR 277v 50/60Hz

#### **DIMENSIONS**

o 7.25" (w) x 16.50" (h) 4.75" (ext.)

#### **SPECIAL NOTE**

o Add caulking around fixture base at the wall to prevent water from entering fixture.

- o 4" Octagonal J-Box
- o ETL WET Listed (installer must provide a bead of caulk between fixture housing and mounting surface)
- o Wall mount
- o Conforms to UL STD 1598
- o Certified CAN/CSA STD C22.2 No. 250.0

# **Sample Catalog Number**



Series # Diffuser Finish **Catalog Number** 3-712 2 3-712-224



**OXYGEN LIGHTING** 201 RAILHEAD RD, FORT WORTH, TX 76106 TEL (877) 607-0202 FAX (877) 607-0203 www.oxygenLighting.com

PROJECT: 19-1425 D 64 of 73








PROJECT

TYPE

# KHA SLIM 8'2"







# KHA SLIM 8'2" CFL

Wet location




Double reflector optical system for downward light distribution below horizontal and zero upward light pollution. High efficiency comfortable glare free light is provided through indirect light distribution and the upper facetted reflector. The high performance reflector system is designed to provide an efficient light distribution based on height and area to be illuminated.

-lmax 2 x 80°.

- -"Body and top manufactured in AISI 316 stainless steel for marine applications, or extruded
- -aluminium finished polyester painted Iron grey or Textured black.
- -UV stabilised high-tech technopolymer impact resistant lamp cover (PC-HT).
- -Reflector in high purity aluminium provides comfortable low glare light control and avoids back reflection onto lamp for improved longevity.
- -Technopolymer control gear housing.
  -Complete with PA66 IP68 plug for fast easy electrical connection, suitable for 3 x 2,5 mm2 cable ø 9-14 mm.
- -Electronic control gear for 120-277 V, 50/60 Hz supply.
- -Anti-ageing silicone gaskets.
- -Stainless steel external screws."



**TEXTURED BLACK** 



STAINLESS STEEL

SOCKET	POWER (W)	FINISH	IP	KELVIN	OPTIC TYPE	OPTIC BEAM	DELIVERED LUMENS (RLO)	LIFETIME	CULUS	UL	VOLTAGE	CODE
COMPAC	T FLUORESCEN	T 120 V										
2G11	1x24/55 W	IRON GRAY	IP 66	-	C/EW	-	-	-			-	076338
2G11	1x24/55 W	STAINLESS STEEL	IP 66	-	C/EW	-	-	-	•		-	076340
2G11	1x24/55 W	TEXTURED BLACK	IP 66	-	C/EW	-	-	-			-	076406
COMPAC	T FLUORESCEN	T 277 V										
2G11	1x24/55 W	IRON GRAY	IP 66	-	C/EW	-	-	-	•		-	076342
2G11	1x24/55 W	STAINLESS STEEL	IP 66	-	C/EW	-	-	-			-	076344
2G11	1x24/55 W	TEXTURED BLACK	IP 66	-	C/EW	-	-	-			-	076408

# KHA SLIM 8'2" LED





Body and top manufactured in AISI 316 stainless steel for marine applications, or extruded aluminium finished polyester painted Iron grey or Textured black. -Double reflector optical system for downward light distribution below horizontal and zero upward light pollution. High efficiency comfortable glare free light is provided through indirect light distribution and the upper facetted reflector. The high performance reflector system is designed to provide an efficient light distribution based on height and area to be illuminated.

-lmax 2 x 80°.

- -Integral driver and available in 3000, 4000 or 5000 degrees kelvin. -UV stabilised high-tech technopolymer impact resistant lamp cover (PC-HT).
- -Reflector in high purity aluminium provides comfortable low glare light control and avoids back reflection onto lamp for improved longevity.
- -Technopolymer control gear housing. -Complete with PA66 IP68 plug for fast easy electrical connection, suitable for 3 x 2,5 mm2 cable ø 9-14 mm.
- -Electronic control gear for 120-277 V, 50/60 Hz supply.
- -Anti-ageing silicone gaskets.
- -Stainless steel external screws.



TEXTURED BLACK



STAINLESS STEEL

SOCKET	POWER (W)	FINISH	IP	KELVIN	OPTIC TYPE	OPTIC BEAM	DELIVERED LUMENS (RLO)	LIFETIME	CULUS	UL	VOLTAGE	CODE
HIGH PO	OWER LEDS 120	)/277 V										
LED	57 W	IRON GRAY	IP 66	3000	C/EW	-	2290 lm	-			Υ	076434
LED	57 W	IRON GRAY	IP 66	4000	C/EW	-	2595 lm	-			Υ	076437
LED	57 W	STAINLESS STEEL	IP 66	3000	C/EW	-	2290 lm	-			Υ	076435
LED	57 W	STAINLESS STEEL	IP 66	4000	C/EW	-	2595 lm	-			Υ	076438
LED	57 W	TEXTURED BLACK	IP 66	3000	C/EW	-	2290 lm	-			Υ	076433
LED	57 W	TEXTURED BLACK	IP 66	4000	C/EW	-	2595 lm	-			Υ	076436

KHA SLIM 8'2"

# **OPTIONAL ACCESSORIES**

DESCRIPTION	FINISH	CODE
KHA SLIM 8'2"		
A0372 Anchor rods for in-ground concrete mounting		
stainless steel plate with galvanised steel rods (TYCO11		
SLIM/FL only).	-	14071320



14071320

# l Springs - El Dorado Fire Protection District

Street Diamond Springs, CA 95619 ~ (530) 626-3190 Fax (530) 626-3188 www.diamondfire.org

# **Project Planning Comments Letter**

Date: 5/4/2017

Evan Mattes
El Dorado County Planning Department
2850 Fair Lane
Placerville, CA 95667

Re: 6035 Service Drive, Diamond Springs, CA

APN: 051-461-59-100

PD17-0002

Dear Mr. Mattes.

The Diamond Springs El Dorado Fire Protection District has reviewed the above referenced project and submits the following comments regarding the ability to provide this site with fire and emergency medical services consistent with the El Dorado County General Plan, State Fire Safe Regulations, as adopted by El Dorado County and the California Fire Code as amended locally. The fire department reserves the right to update the following comments to comply with all current Codes, Standards, Local Ordinances, and Laws in respect to the official documented time of project application and/or building application to the County. Any omissions and/or errors in respect to this letter, as it relates to the aforementioned codes, regulations and plans, shall not be valid, and does not constitute a waiver to the responsible party of the project from complying as required with all Codes, Standards, Local Ordinances, and Laws.

1.1.3 Scope: "The provisions of this code shall apply to the construction, alteration, movement, enlargement, replacement, repair, equipment, use and occupancy, location, maintenance, removal and demolition of every building or structure or any appurtenances connected or attached to such building structures throughout California".

Appendix "B" sets for the fire flow for new construction and Appendix "C" sets for the requirements of fire hydrants.

There are 4 types of structures presented in the submitted plans. These are reflected as Type A, B, C and D. The potable water system with the purpose of fire protection for this multifamily residential development shall provide a minimum fire flow per building as listed below:

## Building Type A = 4312 ft<sup>2</sup> (1-bedroom apartment building)

1500 gallons per minute with a minimum residual pressure of 20 psi for a two-hour duration. This requirement is based on a structure up to 11,300 square feet in size, Type V-B construction.

## Building Type B = 5396 ft<sup>2</sup> (2 bedroom apartment building)

1500 gallons per minute with a minimum residual pressure of 20 psi for a two-hour duration. This requirement is based on a structure up to 11,300square feet in size, Type V-B construction.

#### Building Type C = 6724 ft<sup>2</sup> (3 bedroom apartment building)

1500 gallons per minute with a minimum residual pressure of 20 psi for a two-hour duration. This requirement is based on a structure up to 11,300 square feet in size, Type V-B construction.

#### Building Type D = 4804 ft<sup>2</sup> Community building / common areas / manager residence

1500 gallons per minute with a minimum residual pressure of 20 psi for a two-hour duration. This requirement is based on a structure up to 11,300 square feet in size, Type V-B construction.

- 1. <u>Hydrants:</u> This development shall install Dry Barrel Fire Hydrants which conform to El Dorado Irrigation District specifications for the purpose of providing water for fire protection. The spacing between hydrants in this development shall not exceed 300 feet. The exact location of each hydrant on private roads and on main county maintained roadways shall be determined by the Fire Department.
- 2. <u>Hydrant Visibility:</u> In order to enhance nighttime visibility, each hydrant shall be painted with safety Red enamel and marked in the roadway with a blue reflective marker as specified by the Fire Department and State Fire Safe Regulations
- 3. <u>Fire Flow:</u> The potable water system with the purpose of fire protection for this residential / commercial development shall provide a <u>minimum fire flow of 1,500 gallons per minute</u> with a minimum residual pressure of 20 psi for a three-hour duration. This requirement is based on a commercial building 11,300 square feet or less in size, Type V-B construction. This fire flow rate shall be in excess of the maximum daily consumption rate for this development. A set of engineering calculations reflecting the fire flow capabilities of this system shall be supplied to the Fire Department for review and approval.
- 4. <u>Underground Private Fire Mains:</u> After installation, all rods, nuts, bolts, washers, clamps, and other underground connections and restraints used for underground fire main piping and water supplies, except thrust blocks, shall be cleaned and thoroughly coated with a bituminous or other acceptable corrosion retarding material. All private fire service mains shall be installed per NFPA 24, and shall be inspected, tested and maintained per NFPA 25.
- 5. **Sprinklers:** All structures shall install fire sprinklers in accordance with NFPA 13 and Fire Department requirements. This fire flow rate shall be in excess of the maximum daily consumption rate for this development. A set of engineering calculations reflecting the fire flow capabilities of this system shall be supplied to the Fire Department for review and approval.
- 6. <u>Fire Department Access</u>: Approved fire apparatus access roads and driveways shall be provided for every facility, building, or portion of a building. The fire apparatus access roads and driveways shall comply with the requirements of Section 503 of Diamond Springs El Dorado Fire Protection District as well as State Fire Safe Regulations as stated below (but not limited to):
  - a. All One- or Two-family dwelling residential developments, and residential projects with over 100 dwelling units, shall be provided with separate and approved fire apparatus access roads and shall meet the requirements for Remoteness, when required by the Fire Code Official.
  - b. All roadways shall be a minimum of 20 feet wide, providing two ten (10) foot traffic lanes, not including shoulder and striping.
  - c. Each dead-end road shall have a turnaround constructed at its terminus.
  - d. Where parcels are zoned 5 acres or larger, turnarounds shall be provided at a maximum of 1320 foot intervals.
  - e. Where maximum dead-end road lengths are exceeded, there shall be a minimum of two access roadways allowing for the safe access of emergency apparatus and civilian evacuation concurrently.
  - f. The fire apparatus access roads and driveways shall extend to within 150 feet of all portions of each facility and all portions of the exterior of the first story of the building as measured by an approved route around the exterior of the building or facility.
  - g. Driveways and roadways shall have unobstructed vertical clearance of 15' and a horizontal clearance providing a minimum 2' on each side of the required driveway or roadway width.

- h. Depending on final heights of each building, the final layout of fire apparatus access roads shall be determined and approved by the fire code official with consideration of whether a ladder truck or ground ladders would be used for firefighting operations.
- 7. **Roadway Surface:** Roadways shall be designed to support the imposed load of fire apparatus weighing at least 75,000 pounds and provide all-weather driving conditions. All-weather surfaces shall be asphalt, concrete or other approved driving surface. Project proponent shall provide engineering specifications to support design, if request by the local AHJ.
- 8. **Roadway Grades:** The grade for all roads, streets, private lanes and driveways shall not exceed 16%. If paved or concrete, grades may be allowed up to 20%.
- 9. <u>Traffic Calming:</u> This development shall be prohibited from installing any type of traffic calming device that utilizes a raised bump/dip section of roadway. All other proposed traffic calming devices shall require approval by the fire code official.
- 10. <u>Turning Radius:</u> The required turning radius of a fire apparatus access road/driveway shall be determined by the fire code official. Current requirements are 40' inside and 56' outside.
- 11. <u>Gates:</u> All gates shall meet the El Dorado County Gate Standard "AUTOMATIC GATES ON FIRE ACCESS ROADWAYS" STANDARD #B-002 EFFECTIVE 03-23-2009
- 12. <u>Fire Access During Construction</u>: In order to provide this development with adequate fire and emergency medical response during construction, all access roadways and fire hydrant systems shall be installed and in service prior to combustibles being brought onto the site as specified by the Fire Department, Standard B-003. A secondary means of egress shall be provided prior to any construction or the project can be phased.
- 13. <u>Fire Service Components:</u> Any Fire Department Connection (FDC) to the sprinkler system and all Fire Hydrant(s) outlets shall be positioned so as not to be obstructed by a parked vehicle.
- 14. <u>Wildland Fire Safe Plan:</u> This development shall be conditioned to develop, implement, and maintain a Wildland Fire Safe Plan that is approved by the Fire Department as complying with the State Fire Safe Regulations, prior to approval of the Tentative Map.
- 15. Fencing: Lots that back up to wildland open space shall be required to use non-combustible type fencing.
- 16. Knox Box and Keys: All Commercial or Public occupied buildings shall install a Knox Box and building keys including, but not limited to, main entry doors, utility closets, roof accesses, alarm panels, fire sprinkler locks and all other keys required by the fire code official for emergency access. It is recommended, but not required, that residential buildings also add a Knox box and main front door key for improved emergency access.
- 17. Parking and Fire Lanes: All parking restrictions as stated in the current California Fire Code and the current Diamond Springs El Dorado Fire Protection District Ordinance shall be in effect. All streets with parking restrictions will be signed and marked with red curbs as described in the El Dorado County Regional Fire Protection Standard titled "No Parking-Fire Lane". All curbs in the parking lot(s) that are not designated as parking spaces will be painted red and marked every 25 feet "No Parking Fire Lane." This shall be white letters on a red background. There shall be a designated plan page that shows all Fire Lanes as required by the El Dorado County Regional Fire Protection Standard B-004 "No Parking-Fire Lane" and the fire code official.
  - a. Section 503.4.3 of the Fire Code of the Diamond Springs-El Dorado Fire Protection District is added to read as follows:
    - i. 503.4.3 Roads from 20 to 29 feet in width. Fire apparatus access roads, 20 to 29 feet wide, shall be posted on both sides as a fire lane, with no parking allowed on each of the follows.

- b. Section 503.4.4 of the Fire Code of the Diamond Springs-El Dorado Fire Protection District is added to read as follows:
  - 503.4.4 Roads from 30 to 35 feet in width. Fire apparatus access roads, 30 to 35 feet wide, shall be posted on one side as No Parking, Fire Lane, with parking allowed only on the opposite side of the roadway.
- c. Section 503.4.5 of the Fire Code of the Diamond Springs-El Dorado Fire Protection District is added to read as follows:
  - i. 503.4.5 Roads 36 feet and greater in width. Fire apparatus access roads, 36 feet and greater in width, may allow parking on both sides of the roadway.
- 18. **Setbacks:** Any parcels greater than one acre shall conform to State Fire Safe Regulations requirements for setbacks (minimum 30' setback for buildings and accessory buildings from all property lines).
- 19. <u>Vegetative Fire Clearances:</u> Prior to June 1<sup>st</sup> each year, there shall be vegetation clearance around all EVA's (Emergency Vehicle Access), buildings, up to the property line as stated in Public Resources Code Section 4291, Title 19 as referenced in the CA Fire Code, and the conditioned Wildland Fire Safe Plan.
- 20. <u>Trail Systems and Land-Locked Access</u>: If this project decides on designing a trail-type system or contains/abuts to land-locked open space, the project shall be conditioned to provide emergency vehicle access (EVA) points as required by the fire code official. Gates may be installed and locked with a low priority KNOX lock. The street curbs adjacent to the trail access point shall be painted red. All trails and multi-use paths need to be constructed so as to ensure a minimum of a 10' drivable width <u>and</u> 14' minimum vegetation clearance (the wildfire safe plan will likely require additional clearance on these paths). The purpose of this requirement is to allow access for ambulances and smaller fire apparatus in case of emergency.
- 21. **Knox Key Shunt:** A Knox Key Shunt system shall be installed to terminate power to all back-up power generators.
- 22. <u>Addressing:</u> Approved numbers or addresses shall be provided for all new and existing buildings in such a position as to be plainly visible and legible from the street or road fronting the property, as per El Dorado County Standard B-001.
- 23. <u>Landscaping:</u> The landscaping plan shall be reviewed by the Fire Department to ensure that trees, plants, and other landscaping features proposed to be adjacent to the Fire Apparatus Access roads, Fire and Life Safety equipment, and near address locations on buildings and monuments will not impede fire apparatus access or visual recognition.
- 24. <u>Improvement (Civil) Plans:</u> A Fire plan sheet shall be included in the improvement plans that shows or lists all requirements from the Fire Department as they relate to design of the subdivision. These requirements include, but are not limited to, Fire Lanes (and how they relate to allowed parking), Hydrants, Turning Radius of all turns, Slope % of Roads/Driveways, 2 Points of Egress for the Public and Emergency Personnel, EVA's as required, Road Widths, Gates, etc.
- 25. <u>Building and Fire Plans:</u> Building, fire sprinkler and fire alarm plans shall be reviewed and approved by the fire department prior to respective permit issuance. The plans shall provide the use and occupancy classification for each building for future comments in regards to fire sprinklers, fire alarms, exiting, occupant loads, and other fire and life safety features. There shall be a designated plan page that shows all Fire Lanes as required by the El Dorado County Regional Fire Protection Standard B-004 "No Parking-Fire Lane" and the fire code official.

Approval of subject project is conditioned on meeting the public safety and fire protection requirements of the County of El Dorado General Plan, which shall include provision of a financing mechanism shall include inclusion within, or annexation into, a Community Facilities District ("CFD")

established under the Mello-Roos Community Facilities Act of 1982 (Government Code § 53311 et seq.) established by the Diamond Springs / El Dorado Fire Protection District ("District") for the provision of public services permitted under Government Code § 53313, including fire suppression services, emergency medical services, fire prevention activities and other services (collectively "Public Services"), and as such, shall be subject to the special tax approved with the formation of such CFD with the Tract's inclusion or annexation into the CFD. 1 County of El Dorado General Plan sections Policy 5.1.2 and Policy 6.2.3.

Contact the front office at the Diamond Springs El Dorado Fire Protection District with any questions or to schedule inspections, tests (min. 2 working days in advance) at 530-626-3190. Thank you.

Sincerely,

DIAMOND SPRINGS EL DORADO FIRE PROTECTION DISTRICT

Deputy Chief / Fire Marshal

cc: El Dorado Irrigation District